

## BACnet<sup>®</sup> TESTING LABORATORIES

# INTERIM TEST SPECIFICATION

To Be Used with Test Package 16.1 Version 15 November 5, 2020

Approved by the BTL Working Group on October 15, 2020. Approved by the BTL Working Group Voting Members on November 5, 2020. Published on November 6, 2020.

BACnet is a registered trademark of ASHRAE. ASHRAE does not endorse, approve or test products for compliance with ASHRAE standards. Compliance of listed products to the requirements of ASHRAE Standard 135 is the responsibility of BACnet International. BTL is a registered trademark of BACnet International.

#### Foreward

The purpose of this document is to define interim tests and other test package changes made to support testing of a device that supports functionality currently not covered in the released BTL Test Package. This document shall be applied and used with BTL Test Package 16.1.

Vendors who are planning to submit a device for testing and who implement Protocol\_Revision 17 and higher, or which contain functionality not covered by the Official Test Package, should use this Interim Test document.

Please note that if the device contains functionality not yet covered by the official Test Package, nor by the Interim Tests document, development of new tests may be required for your device. Please contact the BTL Manager before submitting your device for testing to ensure you are aware of all tests that will need to be applied to your device.

The changes in this document are for interim use only and may or may not be used as documented here when the final changes are applied to the next Test Package revision. Devices tested using this interim test document shall be recalled for updated testing when the next revision of test package is released that includes the topics covered here.

In the following document, language to be added to existing clauses of ANSI/ASHRAE 135.1-2013 or any part of the Test Package 16.0 are indicated through the use of *italics*, while deletions are indicated by strikethrough. Where entirely new sections are proposed to be added, plain type is used throughout.

## **Table of Contents**

BTL CHE	CKLIST AND BTL TEST PLAN CHANGES	6
1.2	Testing Virtual Network Gateways	7
3.2	Analog Output Object	9
3.3	Analog Value Object	
3.6	Binary Output Object	11
3.7	Binary Value Object	12
3.15	Multi-state Output Object	13
3.16	Multi-state Value Object	14
3.24	Bitstring Value Object	15
3.25	CharacterString Value Object	16
3.26	Date Pattern Value Object	17
3.27	Date Value Object	
3.28	DateTime Pattern Value Object	19
3.29	DateTime Value Object	
3.30	Integer Value Object	21
3.31	Large Analog Value Object	
3.32	OctetString Value Object	23
3.33	Positive Integer Value Object	
3.34	Time Pattern Value Object	25
3.35	Time Value Object	
3.40	Access Door Object	27
3.54	Lighting Output Object	
3.55	Binary Lighting Output Object	
3.56	Network Port Object	
3.58	Elevator Group object	
3.59	Lift Object	
3.60	Escalator Object	
4.10	Data Sharing - Change Of Value - B	41
4.21	Data Sharing - WriteGroup - A	
4.27	Data Sharing - Life Safety View - A	43
4.28	Data Sharing - Life Safety Advanced View - A	44
4.29	Data Sharing - Life Safety Modify - A	45
4.30	Data Sharing - Life Safety Advanced Modify - A	46
4.31	Data Sharing - Access Control View - A	47
4.32	Data Sharing - Access Control Advanced View - A	
4.33	Data Sharing - Access Control Modify - A	49
4.34	Data Sharing - Life Safety Advanced Modify - A	
4.35	Data Sharing - Access Control User Configuration - A	51
4.37	Data Sharing - Access Control Site Configuration - A	53
4.40	Data Sharing - Access Control Access Door - A	55
4.41	Data Sharing - Access Control Credential Data Input - A	57
4.43	Data Sharing - Lighting Output - A	59
4.44	Data Sharing - Lighting Output Status - A	60
4.45	Data Sharing - Advanced Lighting Output - A	61
4.48	Data Sharing - Lighting Output Management - A	62
4.49	Data Sharing - Lighting View - A	63
4.50	Data Sharing - Lighting Advanced View - A	64
4.51	Data Sharing - Lighting Modify - A	65
4.52	Data Sharing - Lighting Advanced Modify - A	
5.27	Alarm and Event Management - Life Safety View Notifications - A	67
5.28	Alarm and Event Management - Life Safety Advanced View Notifications - A	
5.29	Alarm and Event Management - Life Safety View Modify - A	71
5.30	Alarm and Event Management - Life Safety Advanced View Modify - A	73

5.31	Alarm and Event Management - Access Control - A	75
5.32	Alarm and Event Management - Access Control - B	78
5.33	Alarm and Event Management - Access Controls Advanced View Notifications - A	82
5.34	Alarm and Event Management - Access Control View Modify - A	84
5.35	Alarm and Event Management - Access Control Advanced View Modify - A	85
8.16	Device Management – ReinitializeDevice - B	87
8.30	Device Management - Slave Proxy - B	88
9.*	Data Link Layer - All	89
9.4	BACnet/IP – Annex J - BBMD	90
9.9	Data Link Layer - IPv6	91
9.10	Data Link Layer - Secure Connect	95
10.4	Network Management - Connection Establishment - B	96
10.7	Network Management - BBMD Configuration - B	97
11.1	Gateway - Virtual Network - B	100
13.5	Audit Reporting - View - A	101
BTL SPECIFI	ED TESTS CHANGES	104
722 2 1 2 4 2	Natural Dart Object Tests	105
7 2 2 V/2	Network Port Object Lesis	105
7.3.2.A43.	Network Port non-volatility properties test	105
7.3.2.A43. 7.3.2 X/3	2 Network Fort non-volating properties test	105
7.5.2.745.	Dresent Value	106
		100
7.3.2.X45	Elevator Group Object Tests	106
7.3.2.X45.	Machine_Room_ID property linking with the Positive_Integer_Value Object	106
7.3.2.X45.2	2 Linking of Lift Objects under Group_Members property of the Elevator Group Object	107
7.3.2.X45.	3 Linking of Escalator Objects under Group_Members property of the Elevator Group Ob	ject
7 2 2 3 3 4 5		107
/.3.2.X45.4	Linking of Landing_Call_Control Property Test	10/
7.3.2.X46	Escalator Object Tests	108
7.3.2.X46.	Elevator_Group property of Escalator Object linking with Group_Members property of	
	Elevator Group Object	108
7.3.2.X46.2	2 Energy_Meter, Power_Mode and Operation_Direction Tracking Test	108
7.3.2.X46.	B Passenger_Alarm and Fault_Signals Tracking Test	109
7.3.2.X46.4	4 Escalator_Mode Tracking Test	110
7.3.2.X46.	6 Energy_Meter_Ref Property Test	111
7.3.2.X46.	7 CHANGE_OF_STATE for Passenger_Alarm (ConfirmedEventNotification)	111
7.3.2.X46.	8 CHANGE_OF_STATE for Passenger_Alarm (UnconfirmedEventNotification)	112
7 3 2 X47	Lift Object Tests	113
7 3 2 X47	Elevator Group property of Lift Object linking with Group Members property of Eleva	tor
/.5.2.247.	Group Object	113
732X47	Car Moving Direction and Car Assigned Direction Tracking Test	113
7.3.2.X47.	Car Door Status and Landing Door Status Tracking Test	115
7.3.2.X47	Car_Dool_Status and Landing_Dool_Status Hacking Test	115
7 3 2 X47	5 Passenger Alarm and Fault Signals Tracking Test	115
7 3 2 X47	Making Car Call Car Mode & Car Door Command Tracking Test	116
7 2 7 XA7	Assigned Landing Call and Registered Car Call Tracking Test	117
737X47.	Car Door Zone and Car Load Tracking Test	118
727X47.	Finergy Meter and Car Drive Status Tracking Test	110
7 2 7 XA7	Making Car Call and Registered Car Call Test	110 110
1.3.2.A41. 727V17	10 Maxing_Cal_Call and Registered_Cal_Call 1est	119 110
7 2 7 XA7	11 Anay Size of the Lift Object properties dased off car door Size	19 120
727X47.	<ul> <li>Landing_Dool_Status Tracks Cal_Dool_Status Test</li> <li>Highest Universal floor number linking to Car. Dosition and Next. Stonning, Electronomy</li> </ul>	erties
1.3.2.747.	1.5 Ingrest Oniversal noor number mixing to Cat_i osition and ivext_stopping_r1001 prop	120
7.3.2.X47	14 Highest Universal floor number linking to Assigned Landing Calls, Making Car Call	and
	Registered Car Call properties	121

7.3.2.X47. 7.3.2.X47. 7.3.2.X47.	<ul> <li>Energy_Meter_Ref Property Tests</li> <li>Higher_Deck and Lower_Deck Tests</li> <li>Linking of Assigned_Landing_Calls property of Lift Object to Landing_Calls property of Elevator Group</li> </ul>	122 122 of 123
8.4.X9 8.5.X9.15	CHANGE_OF_RELIABILITY Tests CHANGE_OF_RELIABILITY FAULT-to-FAULT transitions in FAULT_LISTED	124
8.4.X11	ACCESS_EVENT Test (ConfirmedEventNotification)	127
8.5.X11 ACC	CESS_EVENT Test (UnconfirmedEventNotification)	128
8.18 ReadRat	nge Service Initiation Tests	129
8.18.X1 Re	eading and Presenting Large List Properties	129
8.X AuditLog	gQuery Initiation Tests	129
8.X.1 Quer	ry and Present Audit Log Records By Source	129
8.X.2 Quer	ry and Present Audit Log Records By Target	130
8.X2	WriteGroup Service Initiation Tests	131
8.X2.1	Broadcasting to a Group of Channel Objects	131
9.18	ReadProperty Service Execution Tests	131
9.18.1	Positive ReadProperty Service Execution Tests	131
9.18.1.X5	ReadProperty of the Network Port Object using the Unknown Instance	131
12.X.	BACnet/IPv6 Functionality Tests	132
12.X.1	Common Tests	132
12.X.1.1	Execute Original-Unicast-NPDU	132
12.X.1.2 12.X.2 12.X.2.1 12.X.2.1	Execute Virtual-Address-Resolution IPv6 Normal Mode Tests Positive Tests Initiate Original-Broadcast-NPDU	133
12.X.2.1.2	Execute Original-Broadcast-NPDU	133
12.X.2.1.3	Execute Forwarded-NPDU	134
12.X.2.1.4	Execute Address-Resolution	134
12.X.2.1.5 12.X.2.2 12.X.2.2.1	Execute Forwarded-Address-Resolution Negative Tests Reject Register-Foreign-Device Reject Delete Foreign Davies Table Fatry	134 135 135
12.X.2.2.2	Reject Delete-Foreign-Device-Fable-Entry	135
12.X.2.2.3	Reject Distribute-Broadcast-To-Network	135
12.X.3	Foreign Device Tests	136
12.X.3.1	Positive Tests	136
12.X.3.1.1	Initiate Distribute-Broadcast-To-Network-NPDU	136
12.X.3.1.2	Execute Forwarded-NPDU	136
12.X.3.1.3	Execute Forwarded-Address-Resolution	136
12.X.3.2	Negative Tests	137
12.X.3.2.1	Ignores Original-Broadcast-NPDU	137
12.X.3.2.2	Ignore Address-Resolution	137
12.X.3.2.3	Reject Register-Foreign-Device	137
12.X.3.2.4	Reject Delete-Foreign-Device-Table-Entry	137
12.X.3.2.5	Reject Distribute-Broadcast-To-Network	138
12.X.4.1 12.X.4.1.1 12.X.4.1.2	Positive Tests Original-Broadcast-NPDU Forwarded-NPDU	138
12.X.4.1.3	Address-Resolution	140
12.X.4.1.4	Forwarded-Address-Resolution	141
12.X.4.1.5	Distribute-Broadcast-To-Network	141
12.X.4.2	Negative Tests	143
12.X.4.2.1	Reject Forwarded-NPDU	143

12.X.4.2.2	Reject Address-Resolution	143
12.X.4.2.3	Reject Forwarded-Address-Resolution	144
12.X.4.2.4	Reject Distribute-Broadcast-To-Network	144
12.X.4.3	Broadcast Distribution Table Operations	144
12.X.4.3.1	Verify writability of the BDT	144
12.X.5	Foreign Device Management Tests	144
12.X.5.1	Execute Register-Foreign-Device	145
12.X.5.2	Execute Delete-Foreign-Device-Table-Entry	145
12.X.5.3	Foreign Device Table Timer Operations	146
12.X.5.3.1	Non-Zero-Duration Foreign Device Table Timer Operations	146
12.X.5.3.2	Zero-Duration Foreign Device Timer Operations	146
12.X.5.4	Delete-Foreign-Device-Table-Entry For A Non-existent Entry	147
14.3	Broadcast Distribution Table Operations	147
14.3.X1	Write-BDT service is required to return Write-BDT-NAK	147
14.3.X2	Broadcast Distribution Table Holds at Least 5 Entries (via Write-Broadcast-Distributio	on-
	Table)	148
14.3.X3	Broadcast Distribution Table Holds at Least 5 Entries (via	
	BBMD_Broadcast_Distribution_Table)	148
14.6	Foreign Device Management	148
14.6.X1	Holds at Least 5 Foreign Device Registrations	149
14.6.X2	Negative Foreign Device Registration when FD_Supported is FALSE	149

### **BTL Checklist and BTL Test Plan Changes**

This section of the document contains interim changes to the BTL Checklist and the BTL Test Plan documents to support testing of products with functionality outside the scope of the official test plan.

This section is ordered the same as the BTL Checklist and BTL Test Plan documents to allow easy navigation of the material.

All test changes can be found in the next major section.

#### **1.2 Testing Virtual Network Gateways**

The BTL Test Package does not provide adequate direction on testing of virtual network gateways. These changes direct the tester to develop 2 separate Checklists, one for the functionality in the virtual router, and another for the superset of functionality that I supported in virtual devices.

#### **Checklist Changes**

[Modify clause 1 in the BTL Functionality Checklist]

#### **1** Introduction

The *BTL Functionality Checklist* identifies the testable options implemented by the IUT. The table is divided out into sections by functionality. In general, each section maps onto a BIBB, object type, or functional category. Each section has a Base Requirements option and if the BIBB, object type or functional category is supported by the IUT, this item must be selected. In addition, any other option in the section that has a Listing Code of R or BTL-R must be selected.

There are some items in the table that are already marked with an X in the 'Support' column. These are items that all BACnet devices must implement.

The Listing column indicates whether the option is required or not. The codes in the table are:

- R = Required. Items marked with this listing code are required for a listing if the IUT implements the associated BIBB, object type, or functional category.
- BTL-R = Required by BTL. Items marked with this listing code are required for a listing if the IUT implements the associated BIBB, object type, or functional category.
- C = Conditionally Required. Items marked with this listing code may be required for a listing if the IUT implements the associated BIBB, object type, or functional category. The conditions under which the item will be required are identified in a footnote in the Checklist table.
- BTL-C = Conditionally Required by BTL. Items marked with this listing code may be required for a listing if the IUT implements the associated BIBB, object type, or functional category. The conditions under which the item will be required are identified in a footnote in the Checklist table.
- S = Suggested. The BTL suggests that all IUTs implement this option if they implement the associated BIBB, object type, or functional category.
- O = Optional. Items marked with this listing code are optional.
- N = Not recommended. The BTL recommends against IUTs implementing this option due to possible interoperability or performance problems related with the option.

The 'Option' column names the functional item. For each item there is a corresponding item of the same name in the *BTL Test Plan*. The corresponding item in the *BTL Test Plan* provides a more detailed description of the option.

Once filled out, this document will be used to identify the tests to apply to the IUT. By relating the selected items in this table to items in the *BTL Test Plan*, the tester will have a list of all tests that must be applied to the IUT.

If the IUT supports GW-VN-B, then a separate BTL Checklist shall be filled out describing the functionality of the virtual devices. The virtual device checklist shall document all of the functionality that is supported in the virtual devices even if it cannot all be supported in a single virtual device.

#### **Test Plan Changes**

[ Add section 1.2 into BTL Test Plan ]

#### **1.2 Testing Virtual Network Gateways**

This test plan was developed to test a single BACnet device but BACnet virtual gateways are different from other BACnet devices in that they represent 2 or more devices: the virtual router and one or more virtual devices. The functionality of the virtual router device might be very different than the functionality of the virtual devices and thus warrants separate testing.

The Test Plan shall be applied to the virtual router based on its BTL Checklist and on a virtual device based on its BTL Checklist.

### 3.2 Analog Output Object

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.2.2 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

# 3.3 Analog Value Object

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.3.3 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

## **3.6 Binary Output Object**

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.6.2 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

# 3.7 Binary Value Object

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.7.5 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

## 3.15 Multi-state Output Object

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.15.2 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

## 3.16 Multi-state Value Object

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.16.4 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

### **3.24 Bitstring Value Object**

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.24.3 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

## **3.25** CharacterString Value Object

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.25.3 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

# 3.26 Date Pattern Value Object

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.26.3 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

# **3.27 Date Value Object**

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.27.3 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

## **3.28 DateTime Pattern Value Object**

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.28.3 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

## **3.29 DateTime Value Object**

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.29.3 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

## **3.30 Integer Value Object**

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.30.3 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

## 3.31 Large Analog Value Object

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.31.3 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

## **3.32 OctetString Value Object**

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.32.3 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

## **3.33 Positive Integer Value Object**

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.33.3 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

# 3.34 Time Pattern Value Object

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.34.3 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

## 3.35 Time Value Object

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.35.3 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

## 3.40 Access Door Object

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.40.2 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

## **3.54 Lighting Output Object**

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.54.2 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test		
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.
	Test Directives	
	Testing Hints	

## **3.55 Binary Lighting Output Object**

### **Checklist Changes**

None

### **Test Plan Changes**

[In BTL Test Plan, add entry into section 3.55.2 Supports Command Prioritization]

BTL - 7.3.1.X1 - Current_Command_Priority Tracking Test			
	<b>Test Conditionality</b>	Must be executed if the IUT claims Protocol_Revision 17 or higher.	
	Test Directives		
	Testing Hints		

## 3.56 Network Port Object

See Test Package addendum 16.1ai for interim Network Port object testing.

### 3.58 Elevator Group object

A device including an Elevator Group object must claim Protocol\_Revision 18 or higher and comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace Elevator Group Object section]

Listing	Option	
tor Group		
R	Base Requirements	
R	Supports Group Members property	
0	Supports Landing Call_Control property	
	Listing tor Group R R O	

#### **Test Plan Changes**

[In BTL Test Plan, replace section 3.58 Elevator Group Object]

#### **3.58** Elevator Group Object

#### 3.58.1 Base Requirements

The object contains Machine\_Room\_ID Property.

BTL - 7.3.2.X45.1 - Machine_Room_ID property linking with the Positive_Integer_Value Object			
	<b>Test Conditionality</b>	Must be executed.	
	<b>Test Directives</b>		
	Testing Hints		

#### 3.58.2 Supports Group\_Members Property

The object contains a Group\_Members Property.

BTL - 7.3.2.X45.2 - Linking of Lift Objects under Group\_Members property of the Elevator Group Object

	Test Conditionality	Must be executed if IUT supports Lift object.			
	Test Directives				
	Testing Hints				
BTL -	BTL - 7.3.2.X45.3 - Linking of Escalator Objects under Group Members property of the Elevator				
Group	Object				
	Test Conditionality	Must be executed if IUT supports Escalator object.			
	Test Directives				
	Testing Hints				

### 3.58.3 Supports Landing\_Call\_Control Property

The object contains a Landing\_Call\_Control Property.

BTL - 7.3.2.X45.4 - Linking of Landing_Call_Control Property Test			
	Test Conditionality	Must be executed.	
	Test Directives		
	Testing Hints		

### 3.59 Lift Object

A device including a Lift object must claim Protocol\_Revision 18 or higher and must comply with the following section.

#### **Checklist Changes**

[]	n BT	L Checklist,	add new	Lift section i	in existing 3]	

Support	Listing	Option
Lift	Object	
	R	Base Requirements
	S	Supports writable Out_Of_Service properties
	S	Supports Landing Door Status and Car Door Status properties
	0	Supports Making Car Call, and Register Car Call properties
	0	Supports BACnetARRAY Properties related to the doors of a car
	0	Supports Car_Position and Next_Stopping_Floor properties
	0	Supports Assigned Landing Calls, Making Car Call and Registered Car Call properties
	0	Supports Energy_Meter_Ref and Energy_Meter properties
	0	Supports Higher Deck and Lower Deck properties
	0	Supports Reliability Evaluation Inhibit property
	0	Supports Reliability Evaluation
	0	Supports CHANGE_OF_STATE event algorithm with Passenger_Alarm property
	0	Supports writable Assigned Landing Calls property
	0	Supports FAULT-to-FAULT transitions in FAULT_LISTED

#### **Test Plan Changes**

[In BTL Test Plan, replace section 3.59 Lift Object]

#### 3.59 Lift Object

#### 3.59.1 Base Requirements

Base requirements must be met by any IUT that can contain Lift objects.

BTL - 7.3.2.X47.1 - Elevator_Group property of Lift Object linking with Group_Members property of Elevator Group Object.		
	Test Conditionality	Must be executed.
	Test Directives	
	Testing Hints	

#### 3.59.2 Supports writable Out\_Of\_Service properties

The Out\_Of\_Service property in Lift objects contained in the IUT is either writable or can be modified by any other means.

BTL	BTL - 7.3.2.X43.3 - Out_Of_Service, Status_Flags, and Reliability test for an Object that does not			
conta	contain Present_Value			
	Test Conditionality	If this property is writable, this test must be executed.		
	Test Directives			
	Testing Hints			
BTL	- 7.3.2.X47.2 - Car_Mov	ing_Direction and Car_Assigned_Direction Tracking Test		
	Test Conditionality	If Out_Of_Service property is either writable or can be modified by other		
		means and if any of these properties are present, this test must be		
		executed.		
	Test Directives			
DTI	Testing Hints			
BIL	- /.3.2.X4/.3 - Car_Dool	<u>Status and Landing Door Status Tracking Test</u>		
	lest Conditionality	If Out_OI_Service property is either writable or can be modified by other		
		means and it any of these properties are present, this test must be		
	Test Directives			
	Test Directives			
BTL	- 7 3 2 X47 4 - Car Posi	tion and Next Stanning Floor Tracking Test		
DIL	Test Conditionality	If Out Of Service property is either writable or can be modified by other		
	Test Conditionanty	means and if any of these properties are present this test must be		
		executed.		
	Test Directives			
	Testing Hints			
BTL	BTL - 7.3.2.X47.5 - Passenger Alarm and Fault Signals Tracking Test			
	Test Conditionality	If Out Of Service property is either writable or can be modified by other		
		means and if any of these properties are present, this test must be		
		executed.		
	Test Directives			
	Testing Hints			
BTL	- 7.3.2.X47.6 - Making_	Car_Call, Car_Mode & Car_Door_Command Tracking Test		
	Test Conditionality	If Out_Of_Service property is either writable or can be modified by other		
		means and if any of these properties are present, this test must be		
		executed.		
	Test Directives			
DTI	Testing Hints			
BIL	- /.3.2.X4/./ - Assigned	Landing Call and Registered Car_Call Tracking Test		
	Test Conditionality	If Out_Of_Service property is either writable or can be modified by other		
		avecuted		
	Test Directives			
	Testing Hints			
BTL	BTL - 7 3 2 X47 8 - Car Door Zone and Car Load Tracking Test			
	Test Conditionality	If Out Of Service property is either writable or can be modified by other		
	2000 Conucionality	means and if any of these properties are present, this test must be		
		executed.		
	Test Directives			
	Testing Hints			
BTL	- 7.3.2.X47.9 - Energy N	Aeter and Car Drive Status Tracking Test		

Test Conditionality	If Out_Of_Service property is either writable or can be modified by other means and if any of these properties are present, this test must be executed.
Test Directives	
Testing Hints	

#### 3.59.3 Supports Making\_Car\_Call and Register\_Car\_Call Properties

Either of the Making\_Car\_Call, Register\_Car\_Call properties in at least one Lift object are present.

BTL	BTL - 7.3.2.X47.10 - Making_Car_Call and Registered_Car_Call Tests			
	Test Conditionality	This test must be executed if Making_Car_Call and Registered_Car_Call		
		properties are present.		
	Test Directives			
	Testing Hints			

#### 3.59.4 Supports BACnetARRAY Properties related to the doors of a car

BACnetARRAY properties related to the doors of a car are present in at least one Lift object.

BTL ·	BTL - 7.3.2.X47.11 - Array Size of the Lift Object properties based on car door size			
	<b>Test Conditionality</b> This test must be executed if any of the BACnetARRAY properties			
		Car_Door_Text, Assigned_Landing_Calls, Making_Car_Call,		
		Registered Car Call, Car Door Status, Car Door Command and		
		Landing_Door_Status are present.		
	Test Directives			
	Testing Hints			

#### 3.59.5 Supports Landing Door Status and Car Door Status Properties

The Landing\_Door\_Status property in at least one Lift object is present.

BTL - 7.3.2.X47.12 - Landing_Door_Status Tracks Car_Door_Status Test		
	Test Conditionality	This test must be executed if Landing_Door_Status property is present.
	Test Directives	
	Testing Hints	

#### 3.59.6 Supports Car\_Position and Next\_Stopping\_Floor Properties

Either of the Car\_Position, Next\_Stopping\_Floor property in at least one Lift object is present.

BTL - 7.3.2.X47.13 - Highest Universal floor number linking to Car_Position and			
Next_Stopping_Floor properties			
	Test Conditionality	This test must be executed if Car_Position and Next_Stopping_Floor properties are present. If any property is not present, the respective step shall be skipped	
	Test Directives		
	Testing Hints		
# 3.59.7 Supports Assigned\_Landing\_Calls, Making\_Car\_Call and Registered\_Car\_Call Properties

Either of the Assigned\_Landing\_Calls, Making\_Car\_Call and Register\_Car\_Call property in at least one Lift object is present.

BTL - 7.3.2.X47.14 Highest Universal floor number linking to Assigned_Landing_Calls,		
Making_Car_Call and Registered_Car_Call properties		
	<b>Test Conditionality</b> This test must be executed if Assigned Landing Calls,	
	-	Making Car Call and Registered Car Call properties are present. If any
	property is not present, the respective step shall be skipped	
	Test Directives	
	Testing Hints	

# 3.59.8 Supports Energy\_Meter\_Ref and Energy\_Meter Properties

The Energy\_Meter\_Ref and Energy\_Meter property in at least one Lift object is present.

BTL	BTL - 7.3.2.X47.15 Energy_Meter_Ref Property Tests		
	Test Conditionality	This test must be executed if Energy_Meter_Ref and Energy_Meter	
		property is present	
	Test Directives		
	Testing Hints		

# 3.59.9 Supports Higher\_Deck and Lower\_Deck Properties

The Higher\_Deck and Lower\_Deck properties in at least one Lift object is present.

BTL	BTL - 7.3.2.X47.16 Higher_Deck and Lower_Deck Tests		
Test Conditionality This test must be executed if Higher_Deck and Lower_Deck p		This test must be executed if Higher_Deck and Lower_Deck properties	
		are present	
	Test Directives		
	Testing Hints		

# 3.59.10 Supports Reliability\_Evaluation\_Inhibit Property

The IUT contains, or can be made to contain, a Reliability\_Evaluation\_Inhibit property that is configurable to a value of TRUE.

BTL	BTL - 7.3.1.X8.1 - Reliability_Evaluation_Inhibit Test		
Test Conditionality		If no object exists in the IUT for which fault conditions can be generated,	
		then this test shall be skipped.	
	Test Directives		
	Testing Hints		
BTL - 7.3.1.X8.2 - Reliability Evaluation Inhibit Summarization Test		_Evaluation_Inhibit Summarization Test	
	Test Conditionality	If no object exists in the IUT for which fault conditions can be	
		generated, then this test shall be skipped.	
	Test Directives		
	Testing Hints		

# 3.59.11 Supports Reliability Evaluation

The IUT contains, or can be made to contain, a Lift object that can generate ConfirmedEventNotifications and UnconfirmedEventNotifications with an Event\_Type of CHANGE\_OF\_RELIABILITY.

BTL	BTL - 8.4.X9.13 CHANGE_OF_RELIABILITY with FAULT_LISTED Algorithm		
(ConfirmedEventNotification)			
	Test Conditionality	This test must be executed	
	Test Directives		
	Testing Hints		
BTL	BTL - 8.5.X9.14 CHANGE OF RELIABILITY with FAULT LISTED Algorithm		
(Unc	(UnconfirmedEventNotification)		
	Test Conditionality This test must be executed		
	Test Directives		
	Testing Hints		

# 3.59.12 Supports CHANGE\_OF\_STATE event algorithm with Passenger Alarm property

Intrinsic event algorithm is supported using Passenger\_Alarm property in at least one Lift object.

BTL	BTL - 7.3.2.X46.8 CHANGE_OF_STATE for Passenger_Alarm (ConfirmedEventNotification)		
	<b>Test Conditionality</b> This test must be executed if the object under test supports		
		CHANGE_OF_STATE event algorithm with Passenger_Alarm property	
		writable or can be modified by any other means.	
	Test Directives		
	Testing Hints		
BTL - 7.3.2.X46.9 CHANGE OF STATE for Passenger Alarm (UnconfirmedEventNotificati			
BTL	- 7.3.2.X46.9 CHANGE	OF_STATE for Passenger_Alarm (UnconfirmedEventNotification)	
BTL	- 7.3.2.X46.9 CHANGE Test Conditionality	OF_STATE for Passenger_Alarm (UnconfirmedEventNotification) This test must be executed if the object under test supports	
BTL	- 7.3.2.X46.9 CHANGE Test Conditionality	OF_STATE for Passenger_Alarm (UnconfirmedEventNotification) This test must be executed if the object under test supports CHANGE_OF_STATE event algorithm with Passenger_Alarm property	
BTL	- 7.3.2.X46.9 CHANGE Test Conditionality	OF_STATE for Passenger_Alarm (UnconfirmedEventNotification) This test must be executed if the object under test supports CHANGE_OF_STATE event algorithm with Passenger_Alarm property writable or can be modified by any other means.	
BTL	- 7.3.2.X46.9 CHANGE Test Conditionality Test Directives	OF_STATE for Passenger_Alarm (UnconfirmedEventNotification) This test must be executed if the object under test supports CHANGE_OF_STATE event algorithm with Passenger_Alarm property writable or can be modified by any other means.	

# 3.59.13 Supports writable Assigned\_Landing\_Calls Property

The Assigned\_Landing\_Calls property is present in at least one Lift object.

BTL - 7.3.2.X47.17 - Linking of Assigned_Landing_Calls property of Lift Object to Landing_Calls		
property of Elevator Group		
	<b>Test Conditionality</b>	This test must be executed if Assigned_Landing_Calls is writable.
	Test Directives	
	Testing Hints	

# 3.59.14 Supports FAULT-to-FAULT transitions in FAULT\_LISTED

These requirements must be met by any IUT that can contain more than one element or different values in the Fault Signals property in any of its Lift objects.

BTL	- 8.5.X9.15 - C	HANGE_OF_RELIABILITY	FAULT-to-FAULT	transitions	in
FAU	LT_LISTED				
	Test Conditionality	Must be executed.			
	Test Directives				
	Testing Hints				

# **3.60 Escalator Object**

A device including an Escalator object must claim Protocol\_Revision 18 or higher and must comply with the following section.

# **Checklist Changes**

Support	Listing	Option
Esca	alator Obje	ct
	R	Base Requirements
	S	Supports writable Out_Of_Service properties
	S	Supports Escalator_Mode property
	Ο	Supports Energy_Meter_Ref property
	Ο	Supports CHANGE_OF_STATE event algorithm with Passenger_Alarm property
	Ο	Supports Reliability_Evaluation_Inhibit property
	0	Supports Reliability Evaluation
	0	Supports FAULT-to-FAULT transitions in FAULT_LISTED

[In BTL Checklist, replace Escalator Object section]

## **Test Plan Changes**

[In BTL Test Plan, replace section 3.60 Escalator Object]

## **3.60** Escalator Object

## **3.60.1 Base Requirements**

Base requirements must be met by any IUT that can contain Escalator objects.

BTL	- 7.3.2.X46.1 Elevator_	Group property of Escalator Object linking with Group_Members	
prope	property of Elevator Group Object		
	Test Conditionality	Must be executed.	
	<b>Test Directives</b>		
	Testing Hints		

## 3.60.2 Supports writable Out\_Of\_Service properties

The Out\_Of\_Service property in Escalator objects contained in the IUT is either writable or can be modified by any other means.

BTL	BTL - 7.3.2.X43.3 - Out_Of_Service, Status_Flags, and Reliability test for an Object that does not		
contain Present Value			
	<b>Test Conditionality</b> If this property is writable, this test must be executed.		
	Test Directives		
	Testing Hints		
BTL - 7.3.2.X46.2 - Energy Meter, Power Mode and Operation Direction Tracking Test			

	Test Conditionality	This test must be executed if Energy_Meter or Power_Mode properties
		are present.
	Test Directives	
	Testing Hints	
BTL	- 7.3.2.X46.3 - Passenger	-Alarm and Fault_Signals Tracking Test
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	
	Testing Hints	
BTL	- 7.3.2.X46.4 - Escalator	_Mode Tracking Test
	<b>Test Conditionality</b>	This test must be executed if Escalator Mode property is present.
	Test Directives	
	Testing Hints	

#### 3.60.3 Supports Escalator\_Mode Property

The Escalator\_Mode property in at least one Escalator object is present.

BTL - 7.3.2.X46.5 - Operation_Direction Tracks Escalator_Mode Test		
	Test ConditionalityMus	st be executed.
	Test Directives	
	Testing Hints	

# 3.60.4 Supports Energy\_Meter\_Ref Property

The Energy\_Meter\_Ref property in at least one Escalator object is present.

BTL - 7.3.2.X46.6 - Energy_Meter_Ref Property Test		
	Test Conditionality	This test must be executed if both Energy_Meter_Ref and Energy_Meter properties are present.
	Test Directives	
	Testing Hints	

# 3.60.5 Supports CHANGE\_OF\_STATE event algorithm with Passenger\_Alarm property

Intrinsic event algorithm is supported using Passenger\_Alarm property in at least one Escalator.

BTL	BTL - 7.3.2.X46.7 - CHANGE_OF_STATE for Passenger_Alarm (ConfirmedEventNotification)		
	<b>Test Conditionality</b> This test must be executed if the object under test supports		
		CHANGE_OF_STATE event algorithm with Passenger_Alarm property	
		writable or can be modified by any other means.	
	Test Directives		
	Testing Hints		
BTL - 7.3.2.X46.8 - CHANGE OF STATE for Passenger Alarm (UnconfirmedEventNotificat		E_OF_STATE for Passenger_Alarm (UnconfirmedEventNotification)	
	<b>Test Conditionality</b>	This test must be executed if the object under test supports	
		CHANGE_OF_STATE event algorithm with Passenger_Alarm property	
		writable or can be modified by any other means.	
	Test Directives		
	Testing Hints		

# 3.60.6 Supports Reliability\_Evaluation\_Inhibit Property

The IUT contains, or can be made to contain, a Reliability\_Evaluation\_Inhibit property that is configurable to a value of TRUE.

BTL	BTL - 7.3.1.X8.1 - Reliability_Evaluation_Inhibit Test		
	<b>Test Conditionality</b> If no object exists in the IUT for which fault conditions can be gene		
		then this test shall be skipped.	
	Test Directives		
	Testing Hints		
BTL	BTL - 7.3.1.X8.2 - Reliability Evaluation Inhibit Summarization Test		
	<b>Test Conditionality</b>	If no object exists in the IUT for which fault conditions can be generated,	
		then this test shall be skipped.	
	Test Directives		
	Testing Hints		

# 3.60.7 Supports Reliability Evaluation

The IUT contains, or can be made to contain, an Escalator object that can generate ConfirmedEventNotifications and UnconfirmedEventNotifications with an Event\_Type of CHANGE\_OF\_RELIABILITY.

BTL	BTL - 8.4.X9.13 CHANGE_OF_RELIABILITY with FAULT_LISTED Algorithm		
(Con	firmedEventNotification)		
	Test Conditionality This test must be executed		
	Test Directives		
	Testing Hints		
BTL	BTL - 8.5.X9.14 CHANGE OF RELIABILITY with FAULT LISTED Algorithm		
(Unc	(UnconfirmedEventNotification)		
	Test Conditionality This test must be executed		
	Test Directives		
	Testing Hints		

# 3.60.8 Supports FAULT-to-FAULT transitions in FAULT\_LISTED

These requirements must be met by any IUT that can contain more than one element or different values in the Fault\_Signals property in any of its Escalator objects.

BTL	- 8.5.X9.15 - C	HANGE_OF_RELIABILITY	FAULT-to-FAULT	transitions	in
FAU	LT_LISTED				
	Test Conditionality	Must be executed.			
	Test Directives				
	Testing Hints				

# 4.10 Data Sharing - Change Of Value - B

See Test Package addendum 16.1-misc1-section 4 for testing of DS-COV-B with Access Point and Credential Data Input objects.

# 4.21 Data Sharing - WriteGroup - A

Devices claiming support for Data Sharing - WriteGroup - A must comply with the following section.

# **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - WriteGroup - A]

Data	Data Sharing - WriteGroup - A		
	R	Base Requirements	

#### **Test Plan Changes**

[In BTL Test Plan, replace section 4.43 Data Sharing - WriteGroup - A]

# 4.21 Data Sharing - WriteGroup - A

#### **4.21.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	135.1-2013 - 8.X2.1 - Broadcasting to a Group of Channel Objects		
	Test Conditionality	Must be executed.	
	Test Directives		
	Testing Hints		

# 4.27 Data Sharing - Life Safety View - A

Devices claiming support for Data Sharing - Life Safety View - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checlist, replace section Data Sharing - Life Safety View - A]

Dat	Data Sharing - Life Safety View - A		
	R	Base Requirements	
	R	Supports DS-RP-A	

#### **Test Plan Changes**

[In BTL Test Plan replace section 4.27 Data Sharing - Life Safety View - A]

#### 4.27 Data Sharing - Life Safety View - A

#### **4.27.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1-	135.1-2013 - 8.18.3 - Reading and Presenting Properties		
	Test Conditionality	Must be executed if the IUT does not support DS-LSAV-A.	
	Test Directives	Repeat the test for each of the standard object types and associated	
		properties specified by DS-LSV-A.	
	Testing Hints		

## 4.27.2 Supports DS-RP-A

The IUT shall support DS-RP-A in order to read properties for presentation.

Verif	y Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-RP-A.
	Testing Hints	

# 4.28 Data Sharing - Life Safety Advanced View - A

Devices claiming support for Data Sharing - Life Safety Advanced View - A must comply with the following section.

## **Checklist Changes**

[In BTL Checklist, replace section DS-LSAV-A]

Dat	Data Sharing - Life Safety Advanced View - A		
	R	Base Requirements	
	R	Supports DS-RP-A	

#### **Test Plan Changes**

[In BTL Test Plan, replace 4.28 Data Sharing - Life Safety Advanced View - A]

# 4.28 Data Sharing - Life Safety Advanced View - A

#### 4.28.1 Base Requirements

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	135.1-2013 - 8.18.3 - Reading and Presenting Properties	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Repeat the test for <u>all</u> standard objects and properties identified in DS- LSAV-A.
		For properties that contain a CHOICE construct, the IUT shall be capable of reading and presenting each of the forms of the datatype as defined in the IUT's claimed protocol revision.
		Full accuracy presentation is not required throughout the IUT, but there should be at least one place provided by the IUT that allows the presentation of each property to be presented in such a way that the presentation requirements of DS-LSAV-A are met.
	Testing Hints	

# 4.28.2 Supports DS-RP-A

The IUT shall support DS-RP-A in order to read properties for presentation.

Verif	erify Checklist	
	Test Conditionality	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-RP-A.
	Testing Hints	

# 4.29 Data Sharing - Life Safety Modify - A

Devices claiming support for Data Sharing - Life Safety Modify - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Life Safety Modify - A]

Dat	Data Sharing - Life Safety Modify - A		
	R	Base Requirements	
	R	Supports DS-WP-A	

#### **Test Plan Changes**

[In BTL Test Plan, replace section 4.29 Data Sharing - Life Safety Modify - A]

# 4.29 Data Sharing - Life Safety Modify - A

#### **4.29.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	135.1-2013 - 8.22.4 - Accepting Input and Modifying Properties	
	Test Conditionality	Must be executed if the IUT does not support DS-LSAM-A.
	Test Directives	Repeat the test for <u>each</u> of the required object types listed in the BIBB
		definition.
		Repeat for <u>each</u> of the required properties listed in the BIBB definition,
		except for those properties which are commandable.
		Repeat the test for a variety of values that cover the range of values
		required by the "Minimum Writable Value Ranges" table in the DS-M-
		A BIBB definition.
	Testing Hints	
135.1	-2013 - 8.22.5 - Acceptin	g Input and Commanding/Relinquishing Properties
	<b>Test Conditionality</b>	Must be executed if the IUT does not support DS-LSAM-A.
	Test Directives	This test should be executed at priority 8 only, i.e. $PR_1 = 8$ .
	Testing Hints	

# 4.29.2 Supports DS-WP-A

The IUT shall support DS-WP-A in order to update properties modified by the user.

Verif	/erify Checklist	
	Test Conditionality Must be executed.	
	Test Directives	Verify that the IUT claims support for DS-WP-A.
	Testing Hints	

# 4.30 Data Sharing - Life Safety Advanced Modify - A

Devices claiming support for Data Sharing - Life Safety Advanced Modify - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Life Safety Advanced Modify - A]

Dat	Data Sharing - Life Safety Advanced Modify - A		
	R	Base Requirements	
	R	Supports DS-WP-A	

#### **Test Plan Changes**

[Replace Test Plan Entry 4.30 Data Sharing - Life Safety Advanced Modify - A]

## 4.30 Data Sharing - Life Safety Advanced Modify - A

#### **4.30.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	135.1-2013 - 8.22.4 - Accepting Input and Modifying Properties	
	Test Conditionality	Must be executed.
	Test Directives	Repeat the test for each of the required object types listed in the BIBB
		definition.
		Repeat for <u>each</u> of the required properties listed in the BIBB definition,
		except for those properties which are commandable.
		Repeat the test for a variety of values that cover the range of values
		required by the "Minimum Writable Value Ranges" table in the DS-M-
		A BIBB definition.
	Testing Hints	
135.1	135.1-2013 - 8.22.5 - Accepting Input and Commanding/Relinquishing Properties	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	This test should be executed at priority 8 only, i.e. $PR_1 = 8$ .
	Testing Hints	

## 4.30.2 Supports DS-WP-A

The IUT shall support DS-WP-A in order to update properties modified by the user.

Verif	erify Checklist	
	Test Conditionality Must be executed.	
	Test Directives	Verify that the IUT claims support for DS-WP-A.
	Testing Hints	

# 4.31 Data Sharing - Access Control View - A

Devices claiming support for Data Sharing - Access Control View - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Access Control View - A]

Dat	Data Sharing - Access Control View - A		
	R	Base Requirements	
	R	Supports DS-RP-A	

#### **Test Plan Changes**

[In BTL Test Plan, replace section 4.31 Data Sharing - Access Control View - A]

#### 4.31 Data Sharing - Access Control View - A

#### **4.31.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1-	135.1-2013 - 8.18.3 - Reading and Presenting Properties	
	Test Conditionality	Must be executed if the IUT does not support DS-ACAV-A.
	Test Directives	Repeat the test for each of the standard object types and associated
		properties specified by DS-ACV-A.
	Testing Hints	

## 4.31.2 Supports DS-RP-A

The IUT shall support DS-RP-A in order to read properties for presentation.

Verif	Verify Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-RP-A.
	Testing Hints	

# 4.32 Data Sharing - Access Control Advanced View - A

Devices claiming support for Data Sharing - Access Control Advanced View - A must comply with the following section.

## **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Access Control Advanced View - A]

Dat	Data Sharing - Access Control Advanced View - A		
	R	Base Requirements	
	R	Supports DS-RP-A	

#### **Test Plans Changes**

[In BTL Test Plan, replace section 4.32 Data Sharing - Access Control Advanced View - A]

# 4.32 Data Sharing - Access Control Advanced View - A

#### 4.32.1 Base Requirements

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1-2013 - 8.18.3 - Reading	and Presenting Properties
Test Conditionality	Must be executed.

Test Conditionality	Must be executed.
Test Directives	Repeat the test for <u>all</u> standard objects and properties identified in DS-
	ACAV-A.
	For properties that contain a CHOICE construct, the IUT shall be
	capable of reading and presenting each of the forms of the datatype as
	defined in the IUT's claimed protocol revision.
	Full accuracy presentation is not required throughout the IUT, but there
	should be at least one place provided by the IUT that allows the
	presentation of each property to be presented in such a way that the
	presentation requirements of DS-ACAV-A are met.
Testing Hints	

## 4.32.2 Supports DS-RP-A

The IUT shall support DS-RP-A in order to read properties for presentation.

Verify	y Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-RP-A.
	Testing Hints	

# 4.33 Data Sharing - Access Control Modify - A

Devices claiming support for Data Sharing - Access Control Modify - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Access Control Modify - A]

Dat	Data Sharing - Access Control Modify - A		
	R	Base Requirements	
	R	Supports DS-WP-A	

#### **Test Plans Changes**

[In BTL Test Plan, replace section 4.32 Data Sharing - Access Control Advanced View - A]

# 4.33 Data Sharing - Access Control Modify - A

#### **4.33.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	135.1-2013 - 8.22.4 - Accepting Input and Modifying Properties		
	Test Conditionality	Must be executed if the IUT does not support DS-ACAM-A.	
	Test Directives	Repeat the test for each of the required object types listed in the BIBB	
		definition.	
		Repeat for <u>each</u> of the required properties listed in the BIBB definition, except for those properties which are commandable.	
		Repeat the test for a variety of values that cover the range of values	
		required by the "Minimum Writable Value Ranges" table in the DS-M-	
		A BIBB definition.	
	Testing Hints		
135.1	135.1-2013 - 8.22.5 - Accepting Input and Commanding/Relinquishing Properties		
	Test Conditionality	Must be executed if the IUT does not support DS-ACAM-A.	
	Test Directives	This test should be executed at priority 8 only, i.e. $PR_1 = 8$ .	
	Testing Hints		

## 4.33.2 Supports DS-WP-A

The IUT shall support DS-WP-A in order to update properties modified by the user.

Verif	y Checklist	
	Test Conditionality	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-WP-A.
	Testing Hints	

# 4.34 Data Sharing - Life Safety Advanced Modify - A

Devices claiming support for Data Sharing - Access Control Advanced Modify - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Access Control Advanced Modify - A]

Data Sharing - Access Control Advanced Modify - A		
	R	Base Requirements
	R	Supports DS-WP-A

#### **Test Plan Changes**

[In BTL Test Plan, replace section 4.34 Data Sharing - Life Safety Advanced Modify - A]

## 4.34 Data Sharing - Life Safety Advanced Modify - A

#### **4.34.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	35.1-2013 - 8.22.4 - Accepting Input and Modifying Properties	
	Test Conditionality	Must be executed.
	Test Directives	Repeat the test for <u>each</u> of the required object types listed in the BIBB definition.
		Repeat for <u>each</u> of the required properties listed in the BIBB definition, except for those properties which are commandable.
		Repeat the test for a variety of values that cover the range of values
		A BIBB definition.
	Testing Hints	
135.1	-2013 - 8.22.5 - Acceptin	g Input and Commanding/Relinquishing Properties
	Test Conditionality	Must be executed.
	Test Directives	This test should be executed at priority 8 only, i.e. $PR_1 = 8$ .
	Testing Hints	

# 4.34.2 Supports DS-WP-A

The IUT shall support DS-WP-A in order to update properties modified by the user.

Verify	y Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-WP-A.
	Testing Hints	

# 4.35 Data Sharing - Access Control User Configuration - A

Devices claiming support for Data Sharing - Access Control User Configuration - A must comply with the following section.

## **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Access Control User Configuration - A]

Dat	Data Sharing - Access Control User Configuration - A		
	R	Base Requirements	
	R	Supports DS-RP-A	
	R	Supports DS-WP-A	
	R	Supports DM-OCD-A	

## **Test Plan Changes**

[In BTL Test Plan, replace section 4.35 Data Sharing - Access Control User Configuration - A]

# 4.35 Data Sharing - Access Control User Configuration - A

#### **4.35.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1-	135.1-2013 - 8.18.3 - Reading and Presenting Properties	
	Test Conditionality	Must be executed.
	Test Directives	Repeat the test for <u>each</u> of the standard object types and associated
		properties specified by DS-ACUC-A.
	Testing Hints	
135.1-	-2013 - 8.22.4 - Acceptin	g Input and Modifying Properties
	Test Conditionality	Must be executed.
	<b>Test Directives</b>	Repeat the test for each of the required object types listed in the BIBB
		definition.
		Repeat for each of the required properties listed in the BIBB definition,
		except for those properties which are commandable.
		Repeat the test for a variety of values that cover the range of values
		required by the "Minimum Writable Value Ranges" table in the DS-M-
		A BIBB definition.
	Testing Hints	
135.1-	135.1-2013 - 8.22.5 - Accepting Input and Commanding/Relinquishing Properties	
	<b>Test Conditionality</b>	Must be executed.
	<b>Test Directives</b>	This test should be executed at priority 8 only, i.e. $PR_1 = 8$ .
	Testing Hints	

## 4.35.2 Supports DS-RP-A

The IUT shall support DS-RP-A in order to read properties of Access Control objects.

Verify Checklist

<b>Test Conditionality</b>	Must be executed.
Test Directives	Verify that the IUT claims support for DS-RP-A.
Testing Hints	

# 4.35.3 Supports DS-WP-A

The IUT shall support DS-WP-A in order to update properties modified by the user.

Verif	/erify Checklist	
	Test Conditionality	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-WP-A.
	Testing Hints	

# 4.35.2 Supports DM-OCD-A

The IUT shall support DM-OCD-A in order to create and delete Access Control objects.

## Verify Checklist

<b>Test Conditionality</b>	Must be executed.
Test Directives	Verify that the IUT claims support for DM-OCD-A, and that all object
	types required by DS-ACUC-A are claimed within DM-OCD-A.
Testing Hints	

# 4.37 Data Sharing - Access Control Site Configuration - A

Devices claiming support for Data Sharing - Access Control Site Configuration - A must comply with the following section.

## **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Access Control Site Configuration - A]

Dat	Data Sharing - Access Control Site Configuration - A		
	R	Base Requirements	
	R	Supports DS-RP-A	
	R	Supports DS-WP-A	
	R	Supports DM-OCD-A	

## **Test Plan Changes**

[In BTL Test Plan, replace section 4.37 Data Sharing - Access Control Site Configuration - A]

# 4.37 Data Sharing - Access Control Site Configuration - A

#### 4.37.1 Base Requirements

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	5.1-2013 - 8.18.3 - Reading and Presenting Properties	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Repeat the test for each of the standard object types and associated
		properties specified by DS-ACSC-A.
	Testing Hints	
135.1	-2013 - 8.22.4 - Acceptin	g Input and Modifying Properties
	Test Conditionality	Must be executed.
	Test Directives	Repeat the test for each of the required object types listed in the BIBB
		definition.
		Repeat for <u>each</u> of the required properties listed in the BIBB definition,
		except for those properties which are commandable.
		Repeat the test for a variety of values that cover the range of values
		required by the "Minimum Writable Value Ranges" table in the DS-M-
		A BIBB definition.
	Testing Hints	
135.1-2013 - 8.22.5 - Accepting		g Input and Commanding/Relinquishing Properties
	Test Conditionality	Must be executed.
	<b>Test Directives</b>	This test should be executed at priority 8 only, i.e. $PR_1 = 8$ .
	Testing Hints	

#### 4.37.2 Supports DS-RP-A

The IUT shall support DS-RP-A in order to read properties of Access Control objects.

Verif	Verify Checklist		
	Test Conditionality	Must be executed.	
	Test Directives	Verify that the IUT claims support for DS-RP-A.	
	Testing Hints		

# 4.37.3 Supports DS-WP-A

The IUT shall support DS-WP-A in order to update properties modified by the user.

Verify	Verify Checklist	
	Test Conditionality	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-WP-A.
	Testing Hints	

# 4.37.2 Supports DM-OCD-A

The IUT shall support DM-OCD-A in order to create and delete Access Control objects.

Verif	y Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DM-OCD-A, and that all object
		types required by DS-ACSC-A are claimed within DM-OCD-A.
	Testing Hints	

# 4.40 Data Sharing - Access Control Access Door - A

Devices claiming support for Data Sharing - Access Control Access Door - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Access Control Access Door - A]

Dat	Data Sharing - Access Control Access Door - A		
	R	Base Requirements	
	R	Supports DS-RP-A	
	R	Supports DS-WP-A	
	•		

#### **Test Plan Changes**

[In BTL Test Plan, replace section 4.40 Data Sharing - Access Control Access Door - A]

#### 4.40 Data Sharing - Access Control Access Door - A

#### **4.40.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1-	135.1-2013 - 8.18.3 - Reading and Presenting Properties		
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives	Repeat the test for <u>each</u> of the standard object types and associated	
		properties specified by DS-ACAD-A.	
	<b>Testing Hints</b>		
135.1-	-2013 - 8.22.4 - Acceptin	g Input and Modifying Properties	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives	Repeat the test for each of the required object types listed in the BIBB	
		definition.	
		Repeat for <u>each</u> of the required properties listed in the BIBB definition,	
		except for those properties which are commandable.	
		Repeat the test for a variety of values that cover the range of values	
		required by the "Minimum Writable Value Ranges" table in the DS-M-	
		A BIBB definition.	
	Testing Hints		
135.1-2013 - 8.22.5 - Accepting Input and Commanding/Relinquishing Properties		g Input and Commanding/Relinquishing Properties	
	Test Conditionality	Must be executed.	
	Test Directives	This test should be executed at priority 8 only, i.e. $PR_1 = 8$ .	
	<b>Testing Hints</b>		

# 4.40.2 Supports DS-RP-A

The IUT shall support DS-RP-A in order to read properties of Access Door objects.

Verify	ify Checklist	
	<b>Test Conditionality</b>	Must be executed.

	Test Directives	Verify that the IUT claims support for DS-RP-A.
	Testing Hints	

# 4.40.3 Supports DS-WP-A

The IUT shall support DS-WP-A in order to update Access Door properties modified by the user.

 Chitehinge	
Test Conditionality	Must be executed.
Test Directives	Verify that the IUT claims support for DS-WP-A.
Testing Hints	

٦

# 4.41 Data Sharing - Access Control Credential Data Input - A

Devices claiming support for Data Sharing - Access Control Credential Data Input - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Access Control Credential Data Input - A]

Dat	Data Sharing - Access Control Credential Data Input - A		
	R	Base Requirements	
	R	Supports DS-RP-A	
	R	Supports DS-WP-A	
	R	Supports DS-COV-A	

# **Test Plan Changes**

[In BTL Test Plan, replace section 4.41 Data Sharing - Access Control Credential Data Input - A]

# 4.41 Data Sharing - Access Control Credential Data Input - A

#### 4.41.1 Base Requirements

Base requirements must be met by any IUT claiming conformance to this BIBB.

-		
135.1	5.1-2013 - 8.18.3 - Reading and Presenting Properties	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Repeat the test for <u>each</u> of the standard object types and associated
		properties specified by DS-ACCDI-A.
	Testing Hints	
135.1	-2013 - 8.22.4 - Acceptin	g Input and Modifying Properties
	Test Conditionality	Must be executed.
	Test Directives	Repeat the test for each of the required object types listed in the BIBB
		definition.
		Repeat for <u>each</u> of the required properties listed in the BIBB definition,
		except for those properties which are commandable.
		Repeat the test for a variety of values that cover the range of values
		required by the "Minimum Writable Value Ranges" table in the DS-M-
		A BIBB definition.
	Testing Hints	
135.1	-2013 - 8.22.5 - Acceptin	g Input and Commanding/Relinquishing Properties
	Test Conditionality	Must be executed.
	Test Directives	This test should be executed at priority 8 only, i.e. $PR_1 = 8$ .
	Testing Hints	

# 4.41.2 Supports DS-RP-A

The IUT shall support DS-RP-A in order to read properties of Credential Data Input objects.

Verify Checklist		
	Test Conditionality	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-RP-A.
	Testing Hints	

# 4.41.3 Supports DS-WP-A

The IUT shall support DS-WP-A in order to update Credential Data Input properties modified by the user.

Verify	y Checklist	
	Test Conditionality	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-WP-A.
	Testing Hints	

# 4.41.4 Supports DS-COV-A

The IUT shall support DS-COV-A in order to receives COV notifications for Credential Data Input objects.

Verif	y Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-COV-A, and that Credential
		Data Input is claimed within DM-COV-A.
	Testing Hints	

# 4.43 Data Sharing - Lighting Output - A

Devices claiming support for Data Sharing - Lighting Output - A must comply with the following section.

# **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Lighting Output - A]

Data Sharing - Lighting Output - A		
	R	Base Requirements
	R	Supports DS-WP-A

#### **Test Plan Changes**

[In BTL Test Plan, replace section 4.43 Data Sharing - Lighting Output - A]

# 4.43 Data Sharing - Lighting Output - A

#### **4.43.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	135.1-2013 - 8.22.1 - Writing Non-Array Properties		
	<b>Test Conditionality</b>	Must be executed if the IUT does not support DS-ALO-A.	
	Test Directives	Repeat the test for each of the object types listed in the BIBB, writing to	
		the Present_Value property.	
	Testing Hints		

## 4.43.2 Supports DS-WP-A

The IUT shall support DS-WP-A in order to control objects.

Verif	Verify Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-WP-A.
	Testing Hints	

# 4.44 Data Sharing - Lighting Output Status - A

Devices claiming support for Data Sharing - Lighting Output Status - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Lighting Output Status - A]

Dat	Data Sharing - Lighting Output Status - A		
	R	Base Requirements	
	R	Supports DS-RP-A	

#### **Test Plan Changes**

[In BTL Test Plan, replace section 4.44 Data Sharing - Lighting Output Status - A]

## 4.44 Data Sharing - Lighting Output Status - A

#### **4.44.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	135.1-2013 - 8.18.1 - Reading Non-Array Properties		
	<b>Test Conditionality</b>		
	Test Directives	Repeat the test for each of the object types listed in the BIBB, reading the Present_Value and Egress_Active properties from the objects types as required by the BIBB.	
	Testing Hints		

# 4.44.2 Supports DS-RP-A

The IUT shall support DS-RP-A in order to retrieve property values from lighting objects.

Verif	y Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-RP-A, and claims the ability to
		read non-array properties, Enumerated, Unsigned, and REAL properties.
	Testing Hints	

# 4.45 Data Sharing - Advanced Lighting Output - A

Devices claiming support for Data Sharing - Advanced Lighting Output - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Advanced Lighting Output - A]

Data Sharing - Advanced Lighting Output - A		
	R	Base Requirements
	R	Supports DS-WP-A

#### **Test Plan Changes**

[In BTL Test Plan, replace section 4.45 Data Sharing - Advanced Lighting Output - A]

## 4.45 Data Sharing - Advanced Lighting Output - A

#### **4.45.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	135.1-2013 - 8.22.1 - Writing Non-Array Properties		
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives	Repeat the test for each property of each of the object types listed in the	
		BIBB, except those that are required to be read-only by the standard.	
	Testing Hints		

## 4.45.2 Supports DS-WP-A

The IUT shall support DS-WP-A in order to control objects.

Verif	ify Checklist		
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives	Verify that the IUT claims support for DS-WP-A.	
	Testing Hints		

# 4.48 Data Sharing - Lighting Output Management - A

Devices claiming support for Data Sharing - Lighting Output Management - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Lighting Output Management - A]

Data Sharing - Lighting Output Management - A		
	R	Base Requirements
	R	Supports DM-OCD-A

#### **Test Plan Changes**

[In BTL Test Plan, replace section 4.48 Data Sharing - Lighting Output Management - A]

# 4.48 Data Sharing - Lighting Output Management - A

#### 4.48.1 Base Requirements

Base requirements must be met by any IUT claiming conformance to this BIBB. There are no base requirements tests for this section.

# 4.48.2 Supports DM-OCD-A

The IUT shall support DM-OCD-A in order to create and delete Access Control objects.

Verif	y Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DM-OCD-A, and that all object types required by DS-LOM-A are claimed within DM-OCD-A.
	Testing Hints	

# 4.49 Data Sharing - Lighting View - A

Devices claiming support for Data Sharing - Lighting View - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Lighting View - A]

Dat	Data Sharing - Lighting View - A		
	R	Base Requirements	
	R	Supports DS-RP-A	

#### **Test Plan Changes**

[In BTL Test Plan, replace section 4.49 Data Sharing - Lighting View - A]

## 4.49 Data Sharing - Lighting View - A

#### **4.49.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1-	135.1-2013 - 8.18.3 - Reading and Presenting Properties		
	Test Conditionality	Must be executed if the IUT does not support DS-LAV-A.	
	Test Directives	Repeat the test for each of the standard object types and associated	
		properties specified by DS-LV-A.	
	Testing Hints		

## 4.49.2 Supports DS-RP-A

The IUT shall support DS-RP-A in order to read properties for presentation.

Verif	y Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-RP-A.
	Testing Hints	

# 4.50 Data Sharing - Lighting Advanced View - A

Devices claiming support for Data Sharing - Lighting Advanced View - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Lighting Advanced View - A]

Dat	Data Sharing - Lighting Advanced View - A		
	R	Base Requirements	
	R	Supports DS-RP-A	

#### **Test Plan Changes**

[In BTL Test Plan, replace section 4.50 Data Sharing - Lighting Advanced View - A]

# 4.50 Data Sharing - Lighting Advanced View - A

#### 4.50.1 Base Requirements

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	135.1-2013 - 8.18.3 - Reading and Presenting Properties		
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives	Repeat the test for <u>all</u> standard objects and properties identified in DS-	
		LAV-A.	
		For properties that contain a CHOICE construct, the IUT shall be	
		capable of reading and presenting each of the forms of the datatype as	
		defined in the IUT's claimed protocol revision.	
		Full accuracy presentation is not required throughout the IUT, but there	
		should be at least one place provided by the IUT that allows the	
		presentation of each property to be presented in such a way that the	
		presentation requirements of DS-LAV-A are met.	
	<b>Testing Hints</b>		

## 4.50.2 Supports DS-RP-A

The IUT shall support DS-RP-A in order to read properties for presentation.

Verif	fy Checklist		
	Test Conditionality	Must be executed.	
	Test Directives	Verify that the IUT claims support for DS-RP-A.	
	Testing Hints		

# 4.51 Data Sharing - Lighting Modify - A

Devices claiming support for Data Sharing - Lighting Modify - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Lighting Modify - A]

Dat	Data Sharing - Lighting Modify - A		
	R	Base Requirements	
	R	Supports DS-WP-A	

#### **Test Plan Changes**

[In BTL Test Plan, replace section 4.51 Data Sharing - Lighting Modify - A]

# 4.51 Data Sharing - Lighting Modify - A

## **4.51.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	135.1-2013 - 8.22.4 - Accepting Input and Modifying Properties	
	<b>Test Conditionality</b>	Must be executed if the IUT does not support DS-LAM-A.
	Test Directives	Repeat the test for each of the required object types listed in the BIBB
		definition.
		Repeat for <u>each</u> of the required properties listed in the BIBB definition,
		except for those properties which are commandable.
		Repeat the test for a variety of values that cover the range of values
		required by the "Minimum Writable Value Ranges" table in the DS-M-
		A BIBB definition.
	Testing Hints	
135.1	-2013 - 8.22.5 - Acceptin	g Input and Commanding/Relinquishing Properties
	<b>Test Conditionality</b>	Must be executed if the IUT does not support DS-LAM-A.
	Test Directives	This test should be executed at priority 8 only, i.e. $PR_1 = 8$ .
	Testing Hints	

## 4.51.2 Supports DS-WP-A

The IUT shall support DS-WP-A in order to update properties modified by the user.

Verif	Verify Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-WP-A.
	Testing Hints	

# 4.52 Data Sharing - Lighting Advanced Modify - A

Devices claiming support for Data Sharing - Lighting Advanced Modify - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Data Sharing - Lighting Advanced Modify - A]

Dat	Data Sharing - Lighting Advanced Modify - A		
	R	Base Requirements	
	R	Supports DS-WP-A	

#### **Test Plan Changes**

[In BTL Test Plan, replace section 4.52 Data Sharing - Lighting Advanced Modify - A]

# 4.52 Data Sharing - Lighting Advanced Modify - A

#### **4.52.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	135.1-2013 - 8.22.4 - Accepting Input and Modifying Properties	
	Test Conditionality	Must be executed.
	Test Directives	Repeat the test for each of the required object types listed in the BIBB
		definition.
		Repeat for <u>each</u> of the required properties listed in the BIBB definition,
		except for those properties which are commandable.
		Repeat the test for a variety of values that cover the range of values
		required by the "Minimum Writable Value Ranges" table in the DS-M-
		A BIBB definition.
	Testing Hints	
135.1	-2013 - 8.22.5 - Acceptin	g Input and Commanding/Relinquishing Properties
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	This test should be executed at priority 8 only, i.e. $PR_1 = 8$ .
	Testing Hints	

## 4.52.2 Supports DS-WP-A

The IUT shall support DS-WP-A in order to update properties modified by the user.

Verif	ify Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-WP-A.
	Testing Hints	

# 5.27 Alarm and Event Management - Life Safety View Notifications - A

Devices claiming support for Alarm and Event Management - Life Safety View Notification - A must comply with the following section.

#### Checklist Changes

[In BTL Checklist, replace section Alarm and Event Management - Life Safety View Notifications - A]

Alarm and Event Management - Life Safety View Notifications - A		
	R	Base Requirements
	R	Supports AE-N-A
	R	Supports AE-LS-A

#### **Test Plan Changes**

[In BTL Test Plan, replace section 5.27 Alarm and Event Management - Life Safety View Notifications - A]

#### 5.27 Alarm and Event Management - Life Safety View Notifications - A

#### **5.27.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

BTL ·	BTL - 9.4.5 - ConfirmedEventNotification Simple Presentation		
	Test Conditionality	Must be executed.	
	Test Directives	Repeat the test for CHANGE_OF_LIFE_SAFETY, and each of the transitions defined for that event type.	
		Repeat the test for FAULT_LIFE_SAFETY.	
		Execute at least once with a Message_Text 32 or more characters in	
		length.	
	Testing Hints		
135.1-2013 - 9.5.1 - UnconfirmedEventNotification Simple Presentation		nedEventNotification Simple Presentation	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints	Repeat the test for CHANGE_OF_LIFE_SAFETY, and each of the	
		transitions defined for that event type.	
		Repeat the test for FAULT_LIFE_SAFETY.	
		Execute at least once with a Message_Text 32 or more characters in	
		length.	

## 5.27.2 Supports AE-N-A

The IUT shall support AE-N-A in order to receive and display event notifications.

#### Verify Checklist

verny	Checknist	
	<b>Test Conditionality</b>	Must be executed.
	<b>Test Directives</b>	Verify that the IUT claims support for AE-N-A.

**Testing Hints** 

# 5.27.3 Supports AE-LS-A

The IUT shall support AE-LS-A in order to silence / unsilence life safety objects.

## Verify Checklist

vern,		
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for AE-LS-A.
	Testing Hints	

# **5.28** Alarm and Event Management - Life Safety Advanced View Notifications - A

Devices claiming support for Alarm and Event Management - Life Safety Advanced View Notifications - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Alarm and Event Management - Life Safety Advanced View Notifications - A]

Alarm and Event Management - Life Safety Advanced View Notifications - A		
	R	Base Requirements
	R	Supports AE-AVN-A
	R	Supports AE-LS-A

# **Test Plan Changes**

[In BTL Test Plan, replace section 5.28 Alarm and Event Management - Life Safety Advanced View Notifications - A]

#### 5.28 Alarm and Event Management - Life Safety Advanced View Notifications - A

#### 5.28.1 Base Requirements

Base requirements must be met by any IUT claiming conformance to this BIBB.

BTL	BTL - 9.4.6 - ConfirmedEventNotification Full Presentation	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Repeat the test for CHANGE_OF_LIFE_SAFETY, and each of the transitions defined for that event type. Repeat the test for FAULT_LIFE_SAFETY. Execute at least once with a Message_Text 256 or more characters in
	<b>T</b> (* <b>T</b> (	length.
	Testing Hints	
135.1	135.1-2013 - 9.5.2 - UnconfirmedEventNotification Full Presentation	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	
	Testing Hints	Repeat the test for CHANGE_OF_LIFE_SAFETY, and each of the transitions defined for that event type.
		Repeat the test for FAULT_LIFE_SAFETY.
		Execute at least once with a Message_Text 256 or more characters in length.

# 5.28.2 Supports AE-AVN-A

The IUT shall support AE-AVN-A in order to receive and display standard event notifications for most standard object types.

Verify Checklist		
	Test Conditionality	Must be executed.
	Test Directives	Verify that the IUT claims support for AE-AVN-A.
	Testing Hints	

# 5.28.3 Supports AE-LS-A

The IUT shall support AE-LS-A in order to silence / unsilence life safety objects.

Verif	ify Checklist		
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives	Verify that the IUT claims support for AE-LS-A.	
	Testing Hints		

# 5.29 Alarm and Event Management - Life Safety View Modify - A

Devices claiming support for Alarm and Event Management - Life Safety View Modify - A must comply with the following section.

## **Checklist Changes**

[In BTL Checklist, replace section Alarm and Event Management - Life Safety View Modify - A]

Alarm and Event Management - Life Safety View Modify - A				
	R	Base Requirements		
	R	Supports DS-RP-A		
	R	Supports DS-WP-A		
	R	Supports AE-VM-A		

#### **Test Plan Changes**

[In BTL Test Plan, replace section 5.29 Alarm and Event Management - Life Safety View Modify - A]

## 5.29 Alarm and Event Management - Life Safety View Modify - A

#### **5.29.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	135.1-2013 - 8.18.3 - Reading and Presenting Properties		
	Test Conditionality	Must be executed if AE-LSAVM-A is not supported.	
	Test Directives	Repeat the test for each standard object capable of generating	
		CHANGE_OF_LIFE_SAFETY events, reading and displaying the	
		pAlarmValues and pLifeSafetyAlarmValues properties.	
		Repeat the test for each standard object capable of using the	
		FAULT_LIFE_SAFETY algorithm, reading and displaying the	
		pFaultValues property.	
	Testing Hints		
135.1	135.1-2013 - 8.22.4 - Accepting Input and Modifying Properties		
	Test Conditionality	Must be executed if AE-LSAVM-A is not supported.	
	Test Directives	Repeat the test for each standard object capable of generating	
		CHANGE_OF_LIFE_SAFETY events, reading and displaying the	
		pAlarmValues and pLifeSafetyAlarmValues properties.	
		Repeat the test for each standard object capable of using the	
		FAULT_LIFE_SAFETY algorithm, reading and displaying the	
		pFaultValues property.	
	Testing Hints		

## 5.29.2 Supports DS-RP-A

The IUT shall support DS-RP-A in order to read properties for presentation.

Verif	rify Checklist			
	<b>Test Conditionality</b>	Must be executed.		
Test Directives	Verify that the IUT claims support for DS-RP-A.			
-----------------	---			
Testing Hints				

## 5.29.3 Supports DS-WP-A

The IUT shall support DS-WP-A in order to update properties modified by the user.

Verify Checklist		
	Test Conditionality	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-WP-A.
	Testing Hints	

## 5.29.4 Supports AE-VM-A

The IUT shall support AE-VM-A in order to facilitate configuration of alarm parameters by the user.

Verify Checklist		
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for AE-VM-A.
	Testing Hints	

## 5.30 Alarm and Event Management - Life Safety Advanced View Modify - A

Devices claiming support for Alarm and Event Management - Life Safety Advanced Modify - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Alarm and Event Management - Life Safety Advanced View Modify - A]

Ala	Alarm and Event Management - Life Safety Advanced View Modify - A		
	R	Base Requirements	
	R	Supports DS-RP-A	
	R	Supports DS-WP-A	
	R	Supports DM-OCD-A	
	R	Supports AE-AVM-A	

#### **Test Plan Changes**

[In BTL Test Plan, replace section 5.30 Alarm and Event Management - Life Safety Advanced View Modify - A]

#### 5.30 Alarm and Event Management - Life Safety Advanced View Modify - A

#### **5.30.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	135.1-2013 - 8.18.3 - Reading and Presenting Properties	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	
	Testing Hints	Repeat the test for each standard event generating object type which can
		generate CHANGE_OF_LIFE_SAFETY event notifications, or use the
		FAULT_LIFE_SAFETY algorithm.
135.1	-2013 - 8.22.4 - Acceptin	g Input and Modifying Properties
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	
	Testing Hints	Repeat the test for each standard event generating object type which can
	-	generate CHANGE_OF_LIFE_SAFETY event notifications, or use the
		FAULT_LIFE_SAFETY algorithm.

#### **5.30.2 Supports DS-RP-A**

The IUT shall support DS-RP-A in order to read properties for presentation.

Verif	y Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-RP-A.
	Testing Hints	

## 5.30.3 Supports DS-WP-A

The IUT shall support DS-WP-A in order to update properties modified by the user.

Verif	y Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-WP-A.
	Testing Hints	

## 5.30.4 Supports DM-OCD-A

The IUT shall support DM-OCD-A in order to facilitate creation and deletion of life safety objects.

Verif	y Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DM-OCD-A and that all object types required by DS-LSAVM-A are claimed within DM-OCD-A.
	Testing Hints	

#### 5.30.5 Supports AE-AVM-A

The IUT shall support AE-AVM-A in order to facilitate configuration of alarm parameters by the user.

Verify	y Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for AE-AVM-A.
	Testing Hints	

## 5.31 Alarm and Event Management - Access Control - A

Devices claiming support for Alarm and Event Management - Access Control - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Alarm and Event Management - Access Control - A]

Ala	Alarm and Event Management - Access Control - A		
	R	Base Requirements	
	R	Executes ConfirmedEventNotifications	
	R	Executes UnconfirmedEventNotifications	
	R	Processes intrinsically generated notifications	
	R	Processes algorithmically generated notifications	
	R	Processes event notifications with timestamps of the BACnetDateTime form	
	R	Processes event notifications with timestamps of the Time form	
	R	Processes event notifications with timestamps of the Sequence Number form	
	R	Supports AE-ACK-A	

#### **Test Plan Changes**

[In BTL Test Plan, replace section 5.31 Alarm and Event Management - Access Control - A]

#### 5.31 Alarm and Event Management - Access Control - A

#### **5.31.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

BTL	BTL - 9.4.X1 - Unsupported Message Text Character Set ConfirmedEventNotification Test		
	<b>Test Conditionality</b>	If the IUT supports all character sets, this test shall be skipped.	
	Test Directives		
	Testing Hints		
BTL	BTL - 9.5.X1 - Unsupported Message Text Character Set UnconfirmedEventNotification Test		
	<b>Test Conditionality</b>	If the IUT supports all character sets, this test shall be skipped.	
	Test Directives		
	Testing Hints		

#### 5.31.2 Executes ConfirmedEventNotifications

The IUT is capable of executing ConfirmedEventNotifications with an Event Type of ACCESS\_EVENT. This functionality will be covered by the testing of the individual algorithms.

No Sj	No Specific Test	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT's EPICS claims that it supports the
		ConfirmedEventNotification service.
	Testing Hints	

## 5.31.3 Executes UnconfirmedEventNotifications

The IUT is capable of executing UnconfirmedEventNotifications with an Event Type of ACCESS\_EVENT. There are currently no tests defined for this functional item.

No S	pecific Test	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT's EPICS claims that it supports the
		UnconfirmedEventNotification service.
	Testing Hints	

#### **5.31.4 Processes Intrinsically Generated Notifications**

The IUT is capable of executing ConfirmedEventNotifications with an Event Type of ACCESS\_EVENT that reference an object type other than Event Enrollment.

135.1-2013 - 9.4.1 - ConfirmedEventNotification Using the Time Form of the 'Timestamp' Parameter and Conveying a Text Message, 135.1-2013 - 9.4.2 - ConfirmedEventNotification Using the DateTime Form of the 'Timestamp'

Parameter and no Text Message, or 135.1.2013 0.4.3 ConfirmedEventNotification Using the Sequence Number Form of the

135.1-2013 - 9.4.3 - ConfirmedEventNotification Using the Sequence Number Form of the 'Timestamp' Parameter and no Text Message

Test Conditionality	At least one of the tests must be executed with the Event Object Identifier referencing a BACnet object other than an Event Enrollment object.
Test Directives	Execute using an event type of ACCESS_EVENT.
Testing Hints	

#### 5.31.5 Processes Algorithmically Generated Notifications

The IUT is capable of executing ConfirmedEventNotifications with an Event Type of ACCESS\_EVENT that reference an Event Enrollment object.

r		
135.1	-2013 - 9.4.1 - Confirme	dEventNotification Using the Time Form of the 'Timestamp'
Para	meter and Conveying a	Fext Message,
135.1	-2013 - 9.4.2 - Confirme	dEventNotification Using the DateTime Form of the 'Timestamp'
Para	meter and no Text Messa	age, or
135.1	-2013 - 9.4.3 - Confirme	dEventNotification Using the Sequence Number Form of the
'Time	estamp' Parameter and	no Text Message
	Test Conditionality	At least one of the tests must be executed with the Event Object
		Identifier referencing an Event Enrollment object.
	Test Directives	Execute using an event type of ACCESS_EVENT.
	Testing Hints	

#### 5.31.6 Processes Event Notifications with Timestamps of the BACnetDateTime Form

The IUT is capable of executing ConfirmedEventNotifications that contain a timestamp of the BACnetDateTime form.

135.1	-2013 - 9.4.2 - Confirme	dEventNotification Using the DateTime Form of the 'Timestamp'
Para	meter and no Text Messa	nge
	Test Conditionality	Must be executed.
	Test Directives	Execute using an event type of ACCESS_EVENT.
	Testing Hints	

#### 5.31.7 Processes Event Notifications with Timestamps of the Time Form

135.1 Parai	-2013 - 9.4.1 - Confirmed meter and Conveying a T	dEventNotification Using the Time Form of the 'Timestamp' Text Message
	Test Conditionality	Must be executed.
	Test Directives	Execute using an event type of ACCESS EVENT.
	Testing Hints	

The IUT is capable of executing ConfirmedEventNotifications that contain a timestamp of the Time form.

#### 5.31.8 Processes Event Notifications with Timestamps of the Sequence Number Form

The IUT is capable of executing ConfirmedEventNotifications that contain a timestamp of the Sequence Number form.

135.1	-2013 - 9.4.3 - Confirme	dEventNotification Using the Sequence Number Form of the
'Time	estamp' Parameter and 1	no Text Message
	Test Conditionality	Must be executed.
	Test Directives	Execute using an event type of ACCESS_EVENT.
	Testing Hints	

## 5.31.9 Supports AE-ACK-A

The IUT must support AE-ACK-A if it claims support for AE-AC-A.

Veri	fy Checklist	
	Test Conditionality	Must be executed.
	Test Directives	Verify that the IUT claims support for AE-ACK-A in the
		Checklist.
	Testing Hints	
BTI	- 8.1 - ACKNOWLEDGEALARM S	SERVICE INITIATION TESTS
	TEST CONDITIONALITY	Must be executed.
	Test Directives	Execute using an event type of ACCESS_EVENT.
		Execute once to acknowledge a
		ConfirmedEventNotification, and again to acknowledge an
		UnconfirmedEventNotification.
	TESTING HINTS	

# 5.32 Alarm and Event Management - Access Control - B

Devices claiming support for Alarm and Event Management - Access Control - B must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Alarm and Event Management - Access Control - B]

R Base Requirements	
R Supports AE-INFO-B	
R Supports the Notification Class Object	
C <sup>1</sup> Supports AE-ACK-B	
C <sup>2</sup> Implements intrinsic alarming	
C <sup>2</sup> Supports the Event Enrollment object	
C <sup>3</sup> Generates Event Notifications with Timestamps of the Bacnet	DateTime Form
C <sup>3</sup> Generates Event Notifications with Timestamps of the Time Fo	orm
C <sup>3</sup> Generates Event Notifications with Timestamps of the Sequence	e Number Form
O Supports Event Message Texts Property	
O Supports Event Message Texts Config Property	
<sup>1</sup> Required if EventNotifications with service parameter AckRequired =	True can be issued.
<sup>2</sup> At least one of these options must be supported to claim support for this	s BIBB.
<sup>3</sup> At least one of these options must be supported to claim support for this	s BIBB.

#### **Test Plan Changes**

[In BTL Test Plan, replace section 5.32 Alarm and Event management - Access Control - B]

#### 5.32 Alarm and Event Management - Access Control - B

#### **5.32.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

VER	IFY Checklist	
	Test Conditionality	Must be executed.
	Test Directives	Verify that the IUT supports Access Point objects.
	Testing Hints	
BTL	- 7.3.1.10.2 - Event_Ena	ble Tests for TO_NORMAL only Algorithms
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Apply to an object which generates ACCESS_EVENT notifications.
	Testing Hints	
135.1	-2013 - 7.3.1.12 - Notify	_Type Test
	Test Conditionality	If the IUT cannot be configured to meet the 135.1-2013 configuration
		requirements then this test shall be skipped.
	Test Directives	Apply to an object which generates ACCESS_EVENT notifications.
	Testing Hints	
BTL	- 7.3.1.X9.1 - Event_De	tection_Enable Inhibits Event Generation
	<b>Test Conditionality</b>	If Protocol_Revision < 13, then this test shall be skipped.

Test Directives	Apply to an object which generates ACCESS_EVENT notifications.
Testing Hints	
7.3.1.X9.2 - Event_Det	ection_Enable Inhibits FAULT
Test Conditionality	If Protocol_Revision < 13, then this test shall be skipped.
Test Directives	Apply to an object which generates ACCESS_EVENT notifications.
Testing Hints	
7.3.1.X6.1 - Event_Alg	orithm_Inhibit Test
Test Conditionality	If the IUT has no object which generates ACCESS_EVENT
	notifications in which the Event_Algorithm_Inhibit property is present
	and does not support the Event Algorithm Inhibit Ref property.
<b>Test Directives</b>	Apply to an object which generates ACCESS_EVENT notifications.
Testing Hints	
7.3.1.X7.1 - Event_Alg	orithm_Inhibit_Ref Test
Test Conditionality	If the IUT has no object which generates ACCESS_EVENT
	notifications in which the Event_Algorithm_Inhibit_Ref property is
	present, this test shall be skipped.
<b>Test Directives</b>	
Testing Hints	
7.3.1.X7.2 - Event_Alg	orithm_Inhibit Writable Test
Test Conditionality	If the IUT has no object which generates ACCESS_EVENT
	notifications in which the Event_Algorithm_Inhibit_Ref property is
	absent or can be made uninitialized, this test shall be skipped.
<b>Test Directives</b>	
Testing Hints	
	Test Directives Testing Hints 7.3.1.X9.2 - Event_Det Test Conditionality Test Directives Testing Hints 7.3.1.X6.1 - Event_Alg Test Conditionality Test Directives Testing Hints 7.3.1.X7.1 - Event_Alg Test Conditionality Test Directives Testing Hints 7.3.1.X7.2 - Event_Alg Test Conditionality Test Directives Test Directives Testing Hints 7.3.1.X7.2 - Event_Alg Test Directives Test Directives

#### **5.32.2 Supports AE-INFO-B**

The IUT must support AE-INFO-B if it claims support for AE-AC-B.

Verify Checklist

 /	
Test Conditionality	Must be executed.
Test Directives	Verify that the IUT claims support for AE-INFO-B in the Checklist.
Testing Hints	

#### 5.32.3 Supports the Notification Class Object

The IUT supports the Notification Class object in order to send notifications.

|--|

10111	IY Checkhist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for the Notification Class Object in the Checklist.
	Testing Hints	

#### 5.32.4 Supports AE-ACK-B

The IUT supports AE-ACK-B in order to execute the AcknowledgeAlarm Service Service if the IUT is able to send event-notifications with service parameter AckRequired = True.

Verif	y Checklist	
	Test Conditionality	Must be executed.
	Test Directives	Verify that the IUT claims support for AE-ACK-B in the Checklist.
	Testing Hints	

## 5.32.5 Supports Intrinsic Alarming

The IUT contains, or can be made to contain, an Access Point object that can generate ConfirmedEventNotifications and UnconfirmedEventNotifications.

135.1	135.1-2013 - 8.4.X11 - ACCESS EVENT Test (ConfirmedEventNotification)		
	Test ConditionalityMust be executed unless IUT only supports read-only Recipier properties and does not claim Notification Forwarder objects.		
	Test Directives	Apply to an Access Point object.	
	Testing Hints		
135.1	135.1-2013 - 8.5.X11 - ACCESS EVENT Test (UnconfirmedEventNotification)		
	Test Conditionality	Must be executed.	
	Test Directives	Apply to an Access Point object.	
	Testing Hints		

#### 5.32.6 Supports the Event Enrollment object

The IUT contains, or can be made to contain an Event Enrollment object that can generate ACCESS\_EVENT notifications.

135.1	135.1-2013 - 8.4.X11 - ACCESS EVENT Test (ConfirmedEventNotification)	
	Test Conditionality	Must be executed unless IUT only supports read-only Recipient_List
		properties and does not claim Notification Forwarder objects.
	Test Directives	Apply to an Event Enrollment object.
	Testing Hints	
135.1	135.1-2013 - 8.5.X11 - ACCESS EVENT Test (UnconfirmedEventNotification)	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Apply to an Event Enrollment object.
	Testing Hints	

# **5.32.7** Generates Event Notifications with Timestamps of the BacnetDateTime Form

The IUT generates ACCESS\_EVENT notifications with the Time Stamp parameter taking the BACnetDateTime form.

135.1	135.1-2013 - 8.4.X11 - ACCESS_EVENT Test (ConfirmedEventNotification)	
	Test Conditionality Must be executed.	
	Test Directives	Execute the test with the IUT configured to generate ACCESS_EVENT
		notifications with timestamps of the BACnetDateTime form.
	Testing Hints	
135.1	135.1-2013 - 8.5.X11 - ACCESS EVENT Test (UnconfirmedEventNotification)	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Execute the test with the IUT configured to generate ACCESS_EVENT
		notifications with timestamps of the BACnetDateTime form.

#### 5.32.8 Generates Event Notifications with Timestamps of the Time Form

The IUT generates ACCESS\_EVENT notifications with the Time Stamp parameter taking the Time form.

135.1	135.1-2013 - 8.4.X11 - ACCESS_EVENT Test (ConfirmedEventNotification)		
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives	Execute the test with the IUT configured to generate ACCESS_EVENT notifications with timestamps of the Time form.	
	Testing Hints		

135.1-2013 - 8.5.X11 - ACCESS_EVENT Test (UnconfirmedEventNotification)		
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Execute the test with the IUT configured to generate ACCESS_EVENT notifications with timestamps of the Time form.
	Testing Hints	

# **5.32.9** Generates Event Notifications with Timestamps of the Sequence Number Form

The IUT generates ACCESS\_EVENT notifications with the Time Stamp parameter taking the Sequence Number form.

135.1	135.1-2013 - 8.4.X11 - ACCESS_EVENT Test (ConfirmedEventNotification)	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Execute the test with the IUT configured to generate ACCESS_EVENT
		notifications with timestamps of the Sequence Number form.
	Testing Hints	
135.1	135.1-2013 - 8.5.X11 - ACCESS EVENT Test (UnconfirmedEventNotification)	
	Test Conditionality	Must be executed.
	Test Directives	Execute the test with the IUT configured to generate ACCESS_EVENT
		notifications with timestamps of the Sequence Number form.
	Testing Hints	

#### 5.32.10 Supports Event\_Message\_Texts Property

The IUT supports Access Point objects that support the Event\_Message\_Texts property.

BTL	BTL - 7.3.1.X4 - Event_Message_Texts Tests	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Apply to an object which generates ACCESS_EVENT notifications that
		contains an Event_Message_Texts property.
	Testing Hints	

#### 5.32.11 Supports Event\_Message\_Texts\_Config Property

The IUT supports Access Point objects that support the Event\_Message\_Texts\_Config property.

BTL	BTL - 7.3.1.X5 - Event_Message_Texts_Config Test	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Apply to an object which generates ACCESS_EVENT notifications.
		Repeat for each supported transition type (TO_OFFNORMAL,
		TO_FAULT, TO_NORMAL). Different objects may be selected for
		different transitions.
	Testing Hints	

# **5.33** Alarm and Event Management - Access Controls Advanced View Notifications - A

Devices claiming support for Alarm and Event Management - Access Control Advanced View Notifications - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Alarm and Event Management - Access Control Advanced View Notifications - A]

Ala	Alarm and Event Management - Access Control Advanced View Notifications - A		
	R	Base Requirements	
	R	Supports AE-AVN-A	
	R	Supports AE-AC-A	

#### **Test Plan Changes**

[In BTL Test Plan, replace section 5.33 Alarm and Event Management - Access Controls Advanced View Notifications - A]

#### 5.33 Alarm and Event Management - Access Controls Advanced View Notifications - A

#### **5.33.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

BTL	BTL - 9.4.6 - ConfirmedEventNotification Full Presentation	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Repeat the test for ACCESS_EVENT, and each of the transitions
		defined for that event type.
		Execute at least once with a Message_Text 256 or more characters in
		length.
	Testing Hints	
135.1	135.1-2013 - 9.5.2 - UnconfirmedEventNotification Full Presentation	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	
	Testing Hints	Repeat the test for ACCESS_EVENT, and each of the transitions
	_	defined for that event type.
		Execute at least once with a Message_Text 256 or more characters in
		length.

#### 5.33.2 Supports AE-AVN-A

The IUT must support AE-AVN-A in order to receive and display standard event notifications for most standard object types.

Verify	y Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for AE-AVN-A in the Checklist.

**Testing Hints** 

## 5.33.3 Supports AE-AC-A

The IUT must support AE-AC-A if it claims support for AE-ACAVN-A.

#### Verify Checklist

ing Cheekiise	y enternist	
Test Conditionality	Must be executed.	
Test Directives	Verify that the IUT claims support for AE-AC-A in the Checklist.	
Testing Hints		

# 5.34 Alarm and Event Management - Access Control View Modify - A

Devices claiming support for Alarm and Event Management - Access Control View Modify - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Alarm and Event Management - Access Control View Modify - A]

Alarm and Event Management - Access Control View Modify - A		
	R	Base Requirements
	R	Supports AE-VM-A

#### **Test Plan Changes**

[In BTL Test Plan, replace section 5.34 Alarm and Event Management - Access Control View Modify - A]

#### 5.34 Alarm and Event Management - Access Control View Modify - A

#### 5.34.1 Base Requirements

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	135.1-2013 - 8.18.3 - Reading and Presenting Properties	
	Test Conditionality	Must be executed if AE-ACAVM-A is not supported.
	Test Directives	
	Testing Hints	Repeat the test for each standard object capable of generating
		ACCESS_EVENT events, reading and displaying the pAccessEvents
		and pAccessEventTime properties.
135.1	135.1-2013 - 8.22.4 - Accepting Input and Modifying Properties	
	Test Conditionality	Must be executed if AE-ACAVM-A is not supported.
	Test Directives	
	Testing Hints	Repeat the test for each standard object capable of generating
		ACCESS_EVENT events, reading and displaying the pAccessEvents
		and pAccessEventTime properties.

#### 5.34.2 Supports AE-VM-A

The IUT shall support AE-VM-A in order to facilitate configuration of alarm parameters by the user.

Verif	Verify Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for AE-VM-A.
	Testing Hints	

## 5.35 Alarm and Event Management - Access Control Advanced View Modify - A

Devices claiming support for Alarm and Event Management - Access Control Advanced View Modify - A must comply with the following section.

#### **Checklist Changes**

[In BTL Checklist, replace section Alarm and Event Management - Access Control Advanced View Modify - A]

Ala	Alarm and Event Management - Access Control Advanced View Modify - A		
	R	Base Requirements	
	R	Supports DS-RP-A	
	R	Supports DS-WP-A	
	R	Supports D-OCD-A	
	R	Supports AE-AVM-A	

#### **Test Plan Changes**

[In BTL Test Plan, replace section 5.35 Alarm and Event Management - Access Control Advanced View Modify - A]

#### 5.35 Alarm and Event Management - Access Control Advanced View Modify - A

#### **5.35.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	135.1-2013 - 8.18.3 - Reading and Presenting Properties		
	Test Conditionality	Must be executed.	
	Test Directives		
	Testing Hints	Repeat the test for each standard event generating object type which can	
		generate ACCESS_EVENT event notifications.	
135.1	135.1-2013 - 8.22.4 - Accepting Input and Modifying Properties		
	Test Conditionality	Must be executed.	
	Test Directives		
	Testing Hints	Repeat the test for each standard event generating object type which can	
	_	generate ACCESS_EVENT event notifications.	

#### **5.35.2 Supports DS-RP-A**

The IUT shall support DS-RP-A in order to read properties for presentation.

Verify Checklist		
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-RP-A.
	Testing Hints	

## 5.35.3 Supports DS-WP-A

The IUT shall support DS-WP-A in order to update properties modified by the user.

Verif	y Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DS-WP-A.
	Testing Hints	

## 5.35.4 Supports DM-OCD-A

The IUT shall support DM-OCD-A in order to facilitate creation and deletion of life safety objects.

Verif	y Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for DM-OCD-A and that all object types required by DS-ACAVM-A are claimed within DM-OCD-A
	Testing Hints	types required by DS-ACA VIV-A are claimed within DIV-OCD-A.

#### 5.35.5 Supports AE-AVM-A

The IUT shall support AE-AVM-A in order to facilitate configuration of alarm parameters by the user.

Verify	y Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for AE-AVM-A.
	Testing Hints	

# 8.16 Device Management – ReinitializeDevice - B

See Test Package addendum 16.1ai for testing of ReinitializeDevice with Network Port objects.

## 8.30 Device Management – Slave Proxy - B

Devices claiming support for Device Management - Slave Proxy - B must claim support for Protocol\_Revision 4 or higher and comply with the following section.

Addendum 135-2001*a* added MS/TP slave proxy functionality. This document makes needed changes in the BTL Test Package to claim the associated BIBB DM-SP-B.

These changes are not contained in any SSPC proposal.

#### **Checklist Changes**

[In BTL Checklist, replace Device Management - Slave Proxy - B section]

Device Management - Slave Proxy - B		
	R	Base Requirements
	0	Supports Automatic Slave Address Binding

#### **Test Plan Changes**

[In BTL Test Plan, replace section 8.30 Device Management - Slave Proxy - B]

#### 8.30 Device Management - Slave Proxy - B

#### **8.30.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

135.1	135.1-2013 - 13.5.1 Manual Slave Binding Test	
	<b>Test Conditionality</b>	Must be executed.
	<b>Test Directives</b>	
	Testing Hints	
135.1-2013 - 13.5.3 Proxy Test		
	Test Conditionality	Must be executed.
	Test Directives	
	Testing Hints	

#### 8.30.2 Supports Automatic Slave Address Binding

The IUT support automatic slave address binding.

135.1-2013 - 13.5.2 Automatic Slave Discovery Test		
	Test Conditionality	Must be executed.
	Test Directives	
	Testing Hints	

# 9.\* Data Link Layer - All

See Test Package addendum 16.1ai for changes related to Data Link Layer testing with Network Port objects.

## 9.4 BACnet/IP – Annex J - BBMD

The operation and manipulation of Broadcast Distribution Tables in devices claiming Protocol\_Revision 17 or higher is performed through operations on a Network Port object for each supported port.

#### **Test Plan Changes**

[In BTL Test Plan, add test to end of Base Requirements for BACnet/IP - Annex J - BBMD]

#### 9.4 BACnet/IP - Annex J - BBMD

#### 9.4.1 Base Requirements

The IUT acts, or can be made to act, as a BBMD device.

These base requirements must be met by any IUT that claims to support the Annex J BACnet/IP BBMD functionality.

• •	•	
BTL – 14.3.X1 - Write-BDT service is required to return Write-BDT-NAK		
	Test Conditionality	Must be executed in all devices claiming Protocol_Revision >= 17.
	<b>Test Directives</b>	
	Testing Hints	

## 9.9 Data Link Layer - IPv6

Addendum 135-2012aj added support for IPv6 in Protocol\_Revision 18.

These changes are based on, and diverge from, SSPC proposal CLB-029.

#### **Checklist Changes**

[In BTL Checklist, replace Data Link Layer - IPv6 section]

Support	Listing	Option	
Data Link Layer –IPv6			
	R	Base Requirements	
	$C^1$	Is able to operate in Normal mode	
	$C^1$	Is able to operate in Foreign mode	
	$C^2$	Is able to operate in BBMD mode	
	<sup>1</sup> Required if the device does not support BBMD mode.		
	<sup>2</sup> Requ	ired if the device does not support Foreign mode.	

#### **Test Plan Changes**

[In BTL Test Plan, replace section 9.9 Data Link Layer - IPv6]

#### 9.9 Data Link Layer - IPv6

#### 9.9.1 Base Requirements

Base requirements must be met by any IUT that can act, or can be made to act, as a BACnet/IPv6 device in a non-BBMD mode.

BTL	BTL - 12.X.1.1 - Execute Original-Unicast-NPDU	
	<b>Test Conditionality</b>	Must be executed.
	<b>Test Directives</b>	
	Testing Hints	
BTL - 12.X.1.2 - Execute Virtual-Address-Resolution		
	Test Conditionality	Must be executed.
	Test Directives	
	Testing Hints	

#### 9.9.2 Is Able to Operate in Normal Mode

The IUT supports NORMAL mode.

BTL - 12.X.2.1.1 - Initiate Original-Broadcast-NPDU		
	<b>Test Conditionality</b>	If the IUT does not initiate broadcasts, this test shall be skipped.

	Test Directives		
	Testing Hints		
BTL ·	- 12.X.2.1.2 - Execute O	riginal-Broadcast-NPDU	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL ·	- 12.X.2.1.3 - Execute Fo	orwarded-NPDU	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL ·	- 12.X.2.1.4 - Execute A	ddress-Resolution	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL - 12.X.2.1.5 - Execute Forwarded-Address-Resolution			
	Test Conditionality	Must be executed.	
	Test Directives		
	Testing Hints		
BTL ·	BTL - 12.X.2.2.1 - Reject Register-Foreign-Device		
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL ·	- 12.X.2.2.2 - Reject Del	ete-Foreign-Device-Table-Entry	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL ·	BTL - 12.X.2.2.3 - Reject Distribute-Broadcast-To-Network		
	Test Conditionality	Must be executed.	
	<b>Test Directives</b>		
	Testing Hints		

## 9.9.3 Is Able to Operate in Foreign Mode

The IUT supports FOREIGN mode.

BTL	BTL - 12.X.3.1.1 - Initiate Distribute-Broadcast-To-Network-NPDU		
	Test Conditionality	Must be executed.	
	Test Directives		
	Testing Hints		
BTL	- 12.X.3.1.2 - Execute Fo	orwarded-NPDU	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL	BTL - 12.X.3.1.3 - Execute Forwarded-Address-Resolution		
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL	- 12.X.3.2.1 - Ignores Or	riginal-Broadcast-NPDU	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL	BTL - 12.X.3.2.2 - Ignore Address-Resolution		
	<b>Test Conditionality</b>	Must be executed.	

	Test Directives	
	Testing Hints	
BTL ·	- 12.X.3.2.3 - Reject Reg	gister-Foreign-Device
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	
	Testing Hints	
BTL - 12.X.3.2.4 - Reject Delete-Foreign-Device-Table-Entry		
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	
	Testing Hints	
BTL ·	BTL - 12.X.3.2.5- Reject Distribute-Broadcast-To-Network	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	
	Testing Hints	

## 9.9.4 Is Able to Operate in BBMD Mode

The IUT supports BBMD mode.

BTL	BTL - 12.X.4.1.1 - Original-Broadcast-NPDU		
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL	- 12.X.4.1.2 - Forwarded	I-NPDU	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL	- 12.X.4.1.3 - Address-R	esolution	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL	- 12.X.4.1.4 - Forwarded	l-Address-Resolution	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL - 12.X.4.1.5 - Distribute-Broadcast-To-Network			
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL	- 12.X.4.2.1 - Reject For	warded-NPDU	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL	- 12.X.4.2.2 - Reject Add	dress-Resolution	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL	- 12.X.4.2.3 - Reject For	warded-Address-Resolution	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL	- 12.X.4.2.4 - Reject Dist	tribute-Broadcast-To-Network	
	Test Conditionality	Must be executed.	
	Test Directives		

	Testing Hints		
BTL ·	BTL - 12.X.4.3.1 - Verify writability of the BDT		
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL ·	- 12.X.5.1 - Execute Reg	ister-Foreign-Device	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL ·	- 12.X.5.2 - Execute Dele	ete-Foreign-Device-Table-Entry	
	Test Conditionality	Must be executed.	
	Test Directives		
	Testing Hints		
BTL - 12.X.5.3.1 - Non-Zero-Duration Foreign Device Table Timer Operations			
	Test Conditionality	Must be executed.	
	Test Directives		
	Testing Hints		
BTL ·	- 12.X.5.3.2 - Zero-Dura	tion Foreign Device Timer Operations	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL - 12.X.5.4 - Delete-Foreign-Device-Table-Entry For A Non-existent Entry			
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		

# 9.10 Data Link Layer - Secure Connect

See Test Package addendum 16.1bj for changes related to Data Link Layer – Secure Connect.

## 10.4 Network Management - Connection Establishment - B

There are no tests in the BTL Test Package for connection establishment BIBBs.

These changes are not contained in any SSPC proposal.

#### **Checklist Changes**

[In BTL Checklist, replace Network Management - Connection Establishment - B section]

Network Management - Connection Establishment - B		
	R	Base Requirements

## **Test Plan Changes**

[In BTL Test Plan, replace section 10.4 Network Management - Connection Establishment - B]

#### 10.4 Network Management - Connection Establishment - B

#### 9.10.1 Base Requirements

Base requirements must be met by any IUT that supports NM-CE-B.

Verif	Verify Checklist		
	Test Conditionality	Must be executed.	
	Test Directives	Verify that the IUT claims Network Management - Routing	
	Testing Hints	Note that when applying routing tests to a half-router, the PTP	
		connection should be established before the tests are started, and the	
		IUT plus its peer half-router are together considered the router under	
		test.	
135.1	-2013 - 10.3.1.2 - A Netw	ork Number is Specified that can be Reached Through a PTP	
Connection			
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives	Configure the test network as per 10.2.	
	Testing Hints		
135.1	-2013 - 10.3.3 - Initiating	g Half-Router Procedure for Connection Establishment	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives	Configure the test network as per 10.2.	
	Testing Hints		
135.1	135.1-2013 - 10.3.7 - Disconnect-Connection-To-Network		
	Test Conditionality	Must be executed.	
	Test Directives	Configure the test network as per 10.2.	
	Testing Hints		

## 10.7 Network Management - BBMD Configuration - B

Addendum 135-2012al added the NM-BBMDC-B BIBB. This document makes needed changes in the BTL Test Package to claim NM-BBMDC-B.

These changes are not contained in any SSPC proposal.

#### **Checklist Changes**

[In BTL Checklist, replace Network Management - BBMD Configuration - B section]

Support	Listing	Option	
Net	Network Management - BACnet Broadcast Management Device Configuration - B		
	R	Base Requirements	
	R	Supports Registration by Foreign Devices	
	BTL-C <sup>1</sup>	Executes Write-Broadcast-Distribution-Table	
	$C^2$	Supports configurable BBMD_Broadcast_Distribution_Table property	
<sup>1</sup> This option is required if the IUT claims Protocol_Revision 16 or lower.			
<sup>2</sup> Th	<sup>2</sup> This option is required if the IUT claims Protocol Revision 17 or higher.		

#### **Test Plan Changes**

[In BTL Test Plan, replace section 10.7 Network Management - BBMD Configuration - B]

#### **Network Management - BBMD Configuration - B** 10.7

These tests are designed for testing implementations of a BACnet Broadcast Management Device, including the execution of Network Layer and Application Layer commands to configure the BBMD.

#### **10.7.1 Base Requirements**

Base requirements must be met by any IUT claiming conformance to this BIBB.

BTL	BTL - 14.2.1.2 - Execute Forwarded-NPDU (Two-hop Distribution)		
	Test Conditionality	This test may be skipped if the IUT claims support for BACnet/IP - BBMD	
		Functionality.	
	<b>Test Directives</b>		
	Testing Hints		
BTL - 14.2.2.2 - Execute Original-Broadcast-NPDU (Two-hop Distribution)			
	<b>Test Conditionality</b>	This test may be skipped if the IUT claims support for BACnet/IP - BBMD	
		Functionality.	
	Test Directives		
	Testing Hints		
135.1	135.1-2013 - 14.2.3 - Execute Original-Unicast-NPDU		

	Test Conditionality	This test may be skipped if the IUT claims support for BACnet/IP - BBMD
		Functionality.
	<b>Test Directives</b>	
	Testing Hints	
135.1	-2013 - 14.5.2.2 - Origi	nal-Broadcast-NPDU Which Shall Be Forwarded (Two-hop Distribution)
	Test Conditionality	This test may be skipped if the IUT claims support for BACnet/IP - BBMD
		Functionality.
	Test Directives	
	<b>Testing Hints</b>	
BTL	- 14.7.1.2 - Broadcast <b>N</b>	Message from Directly Connected IP Subnet (Two-hop Distribution)
	<b>Test Conditionality</b>	This test may be skipped if the IUT claims support for BACnet/IP - BBMD
		Functionality.
	Test Directives	
	<b>Testing Hints</b>	
BTL	- 14.7.2.2 - Broadcast M	Message Forwarded by a Peer BBMD (Two-hop Distribution)
	Test Conditionality	This test may be skipped if the IUT claims support for BACnet/IP - BBMD
		Functionality.
	Test Directives	
	<b>Testing Hints</b>	
135.1	135.1-2013 - 14.9.3 - Original-Broadcast-NPDU	
	<b>Test Conditionality</b>	This test may be skipped if the IUT claims support for BACnet/IP - BBMD
		Functionality.
	<b>Test Directives</b>	
	Testing Hints	

## **10.7.2 Supports Registration by Foreign Devices**

While configured as a BBMD, the IUT supports, or can be made to support, registration by Foreign Devices and forwards as original BACnet/IP unicasts to each, any broadcasts it processes.

BTL	BTL - 14.6.X1 - Holds at Least 5 Foreign Device Registrations		
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
BTL	- 14.6.X2 - Negative Fo	oreign Device Registration when FD_Supported is FALSE	
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		
135.1	-2013 - 14.6.1 - Execut	e Read-Foreign-Device-Table	
	<b>Test Conditionality</b>	This test may be skipped if the IUT claims support for BACnet/IP - BBMD	
		Functionality.	
	Test Directives		
	Testing Hints		
135.1	-2013 - 14.6.3.1 - Non-z	zero-Duration Foreign Device Table Timer Operations	
	<b>Test Conditionality</b>	This test may be skipped if the IUT claims support for BACnet/IP - BBMD	
		Functionality.	
	Test Directives		
	Testing Hints		
135.1	135.1-2013 - 14.6.5 - Execute Delete-Foreign-Device-Table-Entry Which Should Be Rejected		
	<b>Test Conditionality</b>	This test may be skipped if the IUT claims support for BACnet/IP - BBMD	
		Functionality.	
	Test Directives		
	Testing Hints		

135.1	135.1-2013 - 14.6.6 - Execute Delete-Foreign-Device-Table-Entry		
	<b>Test Conditionality</b>	This test may be skipped if the IUT claims support for BACnet/IP - BBMD	
		Functionality.	
	<b>Test Directives</b>		
	Testing Hints		
BTL	BTL - 14.7.3.2 - Broadcast Message From a Foreign Device (Two-hop Distribution)		
	<b>Test Conditionality</b>	This test may be skipped if the IUT claims support for BACnet/IP - BBMD	
	-	Functionality.	
	Test Directives		
	Testing Hints		

#### **10.7.3 Executes Write-Broadcast-Distribution-Table**

The IUT executes Write-Broadcast-Distribution-Table to update the configured peer BBMDs.

135.1	135.1-2013 - 14.3.1 - Execute Write-Broadcast-Distribution-Table (Table Growth)		
	<b>Test Conditionality</b>	This test may be skipped if the IUT claims support for BACnet/IP - BBMD	
		Functionality.	
	Test Directives		
	Testing Hints		
135.1	-2013 - 14.3.2 - Execut	e Write-Broadcast-Distribution-Table (Table Shrinkage)	
	<b>Test Conditionality</b>	This test may be skipped if the IUT claims support for BACnet/IP - BBMD	
		Functionality.	
	Test Directives		
	Testing Hints		
BTL	BTL - 14.3.3 - Verify Broadcast Distribution Table Created from the Configuration Saved During the		
Previ	Previous Session		
	<b>Test Conditionality</b>	This test may be skipped if the IUT claims support for BACnet/IP - BBMD	
		Functionality.	
	Test Directives		
	Testing Hints		
BTL	- 14.3.X2 - Broadcast	Distribution_Table Holds at Least 5 Entries (via Write-Broadcast-	
Distribution-Table)			
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives		
	Testing Hints		

#### 10.7.4 Supports BBMD\_Broadcast\_Distribution\_Table property

The IUT supports the configurable BBMD\_Broadcast\_Distribution\_Table property in Network Port objects to configure peer BBMDs.

BTL	BTL - 14.3.X3 - BBMD_Broadcast_Distribution_Table Holds at Least 5 Entries (via		
BBM	D_Broadcast_Distribu	tion_Table)	
	<b>Test Conditionality</b>	Must be executed.	
	<b>Test Directives</b>		
	Testing Hints		
BTL	BTL – 14.3.X1 - Write-BDT service is required to return Write-BDT-NAK		
	<b>Test Conditionality</b>	Must be executed in all devices claiming Protocol Revision >= 17.	
	<b>Test Directives</b>		
	Testing Hints		

## 11.1 Gateway - Virtual Network - B

There are no tests in the BTL Test Package for the GW-VN-B BIBB.

These changes are not contained in any SSPC proposal.

## **Checklist Changes**

[There are no Checklist changes]

#### **Test Plan Changes**

[In BTL Test Plan, replace section 11.1.1 Gateway - Virtual Network - B, Base Requirements]

#### **11.1.1 Base Requirements**

Verify	Virtual Devices	
	<b>Test Conditionality</b>	Must be executed
	Test Directives	Test the virtual devices as per their BTL Checklist.
	Testing Hints	Similar to testing derivative products, the functionality supported might need to be spread over 2 or more virtual devices. In such cases, to which of the virtual devices any particular test is applied is left up to the test as long as all applicable tests are executed.
Verify	v Checklist	
	<b>Test Conditionality</b>	Must be executed
	Test Directives	Verify that the IUT claims the Network Management - Routing option "Routes Packets Between a Physical LAN and One or More Virtual LANs"
	Testing Hints	

## 13.5 Audit Reporting - View - A

Addendum 135-2016*bi* added Audit Reporting. This section adds support to the BTL Test Package for claiming AR-V-A.

These changes are not contained in any SSPC proposal.

#### **Checklist Changes**

[In BTL Checklist, replace Audit Reporting sections]

Aud	Audit Reporting - View - A		
	R <sup>1</sup>	Base Requirements	
	$C^1$	Supports initiation of AuditLogQuery by Target	
	$C^1$	Supports initiation of AuditLogQuery by Source	
	$C^1$	Supports initiation of ReadRange	
	<sup>1</sup> At least one of these must be supported.		
Aud	it Reportin	g - Advanced View and Modify - A	
	R <sup>1</sup>	Base Requirements	
	$C^1$	Supports initiation of AuditLogQuery by Target	
	$C^1$	Supports initiation of AuditLogQuery by Source	
	<sup>1</sup> At least one of these must be supported.		

#### **Test Plan Changes**

[In BTL Test Plan, replace section 13.5 Audit Reporting-View-A]

#### 13.5 Audit Reporting-View-A

#### 13.5.1 Base Requirements

Base requirements must be met by any IUT that supports AR-V-A.

#### 13.5.2 Supports Initiation of AuditLogQuery By Target

BTL - 8.X.2 - Query and Present Audit Log Records By Target		
	Test Conditionality	Must be executed.
	Test Directives	
	Testing Hints	

#### 13.5.3 Supports Initiation of AuditLogQuery By Source

BTL - 8.X.1 - Query and Present Audit Log Records By Source		
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	
	Testing Hints	

#### 13.5.4 Supports Initiation of ReadRange

BTL - 8.18.X1 - Reading and Presenting Large List Properties				
	<b>Test Conditionality</b>	Must be executed.		
	Test Directives	Apply on Log_Buffer property of an AuditLog and verify that each record is completely presented.		
	Testing Hints			

## 13.6 Audit Reporting-Advanced View and Modify-A

#### **13.6.1 Base Requirements**

Base requirements must be met by any IUT that supports AR-AVM-A.

Verify Checklist			
	Test Conditionality	Must be executed.	
	<b>Test Directives</b>	Verify that the IUT claims AR-V-A	
	Testing Hints		
Verif	y Checklist		
	<b>Test Conditionality</b>	Must be executed.	
	<b>Test Directives</b>	Verify that the IUT claims DS-RP-A	
	Testing Hints		
Verify Checklist			
	<b>Test Conditionality</b>	Must be executed.	
	<b>Test Directives</b>	Verify that the IUT claims DS-WP-A	
	Testing Hints		
Verify Checklist			
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives	Verify that the IUT claims DM-OCD-A and is able to create Audit	
		Reporter and Audit Log objects.	
	Testing Hints		
135.1-2013 - 8.18.3 - Reading and Presenting Properties			
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives	Repeat for all properties of the Audit Reporter and Audit Log objects	
		specified by AR-AVM-A, and for all audit related properties in a	
		randomly chosen set of other standard object types.	
	Testing Hints		
135.1-2013 - 8.22.4 - Accepting Input and Modifying Properties			
	Test Conditionality	Must be executed.	
	Test Directives	Repeat for all properties of the Audit Reporter and Audit Log objects	
		specified by AR-AVM-A, and for all audit related properties in a	
		randomly chosen set of other standard object types.	
	Testing Hints		

#### 13.5.2 Supports Initiation of AuditLogQuery By Target

Verif	y Checklist	
	<b>Test Conditionality</b>	Must be executed.
	Test Directives	Verify that the IUT claims support for AuditLogQuery by Target for
		AR-V-A.
	Testing Hints	

Verify Checklist			
	<b>Test Conditionality</b>	Must be executed.	
	Test Directives	Verify that the IUT claims support for AuditLogQuery by Source for	
		AR-V-A.	
	Testing Hints		

# 13.5.3 Supports Initiation of AuditLogQuery By Source

# **BTL Specified Tests Changes**

This section contains all of the new and changed tests required by the interim test BTL Checklist and BTL Test Plan changes.

[Network Port Object Tests] [In BTL Specified Tests, add clause 7.3.2.X43 Network Port Object Tests]

#### 7.3.2.X43 Network Port Object Tests

#### 7.3.2.X43.1 Network Port ACTIVATE\_CHANGES test

Reason for Change: New test per Addendum 135-2012ai.

Purpose: This test verifies that after any of the Network Port properties are changed, the revised value is activated when executing a ReinitializeDevice ACTIVATE\_CHANGES service request.

Test Concept: Write any of the writable properties of a Network Port object and activate those changes by issuing a ReinitializeDevice – WARMSTART or ACTIVATE\_CHANGES service request. Then after the IUT has time to have finished its update, verify that the Network Port object properties contain the values that were written.

Test Steps:

- 1. WRITE (any writable Network Port property) = (a value different from current value)
- 2. VERIFY Changes Pending = TRUE
- TRANSMIT ReinitializeDevice-Request
   'Reinitialized State of Device' = WARMSTART | ACTIVATE\_CHANGES
   'Password' = (any valid password)
- 4. RECEIVE BACnet-SimpleACK-PDU
- 5. CHECK (that the IUT has had time to have finished its update)
- 6. REPEAT X for each changed Network Port property) VERIFY X = (the revised value to which it was changed)
- 7. VERIFY Changes Pending = FALSE

#### 7.3.2.X43.2 Network Port non-volatility properties test

Reason for Change: New test per Addendum 135-2012ai.

Purpose: This test verifies that after any of the Network Port properties is changed, and the revised value is activated, then the revised value with which it was configured is maintained through a power failure and device restart.

Test Concept: Write any of the writable properties of a Network Port object (multiple properties may be written), and activate those changes by issuing a ReinitializeDevice – WARMSTART or ACTIVATE\_CHANGES service request. Then after the IUT has time to have finished its update, restart the IUT device by temporarily removing power. When the device has resumed operation after that restart, verify that the Network Port object properties contain the values that were changed and activated.

Test Steps:

- 1. WRITE (X, any writable Network Port property) = (a value different from current value)
- 2. TRANSMIT ReinitializeDevice-Request
  - 'Reinitialized State of Device' = WARMSTART | ACTIVATE\_CHANGES 'Password' = (any valid password)
- 3. RECEIVE BACnet-SimpleACK-PDU
- 4. WAIT for IUT to have finished its update
- 5. CHECK (that the IUT has had time to have finished its update)
- 6. VERIFY X = (the revised value to which it was changed)
- 7. MAKE (the IUT power cycle to reinitialize)
- 8. VERIFY X = (the revised value to which it was changed)

# 7.3.2.X43.3 Out\_Of\_Service, Status\_Flags, and Reliability test for an Object that does not contain Present\_Value

Purpose: This test verifies the interrelationship between the Out\_Of\_Service, Status\_Flags, and Reliability properties. If the PICS indicates that the Out\_Of\_Service property of the object under test is not writable, and if the value of the property cannot be changed by other means, then this test shall be omitted. This test applies to objects that do not contain Present\_Value.

Test Concept: Write to and verify the interrelationship between the Out\_Of\_Service, Status\_Flags, and Reliability properties of an object which does not contain Present\_Value.

Configuration Requirements: The selected object is configured such that its Reliability is NO\_FAULT\_DETECTED before execution of this test.

Test Steps:

- 1. IF (Out\_Of\_Service is writable) THEN WRITE Out\_Of\_Service = TRUE ELSE MAKE (Out\_Of\_Service = TRUE)
- 2. VERIFY Out Of Service = TRUE
- 3. VERIFY Status Flags = (?, FALSE, ?, TRUE)
- 4. IF (Reliability is present and writable) THEN
  - REPEAT X = (all values of the Reliability enumeration appropriate to the object type except NO\_FAULT\_DETECTED) DO { WRITE Reliability = X
    - WRITE Reliability = X VERIFY Reliability = X VERIFY Status\_Flags = (TRUE, TRUE,?, TRUE) WRITE Reliability = NO\_FAULT\_DETECTED VERIFY Reliability = NO\_FAULT\_DETECTED VERIFY Status\_Flags = (? FALSE, ?, TRUE)
- 5. CHECK (all communication of the protocol modeled by the object, through that port is disabled)
- 6. IF (Out\_Of\_Service is writable) THEN WRITE Out\_Of\_Service = FALSE

ELSE

MAKE (Out\_Of\_Service = FALSE)

- 7. VERIFY Out Of Service = FALSE
- 8. VERIFY Status\_Flags = (?,?,?,FALSE)

[Elevator Group, Escalaror, and Lift Object Tests] [In BTL Specified Tests, add clause 7.3.2.X45]

#### 7.3.2.X45 Elevator Group Object Tests

#### 7.3.2.X45.1 Machine\_Room\_ID property linking with the Positive\_Integer\_Value Object

Purpose: To verify that Machine\_Room\_ID property of Elevator Group reference the Positive\_Integer\_Value (PIV) object, whose Present\_Value property contains the identification number for the machine room that contains the group of Lifts or Escalators, represented by this object.

Test Concept: A machine room contains the Elevator Group which is having a group of Lifts or Escalators. This machine room is mapped to the Present\_Value property of Positive\_Integer\_Value Object which in turn is referenced to the Machine\_Room\_ID property of Elevator Group.

Configuration Requirements: The Machine room contains Elevator Group (EG1). OBJECT is any valid object type. X is any valid instance number in the range 0 to 4194302.

Test Steps:

1. IF (Machine\_Room\_ID contains room identification number) THEN VERIFY (EG1), Machine Room ID = (PIV, X)

ELSE

VERIFY (EG1), Machine\_Room\_ID = (OBJECT, 4194303)

#### 7.3.2.X45.2 Linking of Lift Objects under Group\_Members property of the Elevator Group Object

Purpose: This test verifies that the Group\_Members property of the Elevator Group object contains the object identifier of the Lift object representing lifts contained within the group represented by this Elevator Group object.

Test Concept: Tester selects an Elevator Group and reads the Group\_Members property of the Elevator Group and verifies that all the Lifts that are configured under one group are present under the Group\_Members property of the Elevator Group object.

Configuration Requirements: Configure 2 Lifts (L1 and L2) under the Elevator Group (EG1).

Test Steps:

1. VERIFY (EG1), Group\_Members = (L1, L2)

#### 7.3.2.X45.3 Linking of Escalator Objects under Group\_Members property of the Elevator Group Object

Purpose: This test verifies that the Group\_Members property of the Elevator Group object contains the object identifier of the Escalator object representing the escalators contained within the group represented by this Elevator Group object.

Test Concept: Tester selects an Elevator Group and reads the Group\_Members property of the Elevator Group and verifies that all the Escalators that are configured under one group are present under the Group\_Members property of the Elevator Group object.

Configuration Requirements: Configure 2 Escalators (E1 and E2) under the Elevator Group (EG1).

Test Steps:

1. VERIFY (EG1), Group\_Members = (E1, E2)

#### 7.3.2.X45.4 Linking of Landing\_Call\_Control Property Test

Purpose: To verify that writing Landing\_Call\_Control property of Elevator Group assigns an active call to the Lift Object linked by pushing it to the Assigned\_Landing\_Calls property of the Lift object.

Test Concept: An Elevator Group is available, and it contains at least one Lift object. Landing\_Call\_Control property of the Elevator Group is written with a Floor number and direction or destination for the lift. Value written to Landing\_Call\_Control property is updated in the Landing\_Calls property of the Elevator Group which in turn updates the Assigned\_Landing\_Calls property of Lift. This test shall be skipped in the event of absence of Landing\_Call\_Control property. If any of the Landing\_Calls or Assigned\_Landing\_Calls property is not present, then the test steps for that specific property shall be skipped.

Configuration Requirements: The Lift (L1) should be present in the Group\_Members property of Elevator Group (EG1). Lowest universal floor number of the lift < A < Highest universal floor number of the lift. Lowest universal
floor number of the lift  $\leq X \leq$  Highest universal floor number of the lift. B = (UP | DOWN | UP\_AND\_DOWN) and C = (B | UP\_AND\_DOWN).

Test Steps:

1. WRITE (EG1), Landing\_Call\_Control = (Floor Number A, Direction B | Destination X) 2. VERIFY (EG1), Landing Call Control = (Floor Number A, Direction B | Destination X)

- 3. VERIFY (EG1), Landing Calls = (Floor Number A, Direction C | Destination X)
- 4. VERIFY (L1), Assigned Landing Calls = (Floor Number A, Direction C)

4. VERIFT (E1), Assigned\_Landing\_Cans – (Floor Number A, Direction C)

Notes to Tester: Landing\_Calls property may contain other entries from same lift or different lifts connected under same Elevator Group. If the Elevator Group contains more than 1 lift, value written to Landing\_Call\_Control may get assigned to any other lift, based on the lift algorithm.

[In BTL Specified Tests, add clause 7.3.2.X46] 7.3.2.X46 Escalator Object Tests

# 7.3.2.X46.1 Elevator\_Group property of Escalator Object linking with Group\_Members property of Elevator Group Object

Purpose: This test verifies that Elevator\_Group property of Escalator object shall have reference of Elevator Group object whose Group\_Members property contains a reference of Escalator object.

Test Concept: Escalator object falls under one specific Elevator Group object. The reference of Elevator Group object should be mentioned in Elevator\_Group property of Escalator object. If there is no such Elevator Group object, Elevator\_Group property shall contain an object instance of 4194303.

Configuration Requirements: The Escalator (E1), should be present under Elevator Group (EG1). OBJECT is any valid object type.

Test Steps:

- 1. VERIFY (E1), Elevator\_Group = (EG1)
- 2. VERIFY (EG1), Group\_Members = ((E1),...., En)
- 3. IF (IUT does not contain reference of any Elevator Group Object) THEN VERIFY (E1), Elevator\_Group = (OBJECT, 4194303)

# 7.3.2.X46.2 Energy\_Meter, Power\_Mode and Operation\_Direction Tracking Test

Purpose: To verify that when Out\_Of\_Service property is set to TRUE for the monitored Escalator object, it does not track the changes made for Energy\_Meter, Power\_Mode and Operation\_Direction property and it does not control the escalator operation from these properties.

Test Concept: When the Out\_Of\_Service is set to TRUE, writing Energy\_Meter, Power\_Mode and Operation\_Direction property shall not make escalator to update its energy value, power mode and operation direction. Also, while making escalator's energy, power mode and operation direction change from current status, it shall not get updated to Energy\_Meter, Power\_Mode and Operation\_Direction property of the Escalator object. Out\_Of\_Service property of the Escalator object is set to TRUE in the beginning of the test. If either of the Energy\_Meter or Power\_Mode properties are not present, then the test steps for that specific property shall be skipped.

Configuration Requirements: The Escalator Object supports Energy\_Meter and/or Power\_Mode properties. Escalator Power\_Mode is TRUE and Operation\_Direction is STOPPED. Escalator is having energy meter value = X. Tester shall select any value for energy meter Y; Y < 99999 or permitted by IUT. Tester shall select any Operation\_Direction supported by IUT while testing.

Test Steps:

- 1. IF (Out\_Of\_Service is writable) THEN WRITE Out\_Of\_Service = TRUE
  - ELSE

MAKE (Out\_Of\_Service = TRUE)

- 2. VERIFY Out\_Of\_Service = TRUE
- 3. VERIFY Status\_Flags = (?, ?, ?, TRUE)
- 4. WRITE Energy\_Meter = Y
- 5. VERIFY Energy\_Meter = Y
- 6. CHECK (the escalator's energy consumption is having value = X or value other than Y)
- 7. MAKE (the escalator's energy consumption value = Z)
- 8. VERIFY Energy Meter = Y
- 9. WRITE Power Mode = FALSE
- 10. VERIFY Power\_Mode = FALSE
- 11. CHECK (the escalator is still powered up independent of the value written)
- 12. MAKE (the escalator's power mode to be TRUE from FALSE)
- 13. VERIFY Power\_Mode = FALSE
- 14. WRITE Operation Direction = UP RATED SPEED
- 15. VERIFY Operation Direction = UP RATED SPEED
- 16. CHECK (the escalator remains stopped)
- 17. MAKE (the escalator's operation direction to be DOWN\_RATED\_SPEED)
- 18. VERIFY Operation\_Direction = UP\_RATED\_SPEED
- 19. IF (Out Of Service is writable) THEN
  - WRITE Out\_Of\_Service = FALSE
  - ELSE

MAKE (Out\_Of\_Service = FALSE)

20. VERIFY Out\_Of\_Service = FALSE

21. VERIFY Status\_Flags = (?, ?, ?, FALSE)

#### 7.3.2.X46.3 Passenger\_Alarm and Fault\_Signals Tracking Test

Purpose: To verify that when Out\_Of\_Service property is set to TRUE for the monitored Escalator object, it does not track the changes made for Passenger\_Alarm and Fault\_Signals property and it does not control the escalator operation from these properties.

Test Concept: When the Out\_Of\_Service is set to TRUE, writing Passenger\_Alarm and Fault\_Signals property shall not make escalator to update its alarm and fault status. Also, while making escalator's fault and alarm status change from current value, it shall not get updated to Passenger\_Alarm and Fault\_Signals property of the Escalator object. Out\_Of\_Service property of the Escalator object is set to TRUE in the beginning of the test. If Fault\_Signals property is not present, then the respective test steps shall be skipped.

Configuration Requirements: Escalator has no alarm or fault at the start of test. Tester shall select any value for Fault\_Signals property testing that is supported by IUT.

Test Steps:

 IF (Out\_Of\_Service is writable) THEN WRITE Out\_Of\_Service = TRUE ELSE MAKE (Out\_Of\_Service = TRUE)
 VERIFY Out Of Service = TRUE

- 3. VERIFY Status\_Flags = (?, ?, ?, TRUE)
- 4. WRITE Passenger\_Alarm = TRUE
- 5. VERIFY Passenger\_Alarm = TRUE
- 6. CHECK (the escalator's alarm is not triggered)
- 7. MAKE (the escalator in NORMAL state)
- 8. VERIFY Passenger\_Alarm = TRUE
- 9. WRITE Fault\_Signals = OVERSPEED\_FAULT
- 10. VERIFY Fault\_Signals = OVERSPEED\_FAULT
- 11. CHECK (the escalator does not have any fault into it)
- 12. MAKE (the escalator to have SAFETY\_DEVICE\_FAULT fault)
- 13. VERIFY Fault\_Signals = OVERSPEED\_FAULT
- 14. IF (Out\_Of\_Service is writable) THEN

WRITE Out\_Of\_Service = FALSE

ELSE

MAKE (Out\_Of\_Service = FALSE)

- 15. VERIFY Out\_Of\_Service = FALSE
- 16. VERIFY Status\_Flags = (?, ?, ?, FALSE)

# 7.3.2.X46.4 Escalator\_Mode Tracking Test

Purpose: To verify that when Out\_Of\_Service property is set to TRUE for the monitored Escalator object, it does not track the changes made for Escalator\_Mode property and also it does not control the escalator operation from this property.

Test Concept: When the Out\_Of\_Service is set to TRUE, writing Escalator\_Mode property shall not make escalator to update its mode. Also, while making escalator's mode to change from current value, it shall not get updated to Escalator\_Mode property of the Escalator object. Out\_Of\_Service property of the Escalator object is set to TRUE in the beginning of the test. If this property is not present, then this test shall be skipped.

Configuration Requirements: The Escalator Object shall support Escalator\_Mode property. Escalator runs at UP mode. Tester shall select any value for Escalator\_Mode property for testing that are supported by IUT.

Test Steps:

1. IF (Out\_Of\_Service is writable) THEN

WRITE Out\_Of\_Service = TRUE

ELSE

MAKE (Out\_Of\_Service = TRUE)

- 2. VERIFY Out\_Of\_Service = TRUE
- 3. VERIFY Status\_Flags = (?, ?, ?, TRUE)
- 4. WRITE Escalator\_Mode = DOWN
- 5. VERIFY Escalator\_Mode = DOWN
- 6. CHECK (the escalator or slanted passenger conveyor is still moving upward)
- 7. MAKE (the escalator to move from downward to upward)
- 8. VERIFY Escalator\_Mode = DOWN
- 9. IF (Out\_Of\_Service is writable) THEN WRITE Out Of Service = FALSE
  - ELSE

MAKE (Out Of Service = FALSE)

- 10. VERIFY Out Of Service = FALSE
- 11. VERIFY Status\_Flags = (?, ?, ?, FALSE)

# 7.3.2.X46.5 Operation\_Direction Tracks Escalator\_Mode Test

Purpose: To verify the linking of Operation Direction property and Escalator Mode property of Escalator object

Test Concept: Operation\_Direction property i.e. the direction and speed in which this escalator is presently moving corresponds to the Escalator\_Mode property of Escalator object

Test Steps:

- IF (Escalator\_Mode = STOP) THEN VERIFY Operation\_Direction = STOPPED
   IF (Escalator\_Mode = UP) THEN VERIFY Operation\_Direction = UP\_RATED\_SPEED | UP\_REDUCED\_SPEED
   IF (Escalator\_Mode = DOWN) THEN
  - VERIFY Operation\_Direction = DOWN\_RATED\_SPEED | DOWN\_REDUCED\_SPEED

# 7.3.2.X46.6 Energy\_Meter\_Ref Property Test

Purpose: To verify linking of Energy\_Meter property and Energy\_Meter\_Ref property.

Test Concept: If the Energy\_Meter\_Ref property is present and initialized with and Object (contains an instance other than 4194303), then the Energy\_Meter property, if present, shall have a value of 0.0. If Energy\_Meter\_Ref property is un-initialized, then the Energy\_Meter property shall have any valid value.

Test Steps:

 IF (Energy\_Meter\_Ref is present and initialized with instance other than 4194303) THEN VERIFY Energy\_Meter = 0.0 ELSE

VERIFY Energy Meter = (Any Valid Value)

### 7.3.2.X46.7 CHANGE\_OF\_STATE for Passenger\_Alarm (ConfirmedEventNotification)

Purpose: To verify the correct operation of the CHANGE\_OF\_STATE event algorithm. This test applies to Event Enrollment objects with an Event\_Type of CHANGE\_OF\_STATE and to intrinsic event reporting for Escalator and Lift objects.

Test Concept: The object begins the test in a NORMAL state. pMonitoredValue is set to TRUE. After pTimeDelay the object shall enter the OFFNORMAL state and transmit an event notification message. pMonitoredValue is set to FALSE corresponding to a NORMAL state. After pTimeDelayNormal the object shall enter the NORMAL state and transmit an event notification message

Configuration Requirements: The IUT shall be configured such that the Event\_Enable property has a value of TRUE for the TO-OFFNORMAL, TO-FAULT and TO-NORMAL transitions. The Issue\_Confirmed\_Notifications parameter shall have a value of TRUE. The event-generating objects shall be in a NORMAL state at the start of the test. If a Notification Class object is being used to configure recipient information the value of the Transitions parameter for all recipients shall be (TRUE, TRUE, TRUE). If present in the object being tested, the Event\_Detection\_Enable property shall have a value of TRUE, Event\_Algorithm\_Inhibit shall have a value of FALSE.

- 1. VERIFY pCurrentState = NORMAL
- 2. I F (the object, or referenced object, if using Event Enrollment, is an Escalator or Lift object with Passenger Alarm property) THEN
- 3. MAKE (pMonitoredValue (Passenger\_Alarm) = TRUE)
- 4. WAIT (pTimeDelay)
- 5. BEFORE Notification Fail Time
  - RECEIVE ConfirmedEventNotification-Request, 'Process Identifier' = (any valid process ID),

'Initiating Device Identifier' =	IUT.
'Event Object Identifier' = (the intr	insic reporting object being tested or the EventEnrollment
object being tested),	1 0 9 0
'Time Stamp' =	(T1, the current local time or sequence number),
'Notification Class' =	(the configured notification class),
'Priority' = (the value config	ured to correspond to a TO-OFFNORMAL transition),
'Event Type' =	CHANGE_OF_STATE,
'Message Text' =	(optional, any valid message text),
'Notify Type' =	EVENT   ALARM,
'AckRequired' =	TRUE   FALSE,
'From State' =	NORMAL,
'To State' =	OFFNORMAL,
'Event Values' =	(pMonitoredValue, pStatusFlags)
6. TRANSMIT BACnet-SimpleACK-PDU	
7. VERIFY pStatusFlags = (TRUE, FALSE, ?, ?)	
8. VERIFY pCurrentState = OFFNORMAL	
9. VERIFY Event_Time_Stamps = (T1, *, *)	
10. MAKE (pMonitoredValue (Passenger_Alarm) =	FALSE)
11. WAIT (pTimeDelayNormal)	
12. BEFORE Notification Fail Time	
RECEIVE ConfirmedEventNotification-Rec	quest,
'Process Identifier' =	(any valid process ID),
'Initiating Device Identifier' =	IUT
'Event Object Identifier' =	(the intrinsic reporting object being tested or the
	EventEnrollment object being tested),
'Time Stamp' =	(T2, the current local time or sequence number),
'Notification Class' =	(the configured notification class),
'Priority' =	(the value configured to correspond to a TO-NORMAL
	transition),
'Event Type' =	CHANGE_OF_STATE,
'Message Text' =	(optional, any valid message text),
'Notify Type' =	EVENT   ALARM,
'AckRequired' =	TRUE   FALSE,
'From State' =	OFFNORMAL,
'To State' =	NORMAL,
'Event Values' =	(pMonitoredValue, pStatusFlags)
13. TRANSMIT BACnet-SimpleACK-PDU	
14. VERIFY pStatusFlags = (FALSE, FALSE, ?, ?)	
15. VERIFY pCurrentState = NORMAL	
16. VERIFY Event Time Stamps = (T1, *, T2)	

# 7.3.2.X46.8 CHANGE\_OF\_STATE for Passenger\_Alarm (UnconfirmedEventNotification)

Purpose: To verify the correct operation of the CHANGE\_OF\_STATE event algorithm. This test applies to Event Enrollment objects with an Event\_Type of CHANGE\_OF\_STATE and to intrinsic event reporting for Escalator and Lift objects.

Test Concept: The object begins the test in a NORMAL state. pMonitoredValue is set to TRUE. After pTimeDelay the object shall enter the OFFNORMAL state and transmit an event notification message. pMonitoredValue is set to FALSE corresponding to a NORMAL state. After pTimeDelayNormal the object shall enter the NORMAL state and transmit an event notification message

Configuration Requirements: The IUT shall be configured such that the Event\_Enable property has a value of TRUE for the TO-OFFNORMAL, TO-FAULT and TO-NORMAL transitions. The Issue\_Confirmed\_Notifications parameter shall have a value of FALSE. The event-generating objects shall be in a NORMAL state at the start of the test. If a Notification Class object is being used to configure recipient information the value of the Transitions

parameter for all recipients shall be (TRUE, TRUE, TRUE). If present in the object being tested, the Event\_Detection\_Enable property shall have a value of TRUE, Event\_Algorithm\_Inhibit shall have a value of FALSE.

Test Steps: The test steps for this test are identical to the test steps in 7.3.2.X46.7 except that the ConfirmedEventNotification requests are UnconfirmedEventNotification requests and the TD does not acknowledge receiving the notifications.

[Elevator Group, Escalator, and Lift Object Tests] [In BTL Specified Tests, add clause 7.3.2.X47 Lift Object Tests]

# 7.3.2.X47 Lift Object Tests

# 7.3.2.X47.1 Elevator\_Group property of Lift Object linking with Group\_Members property of Elevator Group Object

Purpose: This test verifies that Elevator\_Group property of Lift object shall have reference of Elevator Group object whose Group\_Members property contains a reference of Lift object.

Test Concept: Lift object falls under one specific Elevator Group object. The reference of Elevator Group object should be mentioned in Elevator\_Group property of Lift object. If there is no such Elevator Group object, Elevator\_Group property shall contain an object instance of 4194303.

Configuration Requirements: The Lift (L1) should present under the Elevator Group (EG1). OBJECT is any valid object type.

Test Steps:

- 1. VERIFY (L1), Elevator Group = (EG1)
- 2. VERIFY (EG1), Group Members = ((L1), ..., Ln)
- 3. IF (IUT does not have reference of any such Elevator Group object) THEN VERIFY (L1), Elevator\_Group = (OBJECT, 4194303)

# 7.3.2.X47.2 Car\_Moving\_Direction and Car\_Assigned\_Direction Tracking Test

Purpose: To verify that when Out\_Of\_Service property is set to TRUE for the monitored Lift object, it does not track the changes made for Car\_Moving\_Direction and Car\_Assigned\_Direction property and it does not control the lift operation from these properties.

Test Concept: When Out\_Of\_Service is set to TRUE, writing Car\_Moving\_Direction and Car\_Assigned\_Direction property shall not make lift to serve specified direction. Also, making lift to serve any direction shall not be updated in Car\_Moving\_Direction and Car\_Assigned\_Direction property of Lift object. Out\_Of\_Service property of the Lift object is set to TRUE in the beginning of the test. If Car\_Assigned\_Direction property is not present, then the respective test steps shall be skipped.

Configuration Requirements: 'X' and 'Y' are any valid directions supported by IUT. Tester shall select any car moving direction and car assigned direction supported by IUT.

- 1. IF (Out\_Of\_Service is writable) THEN WRITE Out\_Of\_Service = TRUE ELSE MAKE (Out\_Of\_Service = TRUE)
- 2. VERIFY Out\_Of\_Service = TRUE
- 3. VERIFY Status\_Flags = (?, ?, ?, TRUE)

- 4. WRITE Car\_Moving\_Direction = Direction X
- 5. VERIFY Car\_Moving\_Direction = Direction X
- 6. CHECK (the lift is not serving as per the Car\_Moving\_Direction property)
- 7. MAKE (the lift to move in Direction Y)
- 8. VERIFY Car\_Moving\_Direction = Direction X
- 9. WRITE Car\_Assigned\_Direction = Direction X
- 10. VERIFY Car\_Assigned\_Direction = Direction X
- 11. CHECK (the lift is not serving as per the Car\_Assigned\_Direction property)
- 12. MAKE (the lift assigned towards Direction Y)
- 13. VERIFY Car\_Assigned\_Direction = Direction X
- 14. IF (Out\_Of\_Service is writable) THEN WRITE Out\_Of\_Service = FALSE

ELSE

MAKE (Out\_Of\_Service = FALSE)

- 15. VERIFY Out\_Of\_Service = FALSE
- 16. VERIFY Status\_Flags = (?, ?, ?, FALSE)

### 7.3.2.X47.3 Car\_Door\_Status and Landing\_Door\_Status Tracking Test

Purpose: To verify that when Out\_Of\_Service property is set to TRUE for the monitored Lift object, it does not track the changes made for Car\_Door\_Status and Landing\_Door\_Status property and it does not control the lift operation from these properties.

Test Concept: When Out\_Of\_Service is set to TRUE, writing Car\_Door\_Status and Landing\_Door\_Status property shall not make lift and landing doors to operate. Also, making lift and landing doors to operate shall not be updated in Car\_Door\_Status and Landing\_Door\_Status property when the Out\_Of\_Service is set to TRUE. Out\_Of\_Service property of the Lift object is set to TRUE in the beginning of the test. If Landing\_Door\_Status property is not present, then the respective test steps shall be skipped.

Configuration Requirements: Lift's Door starts in OPEN State. ARRAY INDEX = (any valid value N;  $1 \le N \le$  number of doors of a car). Universal floor number = (X = any valid floor number of the lift connected to the IUT) Tester shall select any car door status and landing door status values supported by IUT.

Test Steps:

- 1. IF (Out\_Of\_Service is writable) THEN
  - WRITE Out\_Of\_Service = TRUE

ELSE

- MAKE (Out\_Of\_Service = TRUE)
- 2. VERIFY Out\_Of\_Service = TRUE
- 3. VERIFY Status\_Flags = (?, ?, ?, TRUE)
- 4. WRITE Car\_Door\_Status = CLOSED, ARRAY INDEX = N
- 5. VERIFY Car\_Door\_Status = CLOSED, ARRAY INDEX = N
- 6. CHECK (the lift's car door is not operating as per the Car\_Door\_Status property)
- 7. MAKE (the lift's car door N to OPEN)
- 8. VERIFY Car\_Door\_Status = CLOSED, ARRAY INDEX = N
- 9. WRITE Landing\_Door\_Status = CLOSING, ARRAY INDEX = N, Universal floor number = X
- 10. VERIFY Landing\_Door\_Status = CLOSING, ARRAY INDEX = N
- 11. CHECK (the specified landing door is not serving as per the Landing\_Door\_Status property)
- 12. MAKE (the landing door for car door N to OPEN at Universal floor number X)
- 13. VERIFY Landing Door Status = CLOSING, ARRAY INDEX = N, Universal floor number = X
- 14. IF (Out\_Of\_Service is writable) THEN
  - WRITE Out\_Of\_Service = FALSE

ELSE

MAKE (Out\_Of\_Service = FALSE)

- 15. VERIFY Out\_Of\_Service = FALSE
- 16. VERIFY Status\_Flags = (?, ?, ?, FALSE)

# 7.3.2.X47.4 Car\_Position and Next\_Stopping\_Floor Tracking Test

Purpose: To verify that when Out\_Of\_Service property is set to TRUE for the monitored Lift object, it does not track the changes made in Car\_Position and Next\_Stopping\_Floor property and also it does not control the lift operation from these properties.

Test Concept: When the Out\_Of\_Service is set to TRUE, writing Car\_Position and Next\_Stopping\_Floor property shall not make lift to update its car position and next stopping floor. Also, while making lift's car position and next stopping floor change from current value, it shall not get updated to Car\_Position and Next\_Stopping\_Floor property of the Lift object. Out\_Of\_Service property of the Lift object is set to TRUE in the beginning of the test. If Next\_Stopping\_Floor property is not present, then the respective test steps shall be skipped.

Configuration Requirements: Lift's current position (floor) is A. Universal floor number = (X, Y, A, B, C = any valid floor number of the lift connected to the IUT). Tester shall select any floor number supported by IUT for this test.

Test Steps:

- 1. IF (Out\_Of\_Service is writable) THEN WRITE Out\_Of\_Service = TRUE ELSE
  - MAKE (Out\_Of\_Service = TRUE)
- 2. VERIFY Out\_Of\_Service = TRUE
- 3. VERIFY Status\_Flags = (?, ?, ?, TRUE)
- 4. WRITE Car\_Position = Y
- 5. VERIFY Car\_Position = Y
- 6. CHECK (the lift still stands at the floor A)
- 7. MAKE (the lift to stand at the floor X)
- 8. VERIFY Car Position = Y
- 9. WRITE Next\_Stopping\_Floor = C
- 10. VERIFY Next Stopping Floor = C
- 11. CHECK (the lift is not moving towards floor C and it still stands at floor X)
- 12. MAKE (the lift to move from floor X to reach floor B)
- 13. VERIFY Next\_Stopping\_Floor = C
- 14. IF (Out\_Of\_Service is writable) THEN
  - WRITE Out\_Of\_Service = FALSE

ELSE

- MAKE (Out\_Of\_Service = FALSE)
- 15. VERIFY Out\_Of\_Service = FALSE
- 16. VERIFY Status\_Flags = (?, ?, ?, FALSE)

# 7.3.2.X47.5 Passenger\_Alarm and Fault\_Signals Tracking Test

Purpose: To verify that when Out\_Of\_Service property is set to TRUE for the monitored Lift object, it does not track the changes made for Passenger\_Alarm and Fault\_Signals property and it does not control the lift operation from these properties.

Test Concept: When the Out\_Of\_Service is set to TRUE, writing Passenger\_Alarm and Fault\_Signals property shall not make lift to update its alarm and fault status. Also, while making lift's fault and alarm status change from current value, it shall not get updated to Passenger\_Alarm and Fault\_Signals property of the Lift object. Out\_Of\_Service property of the Lift object is set to TRUE in the beginning of the test. If Fault\_Signals property is not present, then the respective test steps shall be skipped.

Configuration Requirements: Lift has no alarm or fault at the start of test. Tester shall select any value for Fault\_Signals property testing that is supported by IUT.

Test Steps:

- 1. IF (Out\_Of\_Service is writable) THEN WRITE Out\_Of\_Service = TRUE ELSE
  - MAKE (Out\_Of\_Service = TRUE)
- 2. VERIFY Out\_Of\_Service = TRUE
- 3. WRITE Passenger\_Alarm = TRUE
- 4. VERIFY Passenger\_Alarm = TRUE
- 5. CHECK (the lift's alarm is not triggered)
- 6. MAKE (the lift to move from Alarm to normal state)
- 7. VERIFY Passenger Alarm = TRUE
- 8. WRITE Fault Signals = CALL BUTTON STUCK
- 9. VERIFY Fault Signals = CALL BUTTON STUCK
- 10. CHECK (the lift does not have any fault into it)
- 11. MAKE (the lift to have POSITION LOST fault)
- 12. VERIFY Fault Signals = CALL  $\overline{BUTTON}$  STUCK
- 13. IF (Out Of Service is writable) THEN
  - WRITE Out Of Service = FALSE

ELSE

- MAKE (Out Of Service = FALSE)
- 14. VERIFY Out Of Service = FALSE

### 7.3.2.X47.6 Making\_Car\_Call, Car\_Mode & Car\_Door\_Command Tracking Test

Purpose: To verify that when Out\_Of\_Service property is set to TRUE for the monitored Lift object, it does not track the changes made for Making\_Car\_Call, Car\_Mode & Car\_Door\_Command property and also it does not control the lift operation from these properties.

Test Concept: When Out\_Of\_Service is set to TRUE, writing Making\_Car\_Call, Car\_Mode & Car\_Door\_Command property shall not make lift to serve specified floor, to set the mode and to execute car door commands. Also, making lift to serve different floors, to operate at different modes and for various car door commands shall not be updated in Making\_Car\_Call, Car\_Mode & Car\_Door\_Command properties of Lift Object. Out\_Of\_Service property of the Lift object is set to TRUE in the beginning of the test. If any of the Making\_Car\_Call, Car\_Mode or Car\_Door\_Command property is not present, then the test steps for that specific property shall be skipped.

Configuration Requirements: Car\_Mode is NORMAL and Car\_Door\_Command is CLOSE at the start of the test. ARRAY INDEX = (any valid value N;  $1 \le N \le$  number of doors of a car). Universal floor number = (X, Y = any valid floor number of the lift connected to the IUT). Tester shall select any car door command or car mode supported by IUT while testing.

Test Steps:

1. IF (Out\_Of\_Service is writable) THEN WRITE Out\_Of\_Service = TRUE

ELSE

MAKE (Out Of Service = TRUE)

- 2. VERIFY Out Of Service = TRUE
- 3. VERIFY Status Flags = (?, ?, ?, TRUE)
- 4. WRITE Making Car Call = any valid floor X, ARRAY INDEX = N
- 5. VERIFY Making\_Car\_Call = X, ARRAY INDEX = N
- 6. CHECK (the lift is not serving as per value X in Making\_Car\_Call property)
- 7. MAKE (the lift to serve call at floor Y for car door N)
- 8. VERIFY Making Car Call = X, ARRAY INDEX = N
- 9. WRITE Car Door Command = OPEN, ARRAY INDEX = N

- 10. VERIFY Car\_Door\_Command = OPEN, ARRAY INDEX = N
- 11. CHECK (the lift's car door N is not opening as per the Car\_Door\_Command property)
- 12. MAKE (the lift to CLOSE at the car door N from OPEN or NONE)
- 13. VERIFY Car\_Door\_Command = OPEN, ARRAY INDEX = N
- 14. WRITE Car\_Mode = HOMING
- 15. VERIFY Car\_Mode = HOMING
- 16. CHECK (the lift is not moving into HOMING mode)
- 17. MAKE (the lift into PARKING mode)
- 18. VERIFY Car\_Mode = HOMING
- 19. IF (Out\_Of\_Service is writable) THEN
  - WRITE Out\_Of\_Service = FALSE

ELSE

MAKE (Out\_Of\_Service = FALSE)

- 20. VERIFY Out\_Of\_Service = FALSE
- 21. VERIFY Status\_Flags = (?, ?, ?, FALSE)

#### 7.3.2.X47.7 Assigned\_Landing\_Call and Registered\_Car\_Call Tracking Test

Purpose: To verify that when Out\_Of\_Service property is set to TRUE for the monitored Lift object, it does not track the changes made for Assigned\_Landing\_Call and Registered\_Car\_Call property and it does not control the lift operation from these properties.

Test Concept: When Out\_Of\_Service is set to TRUE, writing Assigned\_Landing\_Call and Registered\_Car\_Call property shall not make lift to serve specified floors and direction. Also, making lift to serve any floors and direction shall not be updated in Assigned\_Landing\_Calls and Registered\_Car\_Call property of Lift object. . Out\_Of\_Service property of the Lift object is set to TRUE in the beginning of the test. If any of the Assigned\_Landing\_Calls and Registered\_Car\_Call property shall be skipped.

Configuration Requirements: ARRAY INDEX = (any valid value N;  $1 \le N \le$  number of doors of a car). Universal floor number = (A, B, X1...n, Y1...n = any valid floor number of the lift connected to the IUT). P, Q is any valid direction supported by IUT.

Test Steps:

- 1. IF (Out\_Of\_Service is writable) THEN
  - WRITE Out\_Of\_Service = TRUE

ELSE

MAKE (Out\_Of\_Service = TRUE)

- 2. VERIFY Out\_Of\_Service = TRUE
- 3. VERIFY Status\_Flags = (?, ?, ?, TRUE)
- 4. WRITE Assigned\_Landing\_Calls = (Floor A, Direction P), ARRAY INDEX = N
- 5. VERIFY Assigned\_Landing\_Calls = (Floor A, Direction P), ARRAY INDEX = N
- 6. CHECK (the lift is not serving as per the values of Assigned\_Landing\_Calls property)
- 7. MAKE (the lift to serve landing call at Floor B, Direction Q for car door N)
- 8. VERIFY Assigned\_Landing\_Calls = (Floor A, Direction P), ARRAY INDEX = N
- 9. WRITE Registered\_Car\_Call = (X1, X2, X3, X4...Xn), ARRAY INDEX = N
- 10. VERIFY Registered\_Car\_Call = (X1, X2, X3, X4...Xn), ARRAY INDEX = N
- 11. CHECK (the lift is not serving as per the Registered\_Car\_Call property)
- 12. MAKE (the lift to serve calls at Floor (Y1, Y2, Y3....Yn) for car door N)
- 13. VERIFY Registered\_Car\_Call = (X1, X2, X3, X4...Xn), ARRAY INDEX = N
- 14. IF (Out Of Service is writable) THEN

WRITE Out\_Of\_Service = FALSE

ELSE

MAKE (Out\_Of\_Service = FALSE)

- 15. VERIFY Out\_Of\_Service = FALSE
- 16. VERIFY Status\_Flags = (?, ?, ?, FALSE)

# 7.3.2.X47.8 Car\_Door\_Zone and Car\_Load Tracking Test

Purpose: To verify that when Out\_Of\_Service property is set to TRUE for the monitored Lift object, it does not track the changes made for Car\_Door\_Zone and Car\_Load property and it does not control the lift operation from these properties.

Test Concept: When the Out\_Of\_Service is set to TRUE, writing Car\_Door\_Zone and Car\_Load property shall not make lift update its car door zone and its load. Also, while making lift's car to enter to a particular door zone where door opening is permitted and having a specific weight of lift car shall not get updated to Car\_Door\_Zone and Car\_Load properties of the Lift object. Out\_Of\_Service property of the Lift object is set to TRUE in the beginning of the test. If any of the Car\_Door\_Zone and Car\_Load property is not present, then the test steps for that specific property shall be skipped.

Configuration Requirements: Lift is stopped at any floor in the specified car door zone and having X units of weight. Tester shall select any weight within the permissible limit of the IUT while testing the Car\_Load property.

Test Steps:

- 1. IF (Out\_Of\_Service is writable) THEN WRITE Out\_Of\_Service = TRUE ELSE
  - MAKE (Out\_Of\_Service = TRUE)
- 2. VERIFY Out\_Of\_Service = TRUE
- 3. VERIFY Status\_Flags = (?, ?, ?, TRUE)
- 4. WRITE Car\_Door\_Zone = FALSE
- 5. VERIFY Car\_Door\_Zone = FALSE
- 6. CHECK (the lift's car door zone remains unchanged independent of value written)
- 7. MAKE (the lift's car door to door opening permitted zone)
- 8. VERIFY Car\_Door\_Zone = FALSE
- 9. WRITE Car\_Load = X+1 units
- 10. VERIFY Car Load = X+1 units
- 11. CHECK (the car load is X units)
- 12. MAKE (the lift car load to X+2)
- 13. VERIFY Car Load = X+1 units
- 14. IF (Out\_Of\_Service is writable) THEN

WRITE Out\_Of\_Service = FALSE

ELSE

- MAKE (Out\_Of\_Service = FALSE)
- 15. VERIFY Out\_Of\_Service = FALSE
- 16. VERIFY Status\_Flags = (?, ?, ?, FALSE)

# 7.3.2.X47.9 Energy\_Meter and Car\_Drive\_Status Tracking Test

Purpose: To verify that when Out\_Of\_Service property is set to TRUE for the monitored Lift object, it does not track the changes made for Energy\_Meter and Car\_Drive\_Status property and it does not control the lift operation from these properties.

Test Concept: When the Out\_Of\_Service is set to TRUE, writing Energy\_Meter and Car\_Drive\_Status property shall not make lift to update its energy value and car drive status. Also, while making lift's energy and car drive status change from current value, it shall not get updated to Energy\_Meter and Car\_Drive\_Status property of the Lift object. Out\_Of\_Service property of the Lift object is set to TRUE in the beginning of the test. If any of the Energy\_Meter and Car\_Drive\_Status property shall be skipped.

Configuration Requirements: Lift is stopped at any floor, i.e. car drive status is stationary. Lift is having energy meter value = X. Tester shall select any value for energy meter Y; Y < 99999 or permitted by IUT. Tester shall select any car drive status supported by IUT.

Test Steps:

 IF (Out\_Of\_Service is writable) THEN WRITE Out\_Of\_Service = TRUE ELSE MAKE (Out\_Of\_Service = TRUE)

2. VERIFY Out Of Service = TRUE

- 3. VERIFY Status Flags = (?, ?, ?, TRUE)
- 4. WRITE Energy Meter = Y
- 4. WRITE Energy\_Meter -1
- 5. VERIFY Energy\_Meter = Y
- 6. CHECK (the lift's energy consumption is having value = X or value other than Y)
- 7. MAKE (the lift's energy consumption value = Z)
- 8. VERIFY Energy\_Meter = Y
- 9. WRITE Car\_Drive\_Status = BRAKING
- 10. VERIFY Car\_Drive\_Status = BRAKING
- 11. CHECK (the lift's car drive status is STATIONARY)
- 12. MAKE (the lift's car drive status to ACCELERATE)
- 13. VERIFY Car\_Drive\_Status = BRAKING
- 14. IF (Out\_Of\_Service is writable) THEN WRITE Out\_Of\_Service = FALSE

ELSE

MAKE (Out Of Service = FALSE)

- 15. VERIFY Out Of Service = FALSE
- 16. VERIFY Status\_Flags = (?, ?, ?, FALSE)

# 7.3.2.X47.10 Making\_Car\_Call and Registered\_Car\_Call Test

Purpose: To verify that the values written into Making\_Car\_Call property of lift object reflects in its Registered\_Car\_Call property at the same door side array index.

Test Concept: Making\_Car\_Call property of Lift (L1) object being tested is subjected for car calls provided by means of passenger requesting for car stop or by means of writing the property. The Registered\_Car\_Call property value at a specified array index is checked to verify that it is same as that of value provided to Making\_Car\_Call property.

Configuration Requirements: For below steps 'Array Index' = (any valid value N;  $1 \le N \le$  number of doors of a car) and 'Property Value' = (any valid value X; X \le highest universal floor number of the lift)

Test Steps:

- 1. IF (Making\_Car\_Call is writable) THEN WRITE (L1), Making\_Car\_Call = X, ARRAY INDEX = N ELSE
  - MAKE (Making\_Car\_Call = (Value of X), ARRAY INDEX = N)
- VERIFY (L1), Making\_Car\_Call = X, ARRAY INDEX = N
   VERIFY (L1), Registered Car Call = X, ARRAY INDEX = N
- \_\_\_\_\_\_

Notes to Tester: Registered\_Car\_Call property may contain other additional entries.

# 7.3.2.X47.11 Array Size of the Lift Object properties based on car door size.

Purpose: To verify that the size of the Car\_Door\_Text, Assigned\_Landing\_Calls, Making\_Car\_Call, Registered\_Car\_Call, Car\_Door\_Status, Car\_Door\_Command and Landing\_Door\_Status array corresponds to the number of car doors present in the lift car and all are of same size.

Test Concept: Above properties will be verified for the array index 0 equals the number of car doors present in the Lift (L1). If change of car door size is possible, change and REPEAT all the steps else skip. If any of above properties are not present, then skip and proceed with the test for available properties.

# Test Steps:

- 1. VERIFY (L1), Car Door Text = (Number of car doors present in the Lift), ARRAY INDEX = 0
- 2. VERIFY (L1), Assigned Landing Calls = (Number of car doors present in Lift), ARRAY INDEX = 0
- 3. VERIFY (L1), Making Car Call = (Number of car doors present in the Lift), ARRAY INDEX = 0
- 4. VERIFY (L1), Registered Car Call = (Number of car doors present in the Lift), ARRAY INDEX = 0
- 5. VERIFY (L1), Car Door Status = (Number of car doors present in the Lift), ARRAY INDEX = 0
- 6. VERIFY (L1), Car Door Command = (Number of car doors present in the Lift), ARRAY INDEX = 0
- 7. VERIFY (L1), Landing Door Status = (Number of car doors present in the Lift), ARRAY INDEX = 0
- 8. CHECK (Array index 0 of all these properties shall be same)

### 7.3.2.X47.12 Landing\_Door\_Status Tracks Car\_Door\_Status Test

Purpose: To verify that the status of Car\_Door\_Status property of lift is as same as that of the Landing\_Door\_Status property at a particular floor.

Test Concept: Car\_Door\_Status property of Lift (L1) object is subjected for different BACnetDoorStatus provided by changing the door status of real time lift connected to IUT or writing to it. The door side and floor number of the lift is considered in this case. The Landing\_Door\_Status property value at a specified array index (door size) for a particular floor (where lift car is currently present) is checked to verify that it is same as that of the status provided to Car Door Status property. If Landing Door Status property is not present, then this test shall be skipped.

Configuration Requirements: For below steps 'Array Index' = (any valid value N;  $1 \le N \le$  number of doors of a car). Y = (any valid floor number of the lift connected to the IUT). Tester shall select any value X for Car\_Door\_Status supported by IUT.

#### Test Steps:

 IF (Car\_Door\_Status is writable) THEN WRITE (L1), Car\_Door\_Status = X, ARRAY INDEX = N ELSE
 MAKE (C = D = Status (U = SX) ADDAY DIDEX = N

MAKE (Car\_Door\_Status = (Value of X), ARRAY INDEX = N)

- 2. VERIFY (L1), Car\_Door\_Status = X, ARRAY INDEX = N
- 3. VERIFY (L1), Car\_Position = Y,
- 4. VERIFY (L1), Landing\_Door\_Status = X, ARRAY INDEX = N
- 5. CHECK (Landing\_Door\_Status property value is X only for the Universal floor number Y)

# 7.3.2.X47.13 Highest Universal floor number linking to Car\_Position and Next\_Stopping\_Floor properties

Purpose: This test verifies that the highest universal floor number of the Lift object can be the maximum value of above properties depending on the floor numbers

Test Concept: Lift Object (L1) Properties Car\_Position and Next\_Stopping\_Floor will be written with the value of highest universal floor number and greater. If there is a physical lift or any alternate way for changing the highest universal floor number, change and REPEAT all the steps else omit. If any of the dependable properties are not writable, then skip the specific property from the test.

This test shall be skipped if Floor\_Text property is not present.

Configuration Requirements: For below steps 'Property Value' = (Y = highest universal floor number of the lift connected to the IUT). If Next\_Stopping\_Floor property is not present, then respective steps shall be skipped.

Test Steps:

- 1. VERIFY (L1), Floor Text = Y, ARRAY INDEX = 0
- 2. IF (Car\_Position is writable) THEN WRITE (L1), Car\_Position = Y VERIFY (L1), Car\_Position = Y
- TRANSMIT WriteProperty-Request, 'Object Identifier' = (L1), 'Property Identifier' = Car\_Position, 'Property Value' = Y+1
- 4. RECEIVE BACnet-Error-PDU,
  'Error Class' = PROPERTY,
  'Error Code' = VALUE OUT OF RANGE
- 5. IF (Next\_Stopping\_Floor is writable) THEN WRITE (L1), Next\_Stopping\_Floor = Y VERIFY (L1), Next\_Stopping\_Floor = Y
- 6. TRANSMIT WriteProperty-Request, 'Object Identifier' = (L1), 'Property Identifier' = Next\_Stopping\_Floor, 'Property Value' = Y+1
- 7. RECEIVE BACnet-Error-PDU, 'Error Class' = PROPERTY, 'Error Code' = VALUE\_OUT\_OF\_RANGE

# 7.3.2.X47.14 Highest Universal floor number linking to Assigned\_Landing\_Calls, Making\_Car\_Call and Registered\_Car\_Call properties

Purpose: This test verifies that the highest universal floor number of the Lift object can be the maximum value of above properties depending on the floor numbers

Test Concept: Lift Object (L1) Properties Assigned\_Landing\_Calls, Making\_Car\_Call and Registered\_Car\_Call will be written with the value of highest universal floor number and greater. If there is a physical lift or any alternate way for changing the highest universal floor number, change and REPEAT all the steps else omit. If any of the dependable properties are not writable, then skip the specific property from the test. This test shall be skipped if Floor\_Text property is not present.

Configuration Requirements: For below steps 'Array Index' = (any valid value N;  $1 \le N \le$  number of doors of a car) and 'Property Value' = (Y = highest universal floor number of the lift). If any of the dependable properties are not writable, then MAKE Out\_Of\_Service TRUE and then write, else skip the specific property from the test.

- 1. VERIFY (L1), Floor Text = Y, ARRAY INDEX = 0
- IF (Making\_Car\_Call is writable) THEN WRITE (L1), Making\_Car\_Call = Y, ARRAY INDEX = N VERIFY (L1), Making\_Car\_Call = Y, ARRAY INDEX = N,
- TRANSMIT WriteProperty-Request, 'Object Identifier' = (L1), 'Property Identifier' = Making\_Car\_Call, 'Property Value' = Y+1
- 4. RECEIVE BACnet-Error-PDU, 'Error Class' = PROPERTY,

'Error Code' = VALUE OUT OF RANGE 5. IF (Registered Car Call is writable) THEN WRITE ( $\overline{L1}$ ), Registered Car Call = Y, ARRAY INDEX = N 6. VERIFY (L1), Registered Car Call = Y, ARRAY INDEX = N, 7. TRANSMIT WriteProperty-Request. 'Object Identifier' = (L1), 'Property Identifier' = Registered Car Call, 'Property Value' = Y+1 8. RECEIVE BACnet-Error-PDU, 'Error Class' = PROPERTY, 'Error Code' = VALUE OUT OF RANGE 9. IF (Assigned Landing Call is writable) THEN WRITE (L1), Assigned Landing Call = (Y, at Z Direction), ARRAY INDEX = N 10. VERIFY (L1), Assigned Landing Call = (Y, at Z Direction), ARRAY INDEX = N 11. TRANSMIT WriteProperty-Request, 'Object Identifier' = (L1), 'Property Identifier' = Assigned Landing Call, 'Property Value' = (Y+1, at Z Direction) 12. RECEIVE BACnet-Error-PDU, 'Error Class' = PROPERTY, 'Error Code' = VALUE OUT OF RANGE

7.3.2.X47.15 Energy Meter Ref Property Tests

Purpose: To verify linking of Energy\_Meter property and Energy\_Meter\_Ref property.

Test Concept: If the Energy\_Meter\_Ref property of Lift object (L1) is present and initialized (contains an instance other than 4194303), then the Energy\_Meter property, if present, shall have a value of 0.0. If Energy\_Meter\_Ref is present and is un-initialized, then the value of Energy Meter property shall have any valid value.

Test Steps:

1. IF (Energy\_Meter\_Ref is present and initialized with instance other than 4194303) THEN VERIFY Energy\_Meter = 0.0

ELSE

VERIFY Energy Meter = (Any Valid Value)

#### 7.3.2.X47.16 Higher\_Deck and Lower\_Deck Tests

Purpose: To verify that the Higher\_Deck and Lower\_Deck property of the Lift Object is referencing the Lift object that refers the car deck above and below the car deck represented by this Lift object.

Test Concept: The IUT under test is configured to have a 3-deck lift having 3 Lift Objects. The Higher\_Deck and Lower\_Deck Property of the Lift object is then read to verify that it is representing the correct Lift Object instances. If there is no higher deck or lower deck, then the object instance shall be 4194303.

Configuration Requirements: The IUT under test is configured to have a 3-deck lift having 3 Lift Object instances: higher deck (L1), middle deck (L2) and lower deck (L3). If the IUT have 2 Deck lift having 2 Lift Objects, then the test steps shall be modified accordingly and executed.

- 1. VERIFY (L1), Higher\_Deck = (OBJECT, 4194303),
- 2. VERIFY (L1), Lower\_Deck = (L2),
- 3. VERIFY (L2), Higher Deck = (L1),
- 4. VERIFY (L2), Lower\_Deck = (L3),

- 5. VERIFY (L3), Higher\_Deck = (L2),
- 6. VERIFY (L3), Lower\_Deck = (OBJECT, 4194303)

# 7.3.2.X47.17 Linking of Assigned\_Landing\_Calls property of Lift Object to Landing\_Calls property of Elevator Group

Purpose: To verify that the Landing\_Calls property of Elevator Group also represents the active calls present in the Assigned\_Landing\_Calls property of the Lift object.

Test Concept: An Elevator Group is available, supports Landing\_Calls property, and it contains at least one Lift object within this group. Assigned\_Landing\_Calls property of the Lift is updated with the Floor number and direction for the lift. Landing\_Calls property of the Elevator Group object shall have the value as per the Assigned\_Landing\_Calls represented by this Lift object. For implementations where it is not possible to write to Assigned\_Landing\_Calls, this test shall be skipped.

Configuration Requirements: The Lift (L1) should be present in the Group\_Members property of Elevator Group (EG1). Lowest universal floor number of the lift < A < Highest universal floor number of the lift. Lowest universal floor number of the lift. B = (UP | DOWN | UP\_AND\_DOWN) and C = (B | UP\_AND\_DOWN).

Test Steps:

- 1. IF (Assigned\_Landing\_Calls is writable) THEN
- WRITE Assigned\_Landing\_Calls = (Floor Number A, Direction B)
- 2. VERIFY (L1), Assigned\_Landing\_Calls = (Floor Number A, Direction B)
- 3. VERIFY (EG1), Landing\_Calls = (Floor Number A, Direction C | Destination X)

Notes to Tester: Landing\_Calls property may contain other entries from same lift or different lifts connected under same Elevator Group.

[Elevator Group, Escalator, and Lift Object Tests] [In BTL Specified Tests, add to Clause 8.4.X9]

# 8.4.X9 CHANGE\_OF\_RELIABILITY Tests

# 8.4.X9.13 CHANGE\_OF\_RELIABILITY with FAULT\_LISTED Algorithm (ConfirmedEventNotification)

Purpose: To verify the correct operation of the FAULT LISTED event algorithm.

Test Concept: Select a fault detecting object O1 which is configured to use the FAULT\_LISTED algorithm. Ensure that no other fault conditions exist in the object. Set pMonitoredList to FV1, any value whose presence in the list property indicates a FAULT\_LISTED fault condition. Verify the correct transition is generated. The fault condition is removed by setting pMonitoredList to empty, a value which indicates NO\_FAULT\_DETECTED and verify the correct transition is generated.

Configuration Requirements: O1 is configured to detect faults and to report those using confirmed event notifications. O1 is initially configured to have no fault conditions present, and has an Event\_State of NORMAL. FV1 is a value for pMonitoredList which indicates a fault condition, and an empty pMonitoredList does not indicate a fault condition.

Test Steps:

- 1. VERIFY pCurrentReliability = NO FAULT DETECTED
- 2. VERIFY Event State = NORMAL
- 3. IF (pMonitoredList is writable) THEN

WRITE pMonitoredList = FV1

ELSE

- MAKE (pMonitoredList = FV1)
- 4. BEFORE Notification Fail Time
  - RECEIVE ConfirmedEventNotification-Request,

'Process Identifier' =	(any valid process Identifier),
'Initiating Device Identifier' =	IUT
'Event Object Identifier' =	01
'Time Stamp' =	(the current local time or sequence number),
'Notification Class' =	(the notification class configured for O1),
'Priority' =	(the value configured for the transition),
'Event Type' =	CHANGE_OF_RELIABILITY,
'Message Text' =	(optional, any valid message text),
'Notify Type' =	ALARM   EVENT,
AckRequired' =	TRUE   FALSE,
'From State' =	NORMAL,
'To State' =	FAULT,
'Event Values' =	(FAULT_LISTED,
	(T, T, ??),
	(A list of valid values for properties required to be reported

for O1, and 0 or more other properties of O1)

- 5. TRANSMIT BACnet-SimpleACK-PDU
- 6. VERIFY pCurrentReliability = FAULTS LISTED
- 7. VERIFY Event State = FAULT
- 8. IF (pMonitoredList is writable) THEN WRITE pMonitoredList = {}

ELSE

- MAKE (pMonitoredList = {})
- 9. BEFORE Notification Fail Time RECEIVE ConfirmedEventNotification-Request,

'Process Identifier' =	(any valid process Identifier),
'Initiating Device Identifier' =	IUT
'Event Object Identifier' =	01
'Time Stamp' =	(the current local time or sequence number),
'Notification Class' =	(the notification class configured for O1),
'Priority' =	(the value configured for the transition),
'Event Type' =	CHANGE OF RELIABILITY,
'Message Text' =	(optional, any valid message text),
'Notify Type' =	ALARM   EVENT,
'AckRequired' =	TRUE   FALSE,
'From State' =	FAULT,
'To State' =	NORMAL,
'Event Values' =	( NO_FAULT_DETECTED,
	(F, F, ??),
	(A list of valid values for properties required to be reported
	for O1, and 0 or more other properties of O1)

10. TRANSMIT BACnet-SimpleACK-PDU

11. pCurrentReliability = NO FAULT DETECTED

12. VERIFY Event\_State = NORMAL

[Elevator Group, Escalator, and Lift Object Tests] [In BTL Specified Tests, add to Clause 8.5.X9]

# 8.5.X9 CHANGE\_OF\_RELIABILITY Tests

# 8.5.X9.14 CHANGE\_OF\_RELIABILITY with FAULT\_LISTED Algorithm (UnconfirmedEventNotification)

Purpose: To verify the correct operation of the FAULT\_LISTED event algorithm.

Test Concept: Select a fault detecting object O1 which is configured to use the FAULT\_LISTED algorithm. Ensure that no other fault conditions exist in the object. Set pMonitoredList to FV1, any value whose presence in the list property indicates a FAULT\_LISTED fault condition. Verify the correct transition is generated. The fault condition is removed by setting pMonitoredList to empty which indicates NO\_FAULT\_DETECTED and verify the correct transition is generated.

Configuration Requirements: O1 is configured to detect faults and to report those using unconfirmed event notifications. O1 is initially configured to have no fault conditions present, and has an Event\_State of NORMAL. FV1 is a value for pMonitoredList which indicates a fault condition, and an empty pMonitoredList does not indicate a fault condition.

Test Steps: The test steps for this test case are identical to the test steps in 'Change\_Of\_Reliability with FAULT\_LISTED Algorithm (ConfirmedEventNotification)' except that the ConfirmedEventNotification requests are UnconfirmedEventNotification requests and the TD does not acknowledge receiving the notifications.

# 8.5.X9.15 CHANGE\_OF\_RELIABILITY FAULT-to-FAULT transitions in FAULT\_LISTED

Purpose: To verify the correct operation of FAULT-to-FAULT transitions in FAULT\_LISTED event algorithm.

Test Concept: Select a fault detecting object O1 which is configured to use the FAULT\_LISTED algorithm. Ensure that a fault condition exists in the object. Set pMonitoredList to FV1, any set of non-empty values different from the current set of values. Verify the correct transition is generated. The fault condition is removed by setting pMonitoredList to empty, a value which indicates NO\_FAULT\_DETECTED and verify the correct transition is generated.

Configuration Requirements: O1 is configured to detect faults and to report those using unconfirmed event notifications. O1 is initially configured to have a fault conditions present by pMonitoredList containing a non-empty value, and has an Event State of FAULT. FV1 is a value or set of values for pMonitoredList, and which the IUT will support in the pMonitoredList value. An empty pMonitoredList does not indicate a fault condition.

Test Steps:

- 1. VERIFY pCurrentReliability = FAULTS LISTED
- VERIFY Event State = FAULT 2.
- IF (pMonitoredList is writable) THEN 3.
  - WRITE pMonitoredList = FV1

ELSE

MAKE (pMonitoredList = FV1)

### 4. BEFORE Notification Fail Time

RECEIVE UnconfirmedEventNotification-Request,

'Process Identifier' =	(any valid process Identifier),
'Initiating Device Identifier' =	IUT
'Event Object Identifier' =	O1
'Time Stamp' =	(the current local time or sequ
'Notification Class' =	(the notification class configu
'Priority' =	(the value configured for the t
'Event Type' =	CHANGE_OF_RELIABILIT
'Message Text' =	(optional, any valid message t
'Notify Type' =	ALARM   EVENT,
'AckRequired' =	TRUE   FALSE,
'From State' =	FAULT,
'To State' =	FAULT,
'Event Values' =	(FAULT_LISTED,

)1 he current local time or sequence number), he notification class configured for O1), he value configured for the transition), CHANGE OF RELIABILITY, optional, any valid message text), LARM | EVENT, RUE | FALSE, AULT, AULT, FAULT LISTED, (T, T, ??),

(A list of valid values for properties required to be reported for O1, and 0 or more other properties of O1)

- 5. VERIFY pCurrentReliability = FAULTS LISTED
- VERIFY Event State = FAULT 6.
- 7. IF (pMonitoredList is writable) THEN WRITE pMonitoredList = {}

#### ELSE

MAKE (pMonitoredList = {})

BEFORE Notification Fail Time 8.

#### RECEIVE UnconfirmedEventNotification-Request,

'Process Identifier' = (any valid process Identifier), IUT 'Initiating Device Identifier' = 'Event Object Identifier' = 01 'Time Stamp' = (the current local time or sequence number), 'Notification Class' = (the notification class configured for O1), 'Priority' = (the value configured for the transition), 'Event Type' = CHANGE OF RELIABILITY, 'Message Text' = (optional, any valid message text), 'Notify Type' = ALARM | EVENT, 'AckRequired' = TRUE | FALSE, 'From State' = FAULT, 'To State' = NORMAL, 'Event Values' = ( NO FAULT DETECTED, (F, F, ??),

(A list of valid values for properties required to be reported for O1, and 0 or more other properties of O1)

)

# 9. VERIFY pCurrentReliability = NO FAULT DETECTED

10. VERIFY Event State = NORMAL

[Alarm and Event Management - Access Control - B Tests] [In BTL Specified Tests, add clause 8.4.X11]

# 8.4.X11 ACCESS\_EVENT Test (ConfirmedEventNotification)

Reason for Change: Add testing for ACCESS\_EVENT algorithm.

Purpose: To verify the correct operation of the ACCESS\_EVENT event algorithm.

Test Concept: The object, O1, begins the test in a NORMAL state. An access event, of a type listed in pAccessEvents is made to occur. It is verified that the IUT sends a confirmed notification of type ACCESS\_EVENT. A second access event, of a type not listed in pAccessEvents, is made to occur, if such is supported by the IUT. It is verified that no notification is generated. A third access event, of a type listed in pAccessEvents is made to occur. It is verified that the IUT sends a confirmed notification of type ACCESS\_EVENT.

Configuration Requirements: The IUT shall be configured such that the Event\_Enable property has a value of TRUE for TO-NORMAL transitions. The Issue\_Confirmed\_Notifications property shall have a value of TRUE. The event-generating object shall be in a NORMAL state at the start of the test. pAccessEvents shall be configured with at least 1 access event type that can be made to occur. If possible, at least access event type that can be made to occur shall not be included in pAccessEvents.

Test Steps:

```
-- Cause an access-event to occur that should be reported
```

- 1. VERIFY O1, Event\_State = NORMAL
- 2. MAKE(an access event occur which is listed in pAccessEvents)
- 3. BEFORE Notification Fail Time

RECEIVE ConfirmedEventNotification-Reque	est,
--	------

-		anon nequest,
	'Process Identifier' =	(the configured process ID),
	'Initiating Device Identifier' =	IUT,
	'Event Object Identifier' =	01,
	'Time Stamp' =	(Tnormal1: the current local time),
	'Notification Class' =	(the configured notification class),
	'Priority' =	(the value configured for a TO-NORMAL transition),
	'Event Type' =	ACCESS_EVENT,
	'Notify Type' =	EVENT   ALARM,
	'AckRequired' =	TRUE   FALSE,
	'From State' =	NORMAL,
	'To State' =	NORMAL,
	'Event Values' =	{ pMonitoredValue, pStatusFlags, pAccessEventTag,
		pAccessEventType, pAccessCredential
		and optionally pAuthenticationFactor

- 6. TRANSMIT BACnet-SimpleACK-PDU
- 7. VERIFY O1, Status Flags = (FALSE, FALSE,?,?)
- 8. VERIFY O1, Event\_State = NORMAL
- 9. VERIFY O1, Event\_Time\_Stamps = (\*, \*, Tnormal1)

-- Cause an access-event to occur that should not be reported

10. IF (the IUT can detect access events which are not in pAccessEvents) THEN { MAKE(an access event occur which is not listed in pAccessEvents)

CHECK(no notification is generated)

```
}
```

- 11. VERIFY O1, Status\_Flags = (FALSE, FALSE,?,?)
- 12. VERIFY O1, Event\_State = NORMAL
- 13. VERIFY O1, Event\_Time\_Stamps = (\*, \*, Tnormal1)

-- Cause an access-event to occur that should be reported

- 14. MAKE(an access event occur which is listed in pAccessEvents, and if possible different from the first access event )
- **15. BEFORE Notification Fail Time**

RECEIVE ConfirmedEventNotification-Request,

'Process Identifier' =	(the configured process ID),
'Initiating Device Identifier' =	IUT,
'Event Object Identifier' =	01,
'Time Stamp' =	(Tnormal2: the current local time),
'Notification Class' =	(the configured notification class),
'Priority' =	(the value configured for a TO-NORMAL transition),
'Event Type' =	ACCESS_EVENT,
'Notify Type' =	EVENT   ALARM,
'AckRequired' =	TRUE   FALSE,
'From State' =	NORMAL,
'To State' =	NORMAL,
'Event Values' =	{ pMonitoredValue, pStatusFlags, pAccessEventTag,
	pAccessEventType, pAccessCredential
	and optionally pAuthenticationFactor
	}

16. TRANSMIT BACnet-SimpleACK-PDU

17. VERIFY O1, Status Flags = (FALSE, FALSE,?,?)

- 18. VERIFY O1, Event State = NORMAL
- 19. VERIFY O1, Event Time Stamps = (\*, \*, Tnormal2)

Notes to Tester: The 'Message Text' parameter is omitted in the test description because it is optional. The IUT may include this parameter in the notification messages. The time stamps indicated by "\*" can have a value that indicates an unspecified time or a time that precedes the timestamp of the first received notification.

[Alarm and Event Management - Access Control - B Tests] [In BTL Specified Tests, add clause 8.5.X11]

#### 8.5.X11 ACCESS\_EVENT Test (UnconfirmedEventNotification)

Reason for Change: Add testing for ACCESS\_EVENT algorithm.

Purpose: To verify the correct operation of the ACCESS EVENT event algorithm.

Test Concept: The object, O1, begins the test in a NORMAL state. An access event, of a type listed in pAccessEvents is made to occur. It is verified that the IUT sends a confirmed notification of type ACCESS\_EVENT. A second access event, of a type not listed in pAccessEvents, is made to occur, if such is supported by the IUT. It is verified that no notification is generated. A third access event, of a type listed in pAccessEvents is made to occur. It is verified that the IUT sends a confirmed notification of type ACCESS\_EVENT.

Configuration Requirements: The IUT shall be configured such that the Event\_Enable property has a value of TRUE for TO-NORMAL transitions. The Issue\_Confirmed\_Notifications property shall have a value of TRUE. The event-generating object shall be in a NORMAL state at the start of the test. pAccessEvents shall be configured with at least 1 access event type that can be made to occur. If possible, at least access event type that can be made to occur shall not be included in pAccessEvents.

Test Steps: The test steps for this test case are identical to the test steps in 8.4.X11 except that the event notification requests are UnconfirmedEventNotification requests and the TD does not acknowledge receiving the notifications.

Notes to Tester: The passing results for this test case are identical to the ones in 8.4.X11 except that the event notifications shall be conveyed using an UnconfirmedEventNotification service request.

[Audit Reporting Tests -- copied from TP 18 Slave Proxy tests in Addendum 16.1-misc1] [Add clause 8.18.X1 into BTL Specified Tests]

### 8.18 ReadRange Service Initiation Tests

### 8.18.X1 Reading and Presenting Large List Properties

Reason for Change: there is no appropriate test for reading and presenting large list property values as required by DM-SP-VM-A.

Purpose: This test case verifies that the IUT is capable of reading and presenting large list properties using ReadRange. It is a generic test used to test data presentation requirements.

Configuration: For this test, the tester shall choose a list property, P1, from an object, O1. The TD shall be configured to not support segmentation. The value is P1 shall be too large to read via ReadProperty or ReadPropertyMultiple.

Test Steps:

1. MAKE (the IUT read P1)

WHILE (the complete list has not been	read)	
RECEIVE ReadRange-Request,		
'Object Identifier' =		O1,
'Property Identifier' =	P1,	
'Range' =		(any valid value for P1)
TRANSMIT BACnet-ComplexAC	CK-PDU,	
'Object Identifier' =		O1,
'Property Identifier' =	P1,	
'Result Flags' =		(values consistent with the request),
'Item Count' =		(values consistent with the request),
'Item Data' =	(values	consistent with the request)
	WHILE (the complete list has not been RECEIVE ReadRange-Request, 'Object Identifier' = 'Range' = TRANSMIT BACnet-ComplexAC 'Object Identifier' = 'Property Identifier' = 'Result Flags' = 'Item Count' = 'Item Data' =	WHILE (the complete list has not been read) RECEIVE ReadRange-Request, 'Object Identifier' = 'Property Identifier' = P1, 'Range' = TRANSMIT BACnet-ComplexACK-PDU, 'Object Identifier' = P1, 'Object Identifier' = P1, 'Result Flags' = 'Item Count' = 'Item Data' = (values)

3. CHECK (that the IUT presents a list of values that is consistent with the values received in step 2)

Notes to Tester: The value presented by the IUT may differ from the value transmitted on the wire due to rounding, truncation, formatting, language conversion, etc.

Notes to Tester: If the IUT has not already determined that the value cannot be read using ReadProperty or ReadPropertyMultiple, the IUT may initiate a ReadProperty or ReadPropertyMultiple. If this occurs, the IUT shall pass the test only if it automatically falls back to using ReadRange upon receipt of the correct BACnetReject-PDU from the TD, indicating that the response is too large.

[ Audit Reporting Tests ] [ Insert clause 8.X ]

# 8.X AuditLogQuery Initiation Tests

This clause defines the tests necessary to demonstrate support for initiating AuditLogQuery service requests.

#### 8.X.1 Query and Present Audit Log Records By Source

Reason for Change: no tests exist for the functionality.

Purpose: To verify that the IUT correctly initiates AuditLogQuery requests and presents the results.

Test Concept: The TD is setup with an AuditLog containing content from multiple sources and for multiple targets. The audit log contains example entries of all possible operations (see clause 19.Y.5) for audit source S1 with a mix of success and failure entries. The IUT is made to request and display the contents of the Audit Log for source S1. The results are verified that they match the content of the log.

Test Configuration:

<move the log description here>

Test Steps:

1.	1. WHILE (the IUT has not retrieved and displayed all entries for S1) MAKE (the IUT request more content from the Audit Log)		
	RECEIVE AuditLogQuery-Request		
	'Audit Log' =	(the audit log in the TD),	
	'Query Parameters' =	(a valid Audit Query by Source query including S1 as	
		the source),	
	'Start At Sequence Number' =	(any valid value)	
	'Requested Count' =	(any valid value)	
	TRANSMIT AuditLogQuery-Result		
	'Audit Log' =	(the audit log in the TD),	
	'Records' =	(the set of audit log records which match the query	
		and which fit within the accepted response size),	
	'No More Items' =	(TRUE if the last item is included, FALSE otherwise)	
2			

2. CHECK(that the displayed content matches audit records returned and that the complete records are presented)

Notes to Tester: If manual interaction is required between subsequent AuditLogQuery requests, checking of the displayed content might need to be performed before the manual interaction is taken instead of at the end of retrieving all of the items.

# 8.X.2 Query and Present Audit Log Records By Target

Reason for Change: no tests exist for the functionality.

Purpose: To verify that the IUT correctly initiates AuditLogQuery requests and presents the results.

Test Concept: TD is setup as an audit logger with an Audit Log. The IUT is made to request and display the contents of the Audit Log for target T1. The results are verified that they match the content of the log.

Test Configuration: The TD is setup with an AuditLog containing content from multiple sources and for multiple targets. The audit log contains example entries of all possible operations (see clause 19.Y.5) for audit target T1 with a mix of success and failure entries.

1.	WHILE (the IUT has not retrieved and displayed all entries for T1)		
	MAKE (the IUT request more content from the Audit Log)		
	RECEIVE AuditLogQuery-Request		
	'Audit Log' =	(the audit log in the TD),	
	'Query Parameters' =	(a valid Audit Query by Target query including T1 as	
		the target),	
	'Start At Sequence Number' =	(any valid value)	
	'Requested Count' =	(any valid value)	
	TRANSMIT AuditLogQuery-Result		
	'Audit Log' =	(the audit log in the TD),	
	'Records' =	(the set of audit log records which match the query	

'No More Items' =

and which fit within the accepted response size),

(TRUE if the last item is included, FALSE otherwise)

2. CHECK(that the displayed content matches audit records returned and that the complete records are presented)

Notes to Tester: If manual interaction is required between subsequent AuditLogQuery requests, checking of the displayed content might need to be performed before the manual interaction is taken instead of at the end of retrieving all of the items.

[WriteGroup Tests]

[In BTL Specified Tests, add clause 8.X WriteGroup Service Initiation Tests]

### 8.X2 WriteGroup Service Initiation Tests

This clause defines the tests necessary to demonstrate support for initiating WriteGroup service requests.

BACnet Reference Clause: 15.11.

### 8.X2.1 Broadcasting to a Group of Channel Objects

Purpose: Verify that the IUT can initiate a WriteGroup request to an arbitrary group with an arbitrary channel number.

Test Concept: Make the IUT perform a WriteGroup request to a tester selected group and channel. Verify that the request is generated.

Test Steps:

1. MAKE(the IUT initiate a	WriteGroup request to	group G and Channel C)
----------------------------	-----------------------	------------------------

2. RECEIVE WriteGroup-Request

DESTINATION =	GLOBAL BROADCAST   LOCAL BROADCAST
	REMOTE BROADCAST   TD,
'Group Number' =	G,
'Write Priority' =	(any valid value),
'Change List' =	(a valid list of 1 or more changes which impact channel C),
'Inhibit Delay' =	(absent or TRUE or FALSE)

[Network Port Object Tests] [Add into clause 9.18.1]

#### 9.18 ReadProperty Service Execution Tests

# 9.18.1 Positive ReadProperty Service Execution Tests

#### 9.18.1.X5 ReadProperty of the Network Port Object using the Unknown Instance

Purpose: Verify that the IUT selects the correct object when it receives Network Port with special object instance of 4194303.

Test Concept: Execute a Read service request specifying 'Object Identifier' = (Network Port, 4194303). The responding BACnet-user shall treat the Object Identifier as if it correctly matched the local Network Port object representing the network port through which the request was received.

Configuration Requirements: Let X be the instance numbers of Network Port object (can be same or different objects) for the IUT. If the Protocol\_Revision claimed is less than 17, this test shall be skipped.

1.	TRANSMIT ReadProperty-Request,	
	'Object Identifier' =	(Network Port, 4194303),
	'Property Identifier' =	Object-Identifier
2.	RECEIVE ReadProperty-ACK,	
	'Object Identifier' =	(Network Port, X),
	'Property Identifier' =	Object-Identifier,
	'Property Value' =	(Network Port, X)
3.	TRANSMIT ReadProperty-Request through the same port as above,	
	'Object Identifier' =	(Network Port, 4194303),
	'Property Identifier' =	(P: any valid property which is present in the same local Network Port object as
	above)	
4.	RECEIVE ReadProperty-ACK,	
	'Object Identifier' =	(Network Port, X),
	'Property Identifier' =	P,
	'Property Value' =	(value of P from the local Network Port object representing the network port through which the request was received)

Passing Result: The IUT shall respond as indicated conveying the value from a local Network Port object representing the network port through which the request was received.

[BACnet/IPv6 Tests] [Insert new Clause 12.X, p. 643]

# 12.X. BACnet/IPv6 Functionality Tests

This clause defines the tests necessary to demonstrate BACnet/IPv6 functionality, as defined in Annex U of the BACnet Standard. For each test case a sequence of one or more messages that are to be exchanged are described. A passing result occurs when the IUT and TD exchange messages as described in the test case. Any other combinations of messages constitute a failure of the test. Some test cases are not valid unless some other test defined in this standard has already been executed and the IUT passed this test. These dependencies are noted in the test case description.

For the tests in this clause references to the virtual address mean the 3-octet virtual address. For example, Source-Virtual-Address = TD means Source-Virtual-Address = (the 3-octet VMAC of TD).

#### 12.X.1 Common Tests

This group of tests verifies that a B/IPv6 device will respond correctly to incoming B/IPv6 messages. All B/IPv6 devices shall execute these tests.

Configuration Requirements: The IUT's Network Port object that represents the B/IPv6 port under test shall be configured as follows:

• BACnet\_IPv6\_Multicast\_Address is FF02::BAC0 (Link Local Multicast Address)

#### 12.X.1.1 Execute Original-Unicast-NPDU

Purpose: To verify that an IUT will process an Original-Unicast-NPDU message.

```
1. TRANSMIT DA = IUT, SA = TD,
Original-Unicast-NPDU,
Source-Virtual-Address = TD,
Destination-Virtual-Address = IUT,
ReadProperty-Request,
'Object Identifier' = X,
'Property Identifier' = Y
2. RECEIVE DA = TD, SA= IUT
```

Original-Unicast-NPDU, Source-Virtual-Address = IUT, Destination-Virtual-Address = TD, ReadProperty-ACK, 'Object Identifier' = X, 'Property Identifier' = Y

# 12.X.1.2 Execute Virtual-Address-Resolution

Purpose: To verify that an IUT will process a Virtual-Address-Resolution message.

Test Steps:

 TRANSMIT DA = IUT, SA = TD, Virtual-Address-Resolution, Source-Virtual-Address = TD
 RECEIVE DA = TD, Virtual-Address-Resolution-ACK, Source Virtual Address = UIT

Source-Virtual-Address = IUT, Destination-Virtual-Address = TD

# 12.X.2 IPv6 Normal Mode Tests

This group of tests verifies that a B/IPv6 device that is operating in normal mode (not a BACnet Broadcast Management Device (BBMD), and not a Foreign Device) will respond correctly to incoming B/IPv6 messages.

Configuration Requirements: The IUT's Network Port object that represents the B/IPv6 port under test shall be configured as follows:

- BACnet\_IPv6\_Mode is NORMAL
- BACnet\_IPv6\_Multicast\_Address is FF02::BAC0 (Link Local Multicast Address)

# 12.X.2.1 Positive Tests

# 12.X.2.1.1 Initiate Original-Broadcast-NPDU

Purpose: To verify that an IUT, operating in normal IPv6 mode, will correctly initiate an Original-Broadcast-NPDU message.

Test Steps:

1. MAKE(the IUT send a broadcast)

 RECEIVE DA=Link Local Multicast Address, SA = IUT Original-Broadcast-NPDU, Source-Virtual-Address = IUT, (any valid BACnet-Unconfirmed-Request-PDU, with any valid broadcast network options)

# 12.X.2.1.2 Execute Original-Broadcast-NPDU

Purpose: To verify that an IUT, operating in normal IPv6 mode, will process an Original-Broadcast-NPDU message.

Test Steps:

 TRANSMIT DA = B/IPv6 Link Local Multicast Address, SA = TD, Original-Broadcast-NPDU, Source-Virtual-Address = TD, Who-Is-Request
 IF (the IUT responds with Unicast I-Am) THEN RECEIVE DA = TD, SA = IUT,

```
Original-Unicast-NPDU,
Source-Virtual-Address = IUT,
```

```
Destination-Virtual-Address = TD,
I-Am-Request
ELSE
RECEIVE DA=Link Local Multicast Address, SA = IUT
Original-Broadcast-NPDU,
Source-Virtual-Address = IUT,
I-Am-Request
3. CHECK (The IUT does not issue any Forwarded-NPDUs)
12.X.2.1.3 Execute Forwarded-NPDU
```

Purpose: To verify that an IUT, operating in normal IPv6 mode, will process a Forwarded-NPDU.

# Test Steps:

```
    TRANSMIT DA = Link Local Multicast Address, SA = TD,
Forwarded-NPDU,
Original-Source-Virtual-Address = D2,
Original-Source-B/IPv6-Address = D2,
Who-Is-Request
    IF (the IUT responds with Unicast I-Am) THEN
RECEIVE DA = D2, SA = IUT,
Original-Unicast-NPDU,
Source-Virtual-Address = IUT,
Destination-Virtual-Address = D2,
I-Am-Request
    ELSE
RECEIVE DA=Link Local Multicast Address, SA = IUT
Original-Broadcast-NPDU,
```

```
RECEIVE DA=Link Local Multicast Address, SA = IUT
Original-Broadcast-NPDU,
Source-Virtual-Address = IUT,
I-Am-Request
3. CHECK (The IUT does not issue any Forwarded-NPDU BVLCs)
```

# 12.X.2.1.4 Execute Address-Resolution

Purpose: To verify that an IUT, operating in normal IPv6 mode, will process an Address-Resolution message.

Test Steps:

```
    TRANSMIT DA = B/IPv6 Link Local Multicast Address, SA = TD,
Address-Resolution,
Source-Virtual-Address = TD,
Target-Virtual-Address = IUT
    RECEIVE DA = TD,
Address-Resolution-ACK,
Source-Virtual-Address = IUT,
Destination-Virtual-Address = TD
```

3. CHECK (The IUT does not issue any Forwarded-Address-Resolution BVLCs)

# 12.X.2.1.5 Execute Forwarded-Address-Resolution

Purpose: To verify that an IUT, operating in normal IPv6 mode, will process a Forwarded-Address-Resolution message.

Test Concept: The TD, acting as a BBMD, sends a Forwarded-Address-Resolution message to the IUT on behalf of device D2. It is verified that the IUT responds to D2 with an Address-Resolution message.

1. TRANSMIT DA = IUT, SA = TD, Forwarded-Address-Resolution, Original-Source-Virtual-Address = D2, Target-Virtual-Address = IUT Original-Source-B/IPv6-Address = D2 2. RECEIVE DA = D2, SA = IUT Address-Resolution-ACK, Source-Virtual-Address = IUT, Destination-Virtual-Address = D2 3. CHECK (The IUT does not issue any Forwarded-Address-Resolution BVLCs).

# 12.X.2.2 Negative Tests

# 12.X.2.2.1 Reject Register-Foreign-Device

Purpose: To verify that an IUT, operating in normal IPv6 mode, will reject a Register-Foreign-Device request.

Test Steps:

 TRANSMIT DESTINATION = IUT, SA = TD, Register-Foreign-Device, Source-Virtual-Address = TD Time-To-Live = 60
 RECEIVE DESTINATION = TD, BVLC-Result, Source-Virtual-Address = IUT 'Result Code' = Register-Foreign-Device NAK

# 12.X.2.2.2 Reject Delete-Foreign-Device-Table-Entry

Purpose: To verify that an IUT, operating in normal IPv6 mode, will reject a Delete-Foreign-Device-Table-Entry request.

Test Steps:

 TRANSMIT DESTINATION = IUT, SA = TD, Delete-Foreign-Device-Table-Entry, Source-Virtual-Address = TD FDT Entry = TD
 RECEIVE DESTINATION = TD, BVLC-Result, Source-Virtual-Address = IUT 'Result Code' = Delete-Foreign-Device-Table-Entry NAK

# 12.X.2.2.3 Reject Distribute-Broadcast-To-Network

Purpose: To verify that an IUT, operating in normal IPv6 mode, will reject a Distribute-Broadcast-To-Network request.

Test Steps:

 TRANSMIT DESTINATION = IUT, SA = TD, Distribute-Broadcast-To-Network, Original-Source-Virtual-Address = TD Who-Is-Request
 RECEIVE DESTINATION = TD, BVLC-Result, Source-Virtual-Address = IUT 'Result Code' = Distribute-Broadcast-To-Network NAK

# 12.X.3 Foreign Device Tests

This group of tests verifies that a B/IPv6 device that is configured as a Foreign Device is able to register with a BBMD and send and receive broadcast messages through the BBMD.

Configuration Requirements: The IUT's Network Port object that represents the B/IPv6 port under test shall be configured as follows:

- BACnet\_IPv6\_Mode is FOREIGN
- BACnet\_IPv6\_Multicast\_Address is FF02::BAC0 (Link Local Multicast Address)

# 12.X.3.1 Positive Tests

# 12.X.3.1.1 Initiate Distribute-Broadcast-To-Network-NPDU

Purpose: To verify that an IUT, configured as a Foreign Device, will correctly initiate an Distribute-Broadcast-To-Network -NPDU message.

Configuration Requirements: The TD is operating as a BBMD, and the IUT has registered as a foreign device with it.

Test Steps:

- 1. MAKE(the IUT send a broadcast)
- 2. RECEIVE DA=IUT, SA = IUT

Distribute-Broadcast-To-Network-NPDU, Source-Virtual-Address = IUT, (any valid BACnet-Unconfirmed-Request-PDU, with any valid broadcast network options)

# 12.X.3.1.2 Execute Forwarded-NPDU

Purpose: To verify that an IUT, operating as a foreign device, will process a Forwarded-NPDU.

Configuration Requirements: The TD is operating as a BBMD, and the IUT has registered as a foreign device with it.

Test Steps:

```
1. TRANSMIT DA = IUT, SA = TD,
      Forwarded-NPDU,
      Original-Source-Virtual-Address = D2,
      Original-Source-B/IPv6-Address = D2,
      Who-Is-Request
2. If (the IUT responds with Unicast I-Am) THEN
      RECEIVE DA = D2, SA = IUT,
            Original-Unicast-NPDU,
            Source-Virtual-Address = IUT,
            Destination-Virtual-Address = D2,
            I-Am-Request
 ELSE
      RECEIVE DA=TD, SA = IUT
            Distribute-Broadcast-To-Network-NPDU,
            Source-Virtual-Address = IUT,
            I-Am-Request
3. CHECK (The IUT does not issue any Forwarded-NPDU BVLCs)
```

# 12.X.3.1.3 Execute Forwarded-Address-Resolution

Purpose: To verify that an IUT, operating as a foreign device, will process a Forwarded-Address-Resolution message.

Test Concept: The TD, acting as a BBMD, sends a Forwarded-Address-Resolution message to the IUT on behalf of device D2. It is verified that the IUT responds to D2 with an Address-Resolution message.

```
    TRANSMIT DA = IUT, SA = TD,
Forwarded-Address-Resolution,
Original-Source-Virtual-Address = D2,
Target-Virtual-Address = IUT
Original-Source-B/IPv6-Address = D2
    RECEIVE
DA = D2, SA = IUT
Address-Resolution-ACK,
Source-Virtual-Address = IUT,
Destination-Virtual-Address = D2
    CHECK (The IUT does not issue any Forwarded-Address-Resolution BVLCs)
```

# 12.X.3.2 Negative Tests

#### 12.X.3.2.1 Ignores Original-Broadcast-NPDU

Purpose: To verify that an IUT, operating as a foreign device, will not process an Original-Broadcast-NPDU message.

Test Steps:

```
    TRANSMIT DA = B/IPv6 Link Local Multicast Address, SA = D2,
Original-Broadcast-NPDU,
Source-Virtual-Address = D2,
Who-Is-Request
    CUEON (TE LARSE ADDRESS)
```

2. CHECK (The IUT does not issue any IAms in response)

#### 12.X.3.2.2 Ignore Address-Resolution

Purpose: To verify that an IUT, operating as a foreign device, will ignore multicast Address-Resolution messages.

Test Steps:

```
    TRANSMIT DA = B/IPv6 Link Local Multicast Address, SA = D2,
Address-Resolution,
Source-Virtual-Address = D2,
Target-Virtual-Address = IUT
    CHECK (The IUT does not issue any Address-Resolution-ACK BVLCs)
```

#### 12.X.3.2.3 Reject Register-Foreign-Device

Purpose: To verify that an IUT, operating as a foreign device, will reject a Register-Foreign-Device request.

Test Steps:

 TRANSMIT DESTINATION = IUT, SA = TD, Register-Foreign-Device, Source-Virtual-Address = TD Time-To-Live = 60
 RECEIVE DESTINATION = TD, BVLC-Result, Source-Virtual-Address = IUT 'Result Code' = Register-Foreign-Device NAK

# 12.X.3.2.4 Reject Delete-Foreign-Device-Table-Entry

Purpose: To verify that an IUT, operating as a foreign device, will reject a Delete-Foreign-Device-Table-Entry request.

Test Steps:

```
    TRANSMIT DESTINATION = IUT, SA = TD,
Delete-Foreign-Device-Table-Entry,
Source-Virtual-Address = TD
FDT Entry = TD
    RECEIVE DESTINATION = TD,
BVLC-Result,
Source-Virtual-Address = IUT
'Result Code' = Delete-Foreign-Device-Table-Entry NAK
```

# 12.X.3.2.5 Reject Distribute-Broadcast-To-Network

Purpose: To verify that an IUT, operating as a foreign device, will reject a Distribute-Broadcast-To-Network request.

Test Steps:

 TRANSMIT DESTINATION = IUT, SA = TD, Distribute-Broadcast-To-Network, Original-Source-Virtual-Address = TD Who-Is-Request
 RECEIVE DESTINATION = TD, BVLC-Result, Source-Virtual-Address = IUT 'Result Code' = Distribute-Broadcast-To-Network NAK

# 12.X.4 BBMD Tests

# 12.X.4.1 Positive Tests

This group of tests verifies that a B/IPv6 device that is configured as a BACnet Broadcast Management Device (BBMD) will correctly process incoming B/IPv6 messages that pertain to BBMDs. Only devices that are configured to support BBMD functionality shall execute these tests.

Configuration Requirements: The IUT's Network Port object that represents the B/IPv6 port under test shall be configured as follows:

- BACnet\_IPv6\_Mode is BBMD
- BACnet\_IPv6\_Multicast\_Address is FF02::BAC0 (Link Local Multicast Address)
- BBMD\_Broadcast\_Distribution\_Table shall contain:

bbmd-address
BBMD1
BBMD2
BBMD3

For purposes of these tests, TD shall be operating as BBMD1.

# 12.X.4.1.1 Original-Broadcast-NPDU

Purpose: To verify that the IUT, configured as a BBMD, will forward an Original-Broadcast-NPDU request.

Test Steps:

1. TRANSMIT

DA = B/IPv6 Link Local Multicast Address, SA = TD. Source-Virtual-Address = TD, Original-Broadcast-NPDU, Who-Is-Request 2. RECEIVE DA = BBMD1, SA = IUT.Forwarded-NPDU, Original-Source-Virtual-Address = TD Original-Source-B/IPv6-Address = TD Who-Is-Request **3. RECEIVE** DA = BBMD2,SA = IUT, Forwarded-NPDU, Original-Source-Virtual-Address = TD Original-Source-B/IPv6-Address = TD Who-Is-Request 4. RECEIVE DA = BBMD3, SA = IUT, Forwarded-NPDU, Original-Source-Virtual-Address = TD Original-Source-B/IPv6-Address = TD Who-Is-Request

# 12.X.4.1.2 Forwarded-NPDU

Purpose: To verify that the IUT, configured as a BBMD, will forward a Forwarded-NPDU request. Configuration Requirements: Register FD1 as a foreign device with the IUT. FD3 is a registered foreign device with BBMD1.

```
1. TRANSMIT
      DA = IUT.
      SA = BBMD1,
      Forwarded-NPDU,
      Source-Virtual-Address = FD3,
      Original-Source-B/IPv6-Address = FD3
      I-Am-Request
2. RECEIVE
      DA = B/IPv6 Link Local Multicast Address,
      SA = IUT
      Forwarded-NPDU,
      Source-Virtual-Address = FD3,
      Original-Source-B/IPv6-Address = FD3
      I-Am-Request
3. RECEIVE
      DA = FD1,
      SA = IUT
      Forwarded-NPDU,
      Source-Virtual-Address = FD3,
      Original-Source-B/IPv6-Address = FD3
      I-Am-Request
```

Notes to Tester: The order of the messages transmitted by the IUT is not significant.

### 12.X.4.1.3 Address-Resolution

Purpose: To verify that the IUT, configured as a BBMD, will process an Address-Resolution request when the target virtual address is not the virtual address of the IUT.

Configuration Requirements: TD shall be a registered foreign device (FD1) with the IUT.

1. TRANSMIT DA = IUT,SA = TD. Address-Resolution, Source-Virtual-Address = TD, Target-Virtual-Address = FD2 2. RECEIVE DA = B/IPv6 Link Local Multicast Address SA = IUT.Forwarded-Address-Resolution, Original-Source-Virtual-Address = TD, Target-Virtual-Address = FD2, Original-Source-B/IPv6-Address = TD **3. RECEIVE** DA = BBMD1, SA = IUT, Forwarded-Address-Resolution, Original-Source-Virtual-Address = TD, Target-Virtual-Address = FD2, Original-Source-B/IPv6-Address = TD 4. RECEIVE DA = BBMD2, SA = IUT, Forwarded-Address-Resolution, Original-Source-Virtual-Address = TD, Target-Virtual-Address = FD2, Original-Source-B/IPv6-Address = TD 5. RECEIVE DA = BBMD3, SA = IUT.Forwarded-Address-Resolution, Original-Source-Virtual-Address = TD, Target-Virtual-Address = FD2, Original-Source-B/IPv6-Address = TD 6. RECEIVE DA = FD2, SA = IUT, Forwarded-Address-Resolution, Original-Source-Virtual-Address = TD. Target-Virtual-Address = FD2, Original-Source-B/IPv6-Address = TD 7. TRANSMIT DA = TD, SA = FD2, Address-Resolution-ACK, Source-Virtual-Address = FD2, Destination-Virtual-Address = TD

Notes to Tester: The execution of step 7 is not significant, but is shown here in order to demonstrate the completion of the BVLC.

# 12.X.4.1.4 Forwarded-Address-Resolution

Purpose: To verify that the IUT, configured as a BBMD, will process a Forwarded-Address-Resolution request when the target virtual address is not the virtual address of the IUT.

Configuration Requirements: TD shall operate as BBMD1 and listed in the IUTs Broadcast Distribution Table.

```
1. TRANSMIT
      DA = IUT,
      SA = TD,
      Forwarded-Address-Resolution,
      Original-Source-Virtual-Address = FD1,
      Target-Virtual-Address = FD2
      Original-Source-B/IPv6-Address = FD1
2. RECEIVE
      DA = B/IPv6 Link Local Multicast Address,
      SA = IUT,
      Forwarded-Address-Resolution,
      Original-Source-Virtual-Address = FD1,
      Target-Virtual-Address = FD2,
      Original-Source-B/IPv6-Address = FD1
3. RECEIVE
      DA = FD2.
      SA = IUT.
      Forwarded-Address-Resolution,
      Original-Source-Virtual-Address = FD1,
      Target-Virtual-Address = FD2,
      Original-Source-B/IPv6-Address = FD1
4. TRANSMIT
      DA = TD,
      SA = FD2,
      Address-Resolution-ACK,
      Source-Virtual-Address = FD2.
      Destination-Virtual-Address = TD
```

Notes to Tester: The execution of step 7 is not significant, but is shown here in order to demonstrate the completion of the BVLC. The order of the messages transmitted by the IUT is not significant.

# 12.X.4.1.5 Distribute-Broadcast-To-Network

Purpose: To verify that the IUT, configured as a BBMD, will process a Distribute-Broadcast-To-Network request.

Configuration Requirements: Register FD1 as a foreign device with the IUT. FD2 is a registered foreign device with BBMD1. For purposes of this test, TD is acting as FD1.

Steps 1 6 are the processing of the Distributed-Broadcast-To-Network, Step 7 and on is the processing of the APDU service by the IUT.

 TRANSMIT DA = IUT, SA = FD1, Distribute-Broadcast-To-Network, Who-Is-Request
 RECEIVE DA = B/IPv6 Link Local Multicast Address,

SA = IUT, Forwarded-NPDU. Source-Virtual-Address = FD1, Original-Source-Virtual-Address = FD1, Who-Is-Request **3. RECEIVE** DA = BBMD1, SA = IUT.Forwarded-NPDU, Source-Virtual-Address = FD1, Original-Source-Virtual-Address = FD1, Who-Is-Request 4. RECEIVE DA = BBMD2, SA = IUT, Forwarded-NPDU, Source-Virtual-Address = FD1, Original-Source-Virtual-Address = FD1, Who-Is-Request 5. RECEIVE DA = BBMD3, SA = IUT, Forwarded-NPDU, Source-Virtual-Address = FD1, Original-Source-Virtual-Address = FD1, Who-Is-Request 6. RECEIVE DA = FD2, SA = IUT, Forwarded-NPDU, Source-Virtual-Address = FD1, Original-Source-Virtual-Address = FD1, Who-Is-Request 7. RECEIVE DA = B/IPv6 Link Local Multicast Address, SA = IUT.Original-Broadcast-NPDU, Original-Source-Virtual-Address = IUT, I-Am-Request 8. RECEIVE DA = BBMD1, SA = IUT, Forwarded-NPDU, Source-Virtual-Address = IUT, Original-Source-Virtual-Address = IUT, I-Am-Request 9. RECEIVE DA = BBMD2. SA = IUT, Forwarded-NPDU, Source-Virtual-Address = IUT, Original-Source-Virtual-Address = IUT, I-Am-Request 10. RECEIVE DA = BBMD3, SA = IUT, Forwarded-NPDU, Source-Virtual-Address = IUT,

```
Original-Source-Virtual-Address = IUT,
      I-Am-Request
11. RECEIVE
      DA = FD1,
      SA = IUT.
      Forwarded-NPDU,
      Source-Virtual-Address = IUT,
      Original-Source-Virtual-Address = IUT,
      I-Am-Request
12. RECEIVE
      DA = FD2.
      SA = IUT
      Forwarded-NPDU,
      Source-Virtual-Address = IUT,
      Original-Source-Virtual-Address = IUT,
      I-Am-Request
```

Notes to Tester: The order of the messages transmitted by the IUT is not significant.

# 12.X.4.2 Negative Tests

# 12.X.4.2.1 Reject Forwarded-NPDU

Purpose: To verify that the IUT, configured as a BBMD, will drop a Forwarded-NPDU request from a BBMD that's not in the IUT's BDT.

Configuration Requirements: Empty the IUT's BDT. FD3 is a foreign device registered with the IUT.

Test Steps:

 TRANSMIT DA = IUT, SA = BBMD1, Forwarded-NPDU, Source-Virtual-Address = FD3, Original-Source-B/IPv6-Address = FD3 I-Am-Request
 CHECK (The IUT does not issue any Forwarded-NPDU BVLCs)

# 12.X.4.2.2 Reject Address-Resolution

Purpose: To verify that the IUT, configured as a BBMD, will not process an Address-Resolution request when the target virtual address is not the virtual address of the IUT and the SA is not from a device registered with the IUT.

Configuration Requirements: TD shall not be a registered foreign device (FD1) with the IUT.

```
    TRANSMIT

            DA = IUT,
            SA = TD,
            Address-Resolution,
            Source-Virtual-Address = TD,
            Target-Virtual-Address = FD2

    RECEIVE

            DA = TD,
            SA = IUT
            BVLC-Result
            Address-Resolution NAK

    CHECK (The IUT does not issue any Forwarded-Address-Resolution BVLCs)
```
### 12.X.4.2.3 Reject Forwarded-Address-Resolution

Purpose: To verify that the IUT, configured as a BBMD, will not process a Forwarded-Address-Resolution request when the source a BBMD that is not present in the IUTs BDT.

Configuration Requirements: Empty the IUT's BDT.

TRANSMIT

 DA = IUT,
 SA = TD,
 Forwarded-Address-Resolution,
 Original-Source-Virtual-Address = FD1,
 Target-Virtual-Address = FD2
 Original-Source-B/IPv6-Address = FD1

 CHECK (The IUT does not issue any Forwarded-Address-Resolution BVLCs)

## 12.X.4.2.4 Reject Distribute-Broadcast-To-Network

Purpose: To verify that the IUT, configured as a BBMD, will not process a Distribute-Broadcast-To-Network request from a device that is not registered as a foreign device with the IUT.

Configuration Requirements: Ensure the TD is not registered as a foreign device with the IUT and that the TD is not listed in the IUTs FDT.

1. TRANSMIT

DA = IUT, SA = TD, Distribute-Broadcast-To-Network, Who-Is-Request

2. RECEIVE

DA = TD SA = IUT BVLC-Result Distribute-Broadcast-To-Network-NAK

### 12.X.4.3 Broadcast Distribution Table Operations

This group of tests verifies that a BACnet Broadcast Management Device will correctly perform BDT operations.

Configuration Requirements: The IUT's Network Port object that represents the B/IPv6 port under test shall be configured as follows:

• BACnet\_IPv6\_Mode is BBMD

# 12.X.4.3.1 Verify writability of the BDT

Purpose: To verify the contents of the broadcast distribution table.

1. TRANSMIT

WriteProperty-Request, 'Object Identifier' = (Network Port Object that represents this port), 'Property Identifier' = BBMD\_Broadcast\_Distribution\_Table 'Property Value' = (WrittenBDT: a list of valid BACnetBDTEntry)

### 2. RECEIVE

BACnetSimple-Ack,

3. READ ReadBDT = NP, BBMD\_Broadcast\_Distribution\_Table

4. CHECK(ReadBDT contains the same entries as WrittenBDT, but not necessarily in the same order)

### 12.X.5 Foreign Device Management Tests

This group of tests verifies that a BBMD with an FDT will correctly perform FDT operations.

Configuration Requirements: The IUT's Network Port object, NP, that represents the B/IPv6 port under test shall be configured as follows:

- BACnet\_IPv6\_Mode is BBMD
- BACnet\_IPv6\_Multicast\_Address is FF02::BAC0 (Link Local Multicast Address)
- BBMD\_Accept\_FD\_Registrations is TRUE.

The TD's Network Port object that represents the B/IPv6 port being used shall be configured as follows:

- BACnet\_IPv6\_Mode is FOREIGN
- BACnet\_IPv6\_Multicast\_Address is FF02::BAC0 (Link Local Multicast Address)

### 12.X.5.1 Execute Register-Foreign-Device

Purpose: To verify that the IUT, will handle a Register-Foreign-Device request.

Test Steps:

```
    TRANSMIT

            DA = IUT,
            SA = TD,
            Source-Virtual-Address = TD,
            Register-Foreign-Device,
            'Time-To-Live' = 60

    RECEIVE

            DA = TD,
            SA = IUT,
            Source-Virtual-Address = IUT,
            BVLC-Result,
            'Result Code' = 0
```

3. VERIFY NP, BBMD\_Foreign\_Device\_Table = ( (B/IPv6 address of FD2, 60, 90-execution time) )

### 12.X.5.2 Execute Delete-Foreign-Device-Table-Entry

Purpose: To verify that the IUT will handle a Delete-Foreign-Device-Table-Entry message when a valid FDT entry is supplied.

Configuration Requirements: The TD shall take the role of foreign device FD1. The IUT's FDT must be empty.

Test Steps:

```
1. TRANSMIT
      DA = IUT.
      SA = FD1,
      Source-Virtual-Address = FD1,
      Register-Foreign-Device,
      'Time-To-Live' = 60
2. RECEIVE
      DA = FD1,
      SA = IUT,
      Source-Virtual-Address = IUT,
      BVLC-Result,
      'Result Code' = 0
3. VERIFY NP, BBMD Foreign Device Table = ( (B/IPv6 address of FD1, 60, 90-execution time) )
4. TRANSMIT
      DA = IUT,
      SA = FD1,
      Source-Virtual-Address = FD1,
```

```
Delete-Foreign-Device-Table-Entry,

'FDT Entry' = FD1

5. RECEIVE

DA = FD1,

SA = IUT,

Source-Virtual-Address = IUT,

BVLC-Result,

'Result Code' = Successful completion

6. VERIFY NP, BBMD Foreign Device Table = ()
```

## 12.X.5.3 Foreign Device Table Timer Operations

### 12.X.5.3.1 Non-Zero-Duration Foreign Device Table Timer Operations

Purpose: To verify that the IUT will handle FDT timer operations: finite time Foreign Device registration, reregistration, adding grace period to the supplied Time-To-Live parameter and FDT entry clearing upon timer expiration.

Configuration Requirements: The TD shall take the role of foreign device FD2. The value of the IUT's BBMD\_Foreign\_Device Table must be empty.

Test Steps:

```
1. TRANSMIT
      DA = IUT,
      SA = FD2.
      Register-Foreign-Device,
      'Time-To-Live' = 60
2. RECEIVE
      DA = FD2,
      SA = IUT,
      BVLC-Result,
      'Result Code' = 0
3. VERIFY NP, BBMD Foreign Device Table = ( (B/IPv6 address of FD2, 60, 90-execution time) )
4. TRANSMIT
      DA = IUT,
      SA = FD2.
      Register-Foreign-Device,
      'Time-To-Live' = 40
5. RECEIVE
      DA = FD2,
      SA = IUT,
      BVLC-Result,
      'Result Code' = 0
6. WAIT (30 seconds)
7. VERIFY NP, BBMD Foreign Device Table = ( (B/IPv6 address of FD2, 40, 40-execution time) )
8. WAIT (50 seconds)
9. VERIFY NP, BBMD Foreign Device Table = ()
```

### 12.X.5.3.2 Zero-Duration Foreign Device Timer Operations

Purpose: To verify that the IUT will handle Foreign Device registration with Time-To-Live parameter equal to zero and clears FDT entry upon timer expiration.

Configuration Requirements: The TD shall take the role of foreign device FD2. The IUTs FDT must be empty.

Test Steps:

 TRANSMIT DA = IUT, SA = FD2, Register-Foreign-Device-Table, 'Time-To-Live' = 0
 RECEIVE DA = FD2, SA = IUT, BVLC-Result, 'Result Code' = 0
 WAIT (10 seconds)
 VERIFY NP, BBMD\_Foreign\_Device\_Table = ( (B/IPv6 address of FD2, 0, 20-execution time) )
 WAIT (30 seconds)
 VERIFY NP, BBMD Foreign Device Table = ()

## 12.X.5.4 Delete-Foreign-Device-Table-Entry For A Non-existent Entry

Purpose: To verify that the IUT will handle a Delete-Foreign-Device-Table-Entry message when a non-existent FDT entry is supplied.

Test Concept: The IUT starts with a Foreign Device Table without a entry for FD1. The TD, acting as FD1, attempts to delete its entry from the IUT's Foreign Device Table. It is verified that the IUT returns a NAK to the request.

Configuration Requirements: The IUT's Foreign Device Table does not contain an entry for FD1.

Test Steps:

```
    VERIFY NP, BBMD_Foreign_Device_Table = (FDT1: a list of entries without an entry for FD1)
    TRANSMIT

            DA = IUT,
            SA = FD1,
            Source-Virtual-Address = FD1,
            Delete-Foreign-Device-Table-Entry,
            'FDT Entry' = FD1

    RECEIVE

            DA = FD1,
            Source-Virtual-Address = IUT
            SVLC-Result,
            'Result Code' = Delete-Foreign-Device-Table-Entry NAK

    VERIFY NP, BBMD_Foreign_Device_Table = FDT1
```

[Network Port Object Tests] [In BTL Specified Tests, add test into 14.3] [All other 14.3 Write-BDT tests need to have a conditionality added to them based on the IUT's Protocol\_Revision being less than 17]

### 14.3 Broadcast Distribution Table Operations

### 14.3.X1 Write-BDT service is required to return Write-BDT-NAK

Reason for Change: Clause J.4.4.2 mandates a change and that all devices claiming Protocol\_Revision >= 17, shall behave in this changed way.

Purpose: To verify that any IUT with Protocol\_Revision claimed as 17 or higher, will return Write-Broadcast-Distribution-Table NAK to every Write-Broadcast-Distribution-Table request.

Configuration Requirements: If the Protocol\_Revision claimed is less than 17, this test shall be skipped.

Test Steps:

- 1. TRANSMIT Write-Broadcast-Distribution-Table
- 2. RECEIVE BVLC-Result,
  - 'Result Code' = Write-Broadcast-Distribution-Table NAK

[Network Port Object Tests] [In BTL Specified Tests, add test into 14.3]

### 14.3.X2 Broadcast Distribution Table Holds at Least 5 Entries (via Write-Broadcast-Distribution-Table)

Reason For Change: NM-BBMDC-B specifically mandates this capacity behavior is supported by the product.

Purpose: Verify that IUT implements capacity mandated for the product by NM-BBMDC-B.

Test Concept: Verify that the Broadcast\_Distribution\_Table can hold at least five distinct peer BBMDs entries (in addition to the entry containing the address of itself in the table) using Write-Broadcast-Distribution-Table.

Configuration Requirements: the IUT is configured to operate as a BBMD.

Test Steps:

- 1. MAKE (IUT enter mode functioning as a BBMD implementation)
- 2. TRANSMIT Write-Broadcast-Distribution-Table
- 'List of BDT Entries' = (its own entry and entries for at least 5 other BBMDs)
- 3. RECEIVE Write-Broadcast-Distribution-Table-Ack,
- 3. TRANSMIT Read-Broadcast-Distribution-Table
- 4. RECEIVE Read-Broadcast-Distribution-Table-Ack,

'List of BDT Entries' = (the table as configured, in any order)

## 14.3.X3 Broadcast Distribution Table Holds at Least 5 Entries (via BBMD\_Broadcast\_Distribution\_Table)

Reason For Change: NM-BBMDC-B specifically mandates this capacity behavior is supported by the product.

Purpose: Verify that the IUT supports at least 5 peer BBMD entries in its broadcast distribution table.

Test Concept: Verify that the Broadcast\_Distribution\_Table in the BBMD's Network Port object, NP, can hold at least five distinct peer BBMDs entries (in addition to the entry containing the address of itself in the table) by writing to the BBM\_Broadcast\_Distribution\_Table property.

Configuration Requirements: The IUT is configured to operate as a BBMD.

Test Steps:

- 1. WRITE NP, BBMD\_Broadcast\_Distribution\_Table = (its own entry and entries for at least 5 other BBMDs)
- 2. TRANSMIT ReinitializeDevice-Request
  - 'Reinitialized State of Device' = WARMSTART | ACTIVATE\_CHANGES 'Password' = (any valid password)
- 3. RECEIVE BACnet-SimpleACK-PDU
- 4. WAIT Activate Change Fail Time
- 5. TRANSMIT Read- Broadcast-Distribution-Table
- 6. RECEIVE Read-Broadcast-Distribution-Table-Ack, 'List of BDT Entries' = (the table as configured, in any order)

[Network Port Object Tests] [In BTL Specified Tests, add test into 14.6]

### 14.6 Foreign Device Management

### 14.6.X1 Holds at Least 5 Foreign Device Registrations

Reason For Change: NM-BBMDC-B specifically mandates this capacity behavior is supported by BBMDs.

Purpose: Verify that when configured to accept foreign device registrations, the IUT supports at least five simultaneous foreign device registrations.

Test Concept: The IUT is configured to support foreign device registrations. Five Register-Foreign-Device requests are sent from 5 different devices, to verify that it supports five registrations simultaneously in the FDT.

Configuration Requirements: Set BBMD\_Accept\_FD\_Registrations in the Network Port object representing the port operating as a BBMD to TRUE. The TD will be configured to emulate 5 devices.

Test Steps:

```
1. REPEAT X = 1 to 5 {
    TRANSMIT Register-Foreign-Device
    SOURCE = (device X)
    'Time-to-Live' = (a value longer than the length of the test)
    RECEIVE BVLC-Result,
    'Result Code' = Successful completion
}
```

#### 14.6.X2 Negative Foreign Device Registration when FD\_Supported is FALSE

Reason For Change: The standard specifically mandates that BBMD\_Accept\_FD\_Registrations property is writable if present in BBMDs.

Purpose: Verify that when BBMD\_Accept\_FD\_Registrations is configured as FALSE, the BBMD will accept no more foreign device registrations.

Test Concept: The IUT is configured with BBMD\_Accept\_FD\_Registrations property as FALSE. Then it is verified that no more Register-Foreign-Device registrations succeed, though those already in the FDT operate as normal.

Configuration Requirements: BBMD\_Accept\_FD\_Registrations in the Network Port object representing the port is initially TRUE. If no Network Port object contains the BBMD\_Accept\_FD\_Registrations property, then this test shall be skipped.

Test Steps:

- 1. WRITE BBMD\_Accept\_FD\_Registrations = FALSE
- 2. TRANSMIT Register-Foreign-Device
- 3. RECEIVE BVLC-Result, 'Persult Code' = Persister Foreign I

'Result Code' = Register-Foreign-Device NAK